

ZTF Help

Table of Contents

- [ZTF: Overview](#)
 - ◆ [History and Background](#)
 - ◆ [Terminology](#)
 - ◆ [Adding Tabs](#)
 - ◆ [Appearance](#)
 - ◆ [User Login](#)
 - ◆ [Getting More Help](#)
- [Searching](#)
 - ◆ [Position Search](#)
 - ◆ [Table of Positions](#)
 - ◆ [Field ID Search](#)
 - ◆ [Solar System Object Search](#)
 - ◆ [Results](#)
- [Results](#)
 - ◆ [Terminology](#)
 - ◆ [Layout](#)
 - ◆ [Columns](#)
 - ◆ [Position](#)
 - ◆ [Table of Positions](#)
 - ◆ [FieldID](#)
 - ◆ [Solar System Object](#)
 - ◆ [Downloading Data](#)
- [Visualization](#)
 - ◆ [The FITS/HiPS viewer](#)
 - ◆ [Image Information](#)
 - ◆ [Breaking out of the pane](#)
 - ◆ [Image Navigation](#)
 - ◆ [Image Toolbar](#)
 - ◆ [Color Stretches](#)
 - ◆ [Image Layers](#)
 - ◆ [WCS Alignment](#)
 - ◆ [Extraction Tools](#)
 - ◆ [Region Selection](#)
 - ◆ [Footprints](#)
 - ◆ [HiPS Images: Information](#)
 - ◆ [Coverage Image](#)
 - ◆ [Upper Left HiPS menus](#)
- [Tables](#)
 - ◆ [Table Header](#)
 - ◆ [Table Columns](#)
 - ◆ [Adding Columns](#)
 - ◆ [Table Filters](#)
 - ◆ [Table Actions](#)
 - ◆ [Table Details](#)
 - ◆ [Table Cells](#)
 - ◆ [Saving Tables](#)
 - ◆ [Table Navigation](#)
- [Catalogs](#)
 - ◆ [Introduction](#)
 - ◆ [Catalog Upload](#)

- ◆ [IRSA Catalogs](#)
- ◆ [Interacting with Catalogs](#)
- ◆ [Hierarchical Catalog Display](#)
- ◆ [Details Tab](#)
- [Other Searches](#)
 - ◆ [Introduction](#)
 - ◆ [Interactive Target Refinement](#)
 - ◆ [VO TAP Constraints](#)
 - ◆ [VO ObsCore Constraints](#)
 - ◆ [IRSA VO TAP Search](#)
 - ◆ [Multi-archive VO TAP Search](#)
 - ◆ [NED Objects](#)
 - ◆ [ObsCore Search](#)
- [Plots](#)
 - ◆ [Default Plot](#)
 - ◆ [Plot Format: A First Look](#)
 - ◆ [Plot Navigation](#)
 - ◆ [Plot Linking](#)
 - ◆ [Changing What is Plotted](#)
 - ◆ [Plotting Manipulated Columns](#)
 - ◆ [Restricting What is Plotted](#)
 - ◆ [Overplotting](#)
 - ◆ [Adding Plots](#)
- [Downloads](#)
 - ◆ [Overview](#)
 - ◆ [Download Options](#)
 - ◆ [Job Monitor](#)
 - ◆ [Email](#)
 - ◆ [Scripts](#)
 - ◆ [Job Info](#)
 - ◆ [Contents of Download](#)
 - ◆ [Acknowledgements](#)
- [Program Interface](#)
 - ◆ [Introduction](#)
 - ◆ [Input Parameters](#)
 - ◆ [Input Examples](#)
- [User Registration](#)
- [FAQ](#)
- [Privacy](#)

Zwicky Transient Facility (ZTF) Image Service: Overview




The Zwicky Transient Facility (ZTF) Image Service is the repository for all image data collected by ZTF and processed by IPAC.



Contents of page/chapter:

- +[History and Background](#)
- +[Terminology, Hints, and Tips](#)
- +[Side Menu and Adding to the Tabs Menu](#)
- +[Side Menu and Appearance](#)
- +[User Login Overview](#)
- +[Getting More Help](#)


History and Background

The ZTF Telescope and Camera

The [Zwicky Transient Facility \(ZTF\)](#)  is a synoptic sky survey being carried out on the [48-inch Oschin Schmidt Telescope](#)  at Palomar Observatory, which is the same telescope as used for the well-known [POSS](#)  survey in the 1950s.


Using a reworked version of the same telescope as [PTF and iPTF](#) , ZTF uses a camera with an instantaneous field-of-view of 47 square degrees. This camera enables a full scan of the visible sky every night, and is a direct lead-in to the [Rubin](#)  era.

For More Information

More information on ZTF can be found at [the project home page](#) .

Acknowledgements

The main [ZTF page at IRSA](#)  has all the wording you need, plus the canonical papers to cite.

Different data sets may have different DOIs. This service you are using now, the Zwicky Transient Facility Image Service, has DOI [10.26131/IRSA539](#) .

Note that you can use the \facilities call in AASTeX to acknowledge IRSA as a facility you used in your journal article.

Terminology, Hints, and Tips

Telescope & Data Terminology

The ZTF Image Service contains all image data available from ZTF, subject to the requirement that it has been actually both processed and deposited in the archive (these are separate operations). Image data products are separated into four types:

- Science Exposure

ZTF Help

Single science (as opposed to calibration or reference) image. Some data may be proprietary. If you have proprietary access to these data, you [must log in](#) to be able to download these data.

Reference (coadd) Image

Image derived from combining the Science Exposure single frame data, such as deep sky coadded data and the catalogs derived from such data. The coadded mosaic is sometimes referred to as the "coadded image", or "reference image", or even "Level-2 Coadd". These are created from at least 15 images and are fixed over the ZTF project for a consistent baseline.

Deep Reference Image

Image derived from combining the Science Exposure single frame data, more than the standard reference image. These deep reference images typically contain 100 images and are slowly refreshed on a rolling basis as more observations accumulate.

Difference Image

Image derived from a difference in Science Exposure single frame data.


Catalog data products can be downloaded with the images, or separately from the images, from this interface. The catalogs can be overlaid on the images and interact with it using the tools found here.


There are a lot of data that are public; if you want to access proprietary data, you [must log in](#) to be able to view or download these data.

Tool Terminology

The words in blue rectangles at the top are 'tabs.'



This icon in the upper left  pulls open a "drawer" from the left hand side which enables you to [add or remove tabs](#) from this top level (see [below](#)). Most of these tabs allow [searching](#). The side drawer also can allow you to change the [appearance](#) (dark or light mode) (see [below](#)).

When you have [results](#) loaded into the ZTF Image Service, your browser window is divided into "panes", like "window panes." The contents of the panes depends on what you are doing with the tool, but could include an image pane, at least one table pane, and/or a plot pane. You can expand any of the window panes by clicking on the expand icon: 

Each of the three main kinds of 'panes' in the display has its own toolbox in its upper right corner which operates on things in that pane, and the basic functionality for each of these panes is covered elsewhere in this document:

- ◇ The [Tables section](#) covers (among other things) the tables toolbox



- ◇ The [Plots section](#) covers (among other things) the plots toolbox





- ◇ The [Visualization section](#) covers (among other things) the images toolbox



In the ZTF Image Service, you can search by position or orbital parameters for moving targets, or any of a number of other ZTF-specific searches. [Searching is in its own section.](#)

Side Menu and Adding to the Tabs Menu

This icon  in the upper left pulls open a "drawer" from the left hand side; the top of it looks like this:



The highlighted bar ("Results" in this example) is the tab you have in the foreground on your main window.


You can use this side menu to add (or remove) blue tabs from the top of your ZTF Image Service interface. By default, Results, Search by Position, Search by ZTF Field ID, Search by Solar System Object/Orbit (all searching options) are shown, along with the [Job Monitor](#).


Under "IRSA search tabs," [Catalogs](#) and [VO TAP](#) search IRSA holdings.

Under "External archive search tabs," [NED Objects](#) and [Multi-archive VO TAP](#) (that is, a general TAP search) search other (non-IRSA) archives.

Click on the "Hide Tab" button to remove that corresponding tab.

Side Menu and Appearance

This icon  in the upper left pulls open a "drawer" from the left hand side; the bottom of it looks like this:






This controls the appearance of the tool in your browser -- do you want it to run as light mode, dark mode, or respect whatever preferences you have set on your system? Try out the different modes; you may have a preference!

User Login


In the far upper right, there is a link to log in. The ZTF Image Service can remember you when you return. See the [user registration section](#) for more information.



Getting More Help

The "Help" icon  leads you into this online help. There are also context-sensitive help markers throughout the tools (). You can also download a PDF version of this manual; look at the top left of the help window. (The PDF may be easier to search than the web pages; use your PDF reader's search function.)

You can submit questions to the [IRSA Help Desk](#) .

A set of frequently asked questions (FAQs) about the ZTF Image Service is [here](#).

The [IRSA YouTube channel](#)  has lots of short videos about IRSA tools.

Found a bug? The known bugs and issues in this version of the ZTF Image Service are listed [here](#) . If you think you have found a bug, before reporting it, please check this list, and read this online ZTF Image Service help. It may be a "feature" we already know about. If you have found a new, real bug, then please do contact us via the [IRSA Help Desk](#) . Please include your operating system version and your browser software and version. If you can, please also include any specific error message you may have gotten. (NB: In our testing, copying shortcuts worked on Windows and Linux; the command-C did not always work on Macs, but selecting and clicking the right mouse button often did when command-C did not.)

ZTF Image Service: Searching

This section is an overview of how to search in the ZTF Image Service. There are several different ways to search. In all cases, after entering your search parameters, click on the blue "Search" button to actually launch the search.

Contents of page/chapter:

- +[Position Search](#)
- +[Table of Positions Search](#) (multiple targets)
- +[ZTF Field or CCD ID Search](#)
- +[Solar System Object/Orbit Search](#)
- +[Results](#)

Position Search

Searching the archive is relatively straightforward -- the most common search is a search by position on the sky for a cone search.

Coordinates or Object Name.

By default, it assumes you are searching on a single target. You may enter a target name, and have either NED-then-Simbad or Simbad-then-NED resolve the target name into coordinates. Alternatively, you may enter coordinates directly. These coordinates can be in decimal degrees or in hh:mm:ss dd:mm:ss format, or Jhhmmss+ddmmss format. By default, it assumes you are working in J2000 coordinates; you can also specify galactic, ecliptic, or B1950 coordinates as follows:

- ◇ '46.53, -0.251 gal' means 46.53, -0.251 degrees in galactic coordinates
- ◇ '12.7, +4.3 ecl' means 12.7, +4.3 degrees in ecliptic coordinates
- ◇ '19h17m 11d58m b1950' means 19h17m 11d58m in B1950 coordinates
- ◇ a source name like 'J140320.67+542028.6' is parsed as 14h03m20.67s +54d20m28.6s.

ZTF Help

◇ a source name like 'G102.0360+59.7715' is parsed as 102.0360 +59.7715 in galactic coordinates

Examples are given below the text entry box before you start typing in the box.

As you are completing a valid coordinate entry, the tool echoes back to you what it thinks you are entering. Look right below the box in which you are typing the coordinates to see it dynamically change.

Search Type (Region Intersection).

You can specify exactly which kind of search type (region intersection) you would like, and the subsequent options change accordingly, e.g., :

◇ *Image contains target* (default)

- The next option becomes "Return Image Size (leave blank for full images)" which is 600 arcsec by default.

◇ *Image covers entire search region*

- The next options become "Search Region (Square) Size", and "Return Image Size (leave blank for full images)." Because you are requesting that the images meeting your search criteria cover the entire region you are requesting, if you make the search region large and your image size small, it's likely that you will be left with no images matching your criteria.

◇ *Image is entirely enclosed by the search region*

- The next option becomes "Search Region (Square) Size." Because you are requesting that the images meeting your search criteria are entirely encompassed by your search region, it is very easy to have a search region too small and thus have no results matching your criteria.

◇ *Any pixel in the image overlaps the search region requested*

- The next option becomes "Search Region (Square) Size." It will give you all images that overlap your search region at all.

For some of these options, you can specify the image size you want to retrieve; you can leave it blank to return the full images. You may enter the image size in arcseconds, arcminutes, or degrees; just change the drop-down option accordingly.

Tips and Troubleshooting Pick your units from the drop-down first, and then enter a number; if you enter a number and then select from the drop-down, it will convert your number from the old units to the new units. There are both upper and lower limits to your search radius; the tool will tell you if you request something too big or too small.

Most Centered Image. You can choose to retrieve only the most centered image containing your target, or any image containing your target. It defaults to 'no' so that you get more images by default.

Data Product Level.

You can choose to have any combination of science exposures, reference (coadd) images, deep reference images, and/or difference images returned. (See [here](#) for more about what these images are.)

Tips and Troubleshooting If you want more frames than just the most centered result of your search, be sure to set "Return only the most centered image containing the target" to 'no.' *If you select all the data products, and leave "most centered" as 'yes', then you will get the data product that is most centered per set*, not all the images that went into your light curve, which may not be what you want.

Optional Search Constraints.

Click on the black 'disclosure arrow' to reveal options for additional constraints. You can put in ZTF field ID(s) and CCD ID(s), if desired. To search for more than one at a time, enter a list separated by semicolons (;).

Click on the blue "Search" button to launch the search.

Table of Positions Search (multiple targets)

The position search can also be executed in "batch mode" for a list of objects given in a file - select the Multi-Object tab from the search page.

You can load a file from your local disk or the [IRSA Workspace](#) . The file can be in any of three formats: comma-separated values (CSV), tab-separated values (TSV), or [IPAC table format](#) , which is basically ASCII text with headers explaining the type of data in each column, separated by vertical bars.

For IPAC table file format, the simplest possible input file looks like this example:

```

|          ra |          dec |
|        double |        double |
|          deg |          deg |
266.461876096161 -28.9303475510113
317.385694084404 -41.1537816217576
267.210580557307 -27.7929408211594
229.172700517754  0.2598861324350
299.510225672473 -38.7735055243326
213.945501950887  13.3596597685085
262.341432853080 -23.7518928284717
271.202769466020 -21.7274227022229
291.167629785682 -29.2569222675305
272.336516119634 -20.2761650442889
237.391628608612  2.5906013137112

```

Note: Your uploaded table must have RA and Dec, not just target names.

Tips and Troubleshooting

Please use the [IPAC Table Validator](#) to check and reformat your input table before the table upload. If the table upload search still does not work properly, try the following :

ZTF Help

- No hyphens allowed in column names, or in the filename! (Sometimes this seems to matter, or matter only for some things and not others, and sometimes it doesn't. If you are getting weird behavior, this is one thing to try.)
- Column names should be all in lower case, so "ra" not "RA" or "Ra" or "RA2000", etc., and same for "dec".
- No spaces after the last pipes in the header lines.
- No empty lines at the end of the input file.
- IPAC table files should end in ".tbl".
- Make sure there are not lots of extra whitespace (spaces, tabs, etc.) at the ends of lines, particularly the header lines.
- Check for and remove odd non-standard characters like curly quotes or Greek letters, and other non-printing special characters (like tabs).
- If using the table verification service, name resolution may fail for some targets with Greek letters or other unusual characters -- provide coordinates for the troublesome names, or remove them.

After you have uploaded your list of targets, the rest of the search form looks the same as for the [single position search](#), with all the same choices starting with "Search Type."

ZTF Field or CCD ID Search

The screenshot shows the ZTF search interface. At the top, there is a navigation bar with tabs: "Results", "Search by Position", "Search by ZTF Field ID" (which is selected), "Search by Solar System Object/Orbit", "Job Monitor", and a help icon. Below the navigation bar, the "Search by ZTF Field ID" section is active. It contains two input fields: "ZTF Field ID(s):" and "CCD ID(s):". Below the "CCD ID(s)" field, there is a note: "Valid ccdid range from 1 to 16. Leave blank for all ccdid. Example for multiple CCD ID(s): 7;8;9". Below the input fields, there is a "Data Product Level:" section with four checkboxes: "Science Exposure" (checked), "Reference (Coadd) Image" (checked), "Deep Reference Image" (checked), and "Difference Image" (unchecked). At the bottom left of the form is a blue "Search" button, and at the bottom right is a help icon (a question mark in a circle).

You can search for an individual ZTF Field ID or CCD ID, or a list of those IDs separated by semicolons (;).

You can ask for any combination of data product levels.

Click on the blue "Search" button to launch the search.

Solar System Object/Orbit Search

You can also search by Solar System Object or Orbit; this is one of the default tabs on the top of your screen. There are three basic search options -- object name, MPC input, and manual input.


Your first choice is searching by object name.

ZTF Help



You can search on the name of a moving target (Solar System Object, SSO), or the NAIF ID. The accepted naming conventions are the ones that have been approved for use by the [CSBN](#) and its predecessors. SSOs are assigned NAIF IDs, which are a unique integer identifier for known Solar System bodies. (See [here](#) or [here](#) for more about NAIF and NAIF IDs; in brief, every body in the Solar System has a number.)

If you know the NAIF ID, just type that in; if you know only the name, it will attempt to resolve the name for you into a NAIF ID. You may need to wait a second or two. You may need to carefully read what it is suggesting to make sure you have selected the NAIF ID you really want. For example, Neptune's NAIF ID is different than that for the Neptunian system's barycenter:



Even if only one suggestion is given, you need to explicitly select that suggestion in order to implement the search.

The other two search choices are two different ways of entering orbital parameters.

The standard six orbital elements for asteroids are *eccentricity* (e), *semimajor axis* (a), *mean anomaly* (M), *inclination* (i), *longitude of the ascending node* ("Node"), and *argument of perihelion* (w). For comets, the elements are *eccentricity* (e), *perihelion distance* (q), *time of perihelion passage* (T_p), *inclination* (i), *longitude of the ascending node* ("Node"), and *argument of perihelion* (w). Notice that for comets, *perihelion distance* is used instead of *semimajor axis* and *time of perihelion passage* is used instead of *mean anomaly*. The reason for replacing these two parameters is to allow for cases where long period comets have a parabolic or hyperbolic orbit. Other parameters you may see include mean motion (n), absolute magnitude (H), and slope parameter (G). A good description of the orbital parameters is given in JPL's [Solar System Dynamics website](#).

ZTF Help

The middle search tab option is "MPC Input". MPC is [Minor Planet Center](#). You should first select, under "Object Type" whether your object is an asteroid or comet, then enter the MPC 1-line input in the blank provided.

Here is an example one-line input for an asteroid that you can try:

01915 18.97 0.10 K145N 81.26155 347.82179 162.96410 20.39795 0.5705064 0.24279518 2.5447356 1 MPO143010

And an example comet:

CJ950010 1997 03 29.3330 0.939095 0.994914 130.8792 282.4988 89.3793 20160524 -2.0 4

The last search tab option is "Manual Input". From this screen, you specify if your object is an asteroid or comet, and enter all the relevant ephemeris parameters individually, as opposed to as the MPC 1-line input.

The properly-formatted MPC input string can be cut-and-pasted directly from a table of orbital elements in [MPC Format](#). There are a number of orbital element tables available at the MPC website, for example, [observable NEO](#) and [observable comets](#). The complete list of minor planets can be found at the [MPC Orbit \(MPCORB\) Database](#). Information on the format of the element tables is given by following sites: [minor planet format](#) and [comet format](#).

MPC Element Input Examples (definitions: e=eccentricity, a=semimajor axis, M=mean anomaly, i=inclination, Node=longitude of the ascending node, w=argument of perihelion, q=perihelion distance, Tp=time of perihelion passage, n=mean motion, H=absolute magnitude, and G=slope parameter):

ZTF Help

Asteroid: Icarus:

| Designation | H | G | Epoch | M | w | Node | i | e | n | a |
|-------------|------|------|-------|----------|----------|----------|----------|-----------|------------|-----------|
| 01566 | 16.9 | 0.15 | K1128 | 78.13687 | 31.35339 | 88.02734 | 22.82772 | 0.8268277 | 0.88069351 | 1.0779191 |

Comet: C/2010 A4 (Siding Spring):

| Name/Desig | Tp | q | e | w | Node | i | Epoch | H | G | Name |
|------------|----------------------|----------|----------|----------|----------|---------|----------|------|-----|------------------------------------|
| CK10A040 | 2010 10 8.7896 | 2.738033 | 0.990439 | 271.6989 | 346.6856 | 96.7301 | 20110208 | 12.5 | 4.0 | C/2010 A4 (Siding Spring) |

After specifying all of that, then you need to specify the date range over which to search. **Note that**, if you leave the date range blank, you will search over the whole ZTF archive, which can take a long time.

Then, the rest of the search form largely looks the same as for the [single position search](#), with all the same choices starting with "Search Type."

Overlay catalog: An additional option you have from this search form is to search the single exposure catalogs at the same time as you are searching for images. If you tick "yes" for "overlay catalog," then it will search the catalog and overlay the catalog on the corresponding images.

Tips and Troubleshooting

- It will take a second or two to turn the name into a NAIF ID. You can't search without a NAIF ID, so please just try to be patient and pick the NAIF ID from the list, even if it just gives you one option.
- Longer time baselines take longer to complete. Don't just cavalierly leave those date ranges blank unless you need to take a trip down the hall for coffee or something.
- More non-Newtonian forces mean an ephemeris loses more accuracy with time. If you copy a current comet ephemeris to try to search for it in 3-year-old (or older!) data, you might not find your comet!
- Moving target search results can include data that are not public. If you do not have access to the proprietary data, you will not be able to view or download those files. If you do have access to those data, you will need to [log in](#) to view or download those files.

Results

Results are described in detail in [another section](#).

The [Visualization section](#) has much more information about interacting with images.

The [Tables section](#) has much more information about interacting with tables in general. The [Catalogs section](#) has much more information about searching for IRSA catalogs. You can do [many other searches as well](#).

When you load a table, you get an x-y plot displayed as well. See the [Plots section](#) for lots more information.

ZTF Image Service: Search Results

Results of a search in the ZTF Archive appear in two different window panes, each of which could have several tabs.

Contents of page/chapter:

- +[Terminology](#)
- +[General Layout Information](#)
- +[Columns in Results](#)
- +[Position Results](#)
- +[Table of Positions Results](#) (multiple targets)
- +[Field or CCD ID Results](#)
- +[Solar System Object/Orbit Results](#)
- +[Downloading Data](#)

Terminology

Panes

The search results appear in two "panes" (like "window panes"). You can grab and drag the division between the two panes to change their relative sizes. The left is usually tables of search results and the right is usually images (or lists of images, or stuff about images, or plots).

Tips and Troubleshooting

- Note that each new [search](#) overwrites the results in the results tab -- that is, a second search doesn't *add* to the results tab; it *replaces* the contents of the results tab. This is different than some other IRSA tools.
- See [here](#) for more about the different kinds of observation products you could have searched on.

General Layout Information

The left pane of the search results contains lists of observations that met your criteria. The right pane of the search results contains more details of the observations. The right pane changes depending on what row you have selected (clicked on) in the left pane.

Left pane

In general, the left pane has between one and four tabs, depending on what you selected on the [search screen](#): "Science Exposure", "Reference (Coadd) Image", "Deep Reference Image", and/or "Difference Image."

For Solar System Object searches (a moving object), there will be two tabs, one that is a list of images, and the other of which is "Orbital Path" a list of positions calculated for the object as a function of time.

If you load a catalog into the tool, it also appears on the left.

ZTF Help

Each tab is its own table, which behaves in the same way that tables throughout IRSA tools with this look and feel. See the [Tables](#) section for more details, but in summary you can change the width of the columns, sort by columns, filter by column values, etc.

The corresponding data can be downloaded by checking the box at the start of each row (or the box at the top of the column of boxes to select all) and clicking "Prepare download". (See the section on [downloads](#) for more information.)

Right pane

The right pane of the search results contains four tabs that enable exploration of the data returned by your search. Click on a row in the left pane and the contents of the right pane change.

Data tab

The "Data" tab displays the FITS file corresponding to the row you have selected on the left. You can interact with this FITS file using the [visualization tools](#).

Coverage tab

The "Coverage" tab shows footprints of all the returned observations, not just those from the foreground tab on the left. The currently selected observation is highlighted a different color than the ensemble of observations. If you select a different row in the table, a different polygon is highlighted in the image, and vice versa. Because this is likely a large region of sky, the coverage image is a HiPS image; see the [visualization section](#).

Chart tab

The "Chart" tab plots values from the table of results. By default, it grabs what it thinks is the best possible position to represent the images it has retrieved. For inertial target searches (e.g., not moving targets), this is crval1 and crval2 (which are, by default, hidden columns in the results table); this is the reference position at crpix1 and 2 for the image. For moving targets, it plots the ra and dec of the object. You can change what is plotted, please see the [plots section](#).

Details

The "Details" tab is a table of metadata about the corresponding row you have selected in the table on the left hand side.

Tips and Troubleshooting

- If you set "Return only the most centered image containing the target" to "yes", you will only get one image set per tab, because that's what you asked it to do. Set "Return only the most centered image containing the target" to "no" to get all the images from your light curve.
- There are a lot of columns returned, some of which are hidden. Go to the gears at the top of the table to hide or show more columns; see below for a list of the columns. More information can be found in the [Tables chapter](#).

About Images

Interacting with images is covered in the [visualization section](#); there are many sophisticated capabilities available.

Tips and Troubleshooting: Note that North is not necessarily up and East is not necessarily left in these images. There's a flip as well as a rotation.

About Tables

Interacting with images is covered in the [tables section](#). You can manipulate columns and create new columns.

About Plots (or Charts)

Interacting with plots (sometimes called charts) is covered in the [plots section](#). You can make some sophisticated plots.

About Catalogs

If you load a [catalog](#) into the tool, you will create a table and a plot and overlay the catalog on the images. If it is a large catalog, the catalog may be shown as hierarchical cells; [see here](#) for more information.

Columns in Results

When you do a search for images, a table is returned with information about the images (image metadata) meeting your search criteria that allows you to decide which images you want to download.

Columns that are returned for a science exposure image search include the following:

| column_name | description | units |
|-------------|---|---------|
| infobits | Info bit flags | |
| field | ZTF field number | |
| ccdid | CCD number (1..16) | |
| qid | Quadrant ID (1..4) | |
| rcid | Readout-channel ID (0..63) | |
| fid | Filter ID | |
| filtercode | Filter code (abbreviated name) | |
| pid | Science product ID | |
| nid | Day/night ID | |
| expid | Exposure ID | |
| itid | Image type ID | |
| imgtype | Image type name | |
| imgtypecode | Single letter image type code | |
| filefracday | Integer (YYYYMMDDddddd) used in product file names | |
| obsdate | Observation UT date/time | |
| obsjd | Observation Julian day | d |
| seeing | Seeing FWHM | arcsec |
| airmass | Telescope airmass | |
| moonillf | Moon illuminated fraction | |
| moonesb | Moon excess in sky brightness | |
| maglimit | Magnitude limit | mag |
| crpix1 | Reference pixel value for axis 1 | pix |
| crpix2 | Reference pixel value for axis 2 | pix |
| crval1 | Reference position right ascension at crpix1,crpix2 | deg |
| crval2 | Reference position declination at crpix1,crpix2 | deg |
| cd11 | CD matrix element 1,1 | deg/pix |
| cd12 | CD matrix element 1,2 | deg/pix |

| column_name | description | units |
|---------------|--|---------|
| cd21 | CD matrix element 2,1 | deg/pix |
| cd22 | CD matrix element 2,2 | deg/pix |
| ra | Right ascension of image center | deg |
| dec | Declination of image center | deg |
| ra1 | Right ascension of first image corner | deg |
| dec1 | Declination of first image corner | deg |
| ra2 | Right ascension of second image corner | deg |
| dec2 | Declination of second image corner | deg |
| ra3 | Right ascension of third image corner | deg |
| dec3 | Declination of third image corner | deg |
| ra4 | Right ascension of fourth image corner | deg |
| dec4 | Declination of fourth image corner | deg |
| ipac_pub_date | UT date/time of raw product release | |
| ipac_gid | IPAC Group ID | |
| meta_id | Metadata record ID | |
| poly | Bounding polygon | |

Position Results

This is the result of a simple, single position search, for all image data products, where the "most centered image" is set to "no." A list of the images (with four tabs) is on the left, and the data appear in the "Data" tab on the right. There are four tabs of image results on the left because I asked for all four image data products. By default, one image at a time is shown on the right; see the [visualization section](#) for much more about images.

ZTF Help

Science Exposu...
Reference Imag...
Deep Reference...
Difference Imag...

Data
Coverage
Chart
Details

Prepare Download
1 of 29
(1 - 100 of 2,829)

| | ra (deg) double | dec (deg) double | infobits int | field int | ccdid int | qid int | rcid int | fid int | filtercod char |
|--------------------------|-----------------------|------------------------|-----------------|--------------|--------------|------------|-------------|------------|-------------------|
| <input type="checkbox"/> | 211.07174223 | 54.42383481 | 33554432 | 792 | 7 | 2 | 25 | 2 | zr |
| <input type="checkbox"/> | 211.07264635 | 54.42409674 | 0 | 792 | 7 | 2 | 25 | 2 | zr |
| <input type="checkbox"/> | 211.07642111 | 54.42337273 | 67108864 | 792 | 7 | 2 | 25 | 2 | zr |
| <input type="checkbox"/> | 211.06985239 | 54.41404272 | 100663296 | 792 | 7 | 2 | 25 | 2 | zr |
| <input type="checkbox"/> | 211.06815842 | 54.41188301 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07150871 | 54.41345710 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07026088 | 54.41452226 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07315935 | 54.41478510 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.06917984 | 54.41586818 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07075277 | 54.41562023 | 67108864 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07385173 | 54.41568978 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07589155 | 54.41544341 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.06926384 | 54.41442731 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.06981657 | 54.41483942 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07245117 | 54.41418872 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07384699 | 54.41488964 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07529273 | 54.41713195 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.07640940 | 54.41608747 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.08901498 | 54.41285040 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.08985457 | 54.41482535 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.09093715 | 54.41369932 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.09097946 | 54.41388277 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.09225625 | 54.41415413 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.09380334 | 54.41483998 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.09514828 | 54.41505349 | 67108864 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.09736155 | 54.41356595 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.08716388 | 54.40710317 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 210.26960918 | 54.63042421 | 0 | 1794 | 14 | 1 | 52 | 1 | zg |
| <input type="checkbox"/> | 211.08785427 | 54.40860449 | 0 | 792 | 7 | 2 | 25 | 1 | zg |
| <input type="checkbox"/> | 211.08991872 | 54.40817255 | 0 | 792 | 7 | 2 | 25 | 1 | zg |

ZTF-sci-20180321369965-zr size: 600.0(arc... FOV:7.8'

EQ-J2000: Value:

Table of Positions Results

When you upload a list of targets, you get results that look something like this. Here, the search was made for all image data products, where the "most centered image" is set to "no." A list of the images is on the left, and the data appear in the "Data" tab on the right. Because a list of targets was submitted, an additional column appears in the search results "in_objname", which is the column "objname" from the uploaded data table. The table of results is initially sorted by observation date, as opposed to input target order, or RA order, or filter; you can manipulate this table like [any other table in this tool](#).

Science Exposure
Reference Image
Deep Reference Im...
Difference Image

Data
Coverage
Chart
Details

Prepare Download
1 of 16
(1 - 100 of 1,534)

| | in_objname char | ra (deg) double | dec (deg) double | infobits int | field int | ccdid int | qid int | rcid int |
|--------------------------|--------------------|-----------------------|------------------------|-----------------|--------------|--------------|------------|-------------|
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41432330 | 58.19964595 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41577862 | 58.20405394 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41568119 | 58.20452290 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41624970 | 58.20972502 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.42073147 | 58.22090854 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.42165241 | 58.23727182 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41173398 | 58.16844119 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41196299 | 58.17433915 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41368141 | 58.18317414 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41440267 | 58.18974257 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41529653 | 58.18632069 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41501709 | 58.19003863 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41269331 | 58.18500199 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41299585 | 58.18744640 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41105042 | 58.15125920 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41079054 | 58.15538769 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | HD787 | 3.03804348 | -17.57090845 | 0 | 294 | 6 | 1 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41265538 | 58.16499003 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41307977 | 58.16614173 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41441093 | 58.17900632 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41391789 | 58.19740280 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41357643 | 58.20018612 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | HD787 | 3.03641518 | -17.54625888 | 0 | 294 | 6 | 1 | |
| <input type="checkbox"/> | HD787 | 3.03621648 | -17.58115966 | 0 | 294 | 6 | 1 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.40937823 | 58.16640554 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41081698 | 58.16864328 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | HD787 | 3.03664389 | -17.57892222 | 0 | 294 | 6 | 1 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41114374 | 58.16676900 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | Tyc3663-01966-1 | 11.41194831 | 58.17320084 | 0 | 773 | 13 | 2 | |
| <input type="checkbox"/> | HD787 | 3.03617971 | -17.55301238 | 0 | 294 | 6 | 1 | |

ZTF-sci-20180519468472-zr size: 600.0(arc... FOV:7.4'

Field or CCD ID Results

This is the result of a Field or CCD ID search. The left hand side is a list of all the data matching the search request, and the data appear in the "Data" tab on the right. If you choose the 'coverage' tab, it will show you the location of the requested Field IDs (and/or CCD IDs).

The screenshot shows the ZTF Image Service interface. On the left, there is a table of search results. The table has the following columns: **ra (deg) double**, **dec (deg) double**, **infobits int**, **field int**, **ccdid int**, **qid int**, **rcid int**, **fid int**, and **filtercode char**. The table contains 30 rows of data. The first row is highlighted in orange. The right pane shows a 'Data' tab with a grayscale image of a field of stars. The image is labeled 'ZTF-sci-20180320304317-zr FOV:51'.

| ra (deg) double | dec (deg) double | infobits int | field int | ccdid int | qid int | rcid int | fid int | filtercode char |
|-----------------|------------------|--------------|-----------|-----------|---------|----------|---------|-----------------|
| 218.67908440 | 52.47887250 | 0 | 792 | 1 | 1 | 0 | 2 zr | |
| 217.26154089 | 52.53821751 | 0 | 792 | 1 | 2 | 1 | 2 zr | |
| 217.17962843 | 51.67331388 | 0 | 792 | 1 | 3 | 2 | 2 zr | |
| 218.56997653 | 51.61522722 | 0 | 792 | 1 | 4 | 3 | 2 zr | |
| 218.93646367 | 54.38580169 | 0 | 792 | 5 | 1 | 16 | 2 zr | |
| 217.45357025 | 54.44684058 | 0 | 792 | 5 | 2 | 17 | 2 zr | |
| 217.36598396 | 53.58185964 | 0 | 792 | 5 | 3 | 18 | 2 zr | |
| 218.81851884 | 53.52216535 | 0 | 792 | 5 | 4 | 19 | 2 zr | |
| 219.21596544 | 56.29071151 | 0 | 792 | 9 | 1 | 32 | 2 zr | |
| 219.08559148 | 55.42740676 | 0 | 792 | 9 | 4 | 35 | 2 zr | |
| 219.53236973 | 58.19698828 | 0 | 792 | 13 | 1 | 48 | 2 zr | |
| 219.38513338 | 57.33425584 | 0 | 792 | 13 | 4 | 51 | 2 zr | |
| 218.68221505 | 52.48104853 | 0 | 792 | 1 | 1 | 0 | 2 zr | |
| 218.573333818 | 51.61736187 | 0 | 792 | 1 | 4 | 3 | 2 zr | |
| 218.93898260 | 54.38796163 | 0 | 792 | 5 | 1 | 16 | 2 zr | |
| 218.82132350 | 53.52433158 | 0 | 792 | 5 | 4 | 19 | 2 zr | |
| 219.53356696 | 58.19918865 | 0 | 792 | 13 | 1 | 48 | 2 zr | |
| 219.38665254 | 57.33642381 | 0 | 792 | 13 | 4 | 51 | 2 zr | |
| 218.68203023 | 52.48246126 | 0 | 792 | 1 | 1 | 0 | 2 zr | |
| 218.57307586 | 51.61880361 | 0 | 792 | 1 | 4 | 3 | 2 zr | |
| 218.67264248 | 52.40472260 | 0 | 792 | 1 | 1 | 0 | 2 zr | |
| 217.25772514 | 52.46373913 | 0 | 792 | 1 | 2 | 1 | 2 zr | |
| 217.17650112 | 51.59882511 | 0 | 792 | 1 | 3 | 2 | 2 zr | |
| 218.56435037 | 51.54106056 | 0 | 792 | 1 | 4 | 3 | 2 zr | |
| 215.63205074 | 52.50365366 | 0 | 792 | 2 | 1 | 4 | 2 zr | |
| 214.21150289 | 52.52376612 | 0 | 792 | 2 | 2 | 5 | 2 zr | |
| 214.19283712 | 51.65734434 | 0 | 792 | 2 | 3 | 6 | 2 zr | |
| 215.58593861 | 51.63763938 | 0 | 792 | 2 | 4 | 7 | 2 zr | |
| 212.58980289 | 52.52602319 | 0 | 792 | 3 | 1 | 8 | 2 zr | |
| 211.16895830 | 52.51058428 | 0 | 792 | 3 | 2 | 9 | 2 zr | |

Solar System Object/Orbit Results

This is the result of a search on Pallas. The left hand side is a list of individual exposures that the tool calculated should include Pallas, and a list of calculated positions for Pallas. Note that the right hand side is showing all of the exposures, 12 at a time, and you can page through the list given the navigation tools at the top of the window pane. Unlike searching for targets that don't move, these search results do not default to showing you one image at a time; it is showing you 12 exposures at a time. (You can still view one image at a time; see the [visualization section](#) for much more about images.)

ZTF Help

Pallas;20000002 Orbital Path Data Coverage Chart Details



Prepare Download |< < 1 of 15 >> | (1 - 100 of 1,489) [Icons]

| | ra_obj | dec_obj | sun_dist | geo_dist | dist_ctr | phase | vmag | match | (c fl) |
|--------------------------|------------|-----------|----------|----------|----------|---------|--------|---------|--------|
| | double | double | double | double | double | double | double | integer | |
| <input type="checkbox"/> | 184.254732 | -6.194754 | 2.2388 | 2.7143 | 0.4657 | 20.2329 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.271502 | -6.196387 | 2.2388 | 2.714 | 0.4562 | 20.2387 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.271697 | -6.196406 | 2.2388 | 2.714 | 0.4236 | 20.2388 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.273609 | -6.196592 | 2.2388 | 2.7139 | 0.4549 | 20.2395 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.273803 | -6.196611 | 2.2388 | 2.7139 | 0.424 | 20.2395 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.275715 | -6.196797 | 2.2389 | 2.7139 | 0.4542 | 20.2402 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.275909 | -6.196816 | 2.2389 | 2.7139 | 0.4246 | 20.2402 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.277821 | -6.197002 | 2.2389 | 2.7138 | 0.4531 | 20.2409 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.27802 | -6.197022 | 2.2389 | 2.7138 | 0.425 | 20.241 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.705206 | -6.237134 | 2.2405 | 2.7053 | 0.291 | 20.3898 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.705404 | -6.237152 | 2.2405 | 2.7053 | 0.3313 | 20.3898 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.707265 | -6.237327 | 2.2405 | 2.7053 | 0.292 | 20.3905 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.707463 | -6.237345 | 2.2405 | 2.7053 | 0.3296 | 20.3905 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.709329 | -6.23752 | 2.2405 | 2.7052 | 0.2931 | 20.3912 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.709522 | -6.237538 | 2.2405 | 2.7052 | 0.3283 | 20.3912 | 9.25 | 1 | |
| <input type="checkbox"/> | 184.711392 | -6.237713 | 2.2405 | 2.7052 | 0.294 | 20.3919 | 9.25 | 1 | |
| <input type="checkbox"/> | 187.267601 | -6.443769 | 2.2504 | 2.6518 | 0.1176 | 21.2602 | 9.25 | 1 | |
| <input type="checkbox"/> | 195.332323 | -6.578727 | 2.286 | 2.4534 | 0.0696 | 23.6248 | 9.2 | 1 | |
| <input type="checkbox"/> | 196.45263 | -6.51209 | 2.2916 | 2.4219 | 0.1768 | 23.8861 | 9.19 | 1 | |
| <input type="checkbox"/> | 197.567284 | -6.418261 | 2.2974 | 2.3894 | 0.4355 | 24.1234 | 9.18 | 1 | |
| <input type="checkbox"/> | 197.940623 | -6.380166 | 2.2993 | 2.3783 | 0.4281 | 24.1974 | 9.17 | 1 | |
| <input type="checkbox"/> | 197.940789 | -6.380148 | 2.2993 | 2.3783 | 0.3944 | 24.1974 | 9.17 | 1 | |
| <input type="checkbox"/> | 197.943279 | -6.379881 | 2.2993 | 2.3782 | 0.2534 | 24.1979 | 9.17 | 1 | |
| <input type="checkbox"/> | 199.378412 | -6.198879 | 2.3071 | 2.3342 | 0.385 | 24.4534 | 9.15 | 1 | |
| <input type="checkbox"/> | 199.397876 | -6.195992 | 2.3072 | 2.3336 | 0.4918 | 24.4564 | 9.15 | 1 | |
| <input type="checkbox"/> | 201.763768 | -5.755426 | 2.321 | 2.2562 | 0.1945 | 24.7568 | 9.1 | 1 | |
| <input type="checkbox"/> | 201.773441 | -5.753179 | 2.321 | 2.2558 | 0.1959 | 24.7576 | 9.1 | 1 | |
| <input type="checkbox"/> | 203.064497 | -5.420311 | 2.3291 | 2.2107 | 0.3683 | 24.8411 | 9.06 | 1 | |
| <input type="checkbox"/> | 203.996428 | -5.130041 | 2.3353 | 2.1767 | 0.0857 | 24.8573 | 9.04 | 1 | |
| <input type="checkbox"/> | 206.285835 | -4.188346 | 2.3518 | 2.0872 | 0.3885 | 24.6945 | 8.95 | 1 | |

Downloading Data

Downloading is covered in [separate section](#).

ZTF Image Service: Visualization

In your search [results](#), the images meeting your search criteria are listed on the left, and shown on the right. Clicking on different rows on the left changes what is shown on the right. The colored circle-with-crosshairs (a reticle) that is overlaid by default on your images is the search position you submitted (for position searches). The coverage image puts all of your search results in context with each other. You can add and overlay catalogs and add other layers to your image. (See [the catalogs section](#) for more on catalogs.) The ZTF images as shown are [FITS \(Flexible image transport system\)](#)  and the images used for the coverage image [HiPS \(hierarchical progressive surveys\)](#)  format.

All of the interactive image visualization tools work the same basic way, and here we describe these basic options, in roughly the order in which you might encounter them in the window.

Contents of page/chapter:

- +[FITS/HiPS Viewer](#)
- +[Image Information](#)
- +[Breaking Out of the Pane \(and Going Back\)](#)
- +[Image Navigation](#)
- +[Image Toolbar](#)
- +[Color Stretches](#)
- +[Image Layers: Viewing/Changing the Layers on the Image](#)
- +[World Coordinate System \(WCS\) Alignment](#)
- +[Extraction Tools](#)
- +[Region Selection](#)
- +[Footprints](#)
- +[HiPS Images: General Information](#)
- +[Coverage Image](#)
- +[Upper Left HiPS menus](#)

FITS/HiPS Image Viewer

You can interactively explore the images with the mouse. Move your mouse over any image that is loaded into the viewer. Details about the image, specifically, the pixel beneath your mouse cursor, appear along the bottom left of the image window. Some information is updated in real time (coordinates); some information (pixel value) is updated when you stop moving your mouse for a second or two. The image can be interactively investigated in this fashion.



EQ-J2000: 14h03m13.92s, +54d20m44.9s Flux: 1.115584 MJy/sr

You can change the units of what is being read out, in terms of coordinates or pixel values.

If you click on the label of the coordinates, "EQ-J2000" in the screenshot example above, you get this pop-up, from which you can choose the coordinates from among:

- Equatorial (RA/Dec) J2000 in hh:mm:ss ddd:mm:ss format

Choose readout coordinates ✕

Readout Options:

- ☒ Equatorial J2000 HMS
- ☐ Equatorial J2000 Decimal
- ☐ Equatorial B1950 HMS
- ☐ Equatorial B1950 Decimal
- ☐ Galactic
- ☐ Super Galactic
- ☐ Ecliptic J2000
- ☐ Ecliptic B1950
- ☐ FITS Image Pixel
- ☐ Zero based Image Pixel

Copy Options:

- ☒ Readout values verbatim
- ☐ [Python] AstroPy SkyCoord

Close ?

- Equatorial (RA/Dec) J2000 in decimal degrees
- Galactic in decimal degrees
- Equatorial B1950
- Ecliptic J2000
- Ecliptic B1950
- FITS Image Pixel
- Zero-based Image Pixel

If you click on the "click lock" toggle, the coordinates stop dynamically updating when you move your mouse, and they update only when you click on the image. When you do that, little clip boards appear next to each coordinate readout; clicking on those copy the position to your clipboard. From this pop-up window here as shown, you can control the format of the coordinates that are copied to your clipboard -- they can be as shown in the readout, or in the format that Python is expecting (for easy pasting into code).

Choose pixel readout radix ✕

Integer data readout radix:

- ☒ Decimal
- ☐ Hexadecimal

Floating Point data readout radix:

- ☒ Decimal
- ☐ Hexadecimal

Choosing hexadecimal display will suppress all application of rescaling corrections (i.e. BZERO and BSCALE).

Hexadecimal will show the raw number in the file.


Close ?


If you have a FITS image loaded, you have an additional readout. Click on the label of the readout, "Flux" in the tiny snippet of a screenshot example above, and you get this pop-up, from which you can choose the pixel readout from among:

- Integer data readout in decimal
- Integer data readout in hexadecimal
- Floating point data readout in decimal
- Floating point data readout in hexadecimal

If you choose the hexadecimal options, it will suppress all rescaling

corrections found in the header, like BZERO or BSCALE. It will just show you the raw binary number in the file. (For example, if the value in decimals is 5.13795757, the binary value in the file is 0x40a46a26; [here](#) ↗ is a conversion tool between decimal and hex.)

In the lower left of the images, if you click on this: , you get this pop-up. If you have a FITS image loaded, at the top of this pop-up, it shows the whole image; the orientation of the image is given with a compass rose. There is also a zoom-in of the image at the location under your cursor. Underneath that in the pop-up, whether you have a FITS or HiPS image loaded, you can get a readout of the pixel size, a readout of location on the image in two different coordinate systems, and a readout of the pixel value. You can change the units of those values by clicking on the name of the field: "Pixel Size", "EQ-J2000", "Image Pixel", and "Value". Each results in a pop-up, as above.



You can make the cursor 'stick' on a particular place on the image -- flip the "Click Lock: off" switch to "on" (either in the pop-up or in the lower right of the image window), and then click on the image at your desired location. When this is clicked, small "clipboards" appear near the position readout. Click on that icon to copy that position to your clipboard.

EQ-J2000:  14h03m12.63s, +54d20m59.6s Flux: 4.655877 MJy/sr

Image Information


The upper left corner of the loaded image has a label that tells you basic things about the image you are viewing. The telescope and/or instrument and/or channel and/or data release is first, in black. The field of view follows, in a paler font; this corresponds to the (horizontal) width of the image window. The currently selected image is outlined in brown; other images are outlined in grey.

ZTF-sci-20180325307801-zg size: 600.0(arc... FOV:10' ZTF-sci-20180321369965-zr size: 600.0(arc... FOV:1.7'

Here are two examples of image labels. The former is a ZTF g-band image, and the field of view shown in the tool at the time this screenshot was taken is 10.0 arcmin. The latter is a ZTF r-band image, and the field of view is 1.7 arcmin.

For HiPS images, the FOV is the angular size of the width of the HiPS viewer. Even if the image as displayed is smaller than the window, the FOV readout is the width of the window, not the image. If you shrink your browser screen, the FOV can get smaller because the viewer gets smaller. If you load more than one image, the FOV can get smaller because two viewers must fit in the same pane. As a result, the HiPS FOV requested in the search panel is approximate.


For FITS images, the FOV label on FITS images works analogously to the FOV label on HiPS images. If you zoom out, the FOV will increase even when the FITS image is entirely within the viewer. That's because the FOV is what the viewer can show you based on the pixel size. If you drag the image so that it is only partially seen through the viewer, the FOV will not change. For FITS images, the cutout size is not the same as the FOV.




The target on which you searched is overlaid on the main image with a cross-hair marker, sometimes called a "reticle." You can remove this (or change its color) from the layers pop-up, described below.

Breaking Out of the Pane (and Going Back)

Panes: The search results screen is broken up into panes - the left is a list of items (images or sources for loaded catalogs), and the right is images. If you have more than one image loaded in, the image pane is further subdivided.

Make it big! For some purposes, it is useful to individually view just the table, or the images, or the plots, as large as possible. In any pane, this icon  appears in the upper right of the pane. Clicking on it will expand the pane into a larger window, as big as possible given your browser size.


Go back the way it was:  The large "Close" arrow at the upper left is always available in the expanded views, and enables you to return back to the pane view.

Also see the next section on image navigation. You have different image navigation options when you are in expanded view (as compared with the default view in a pane).

FITS Image Navigation



Single or Tiled Images

In the upper left of the images window pane, you have these icons:  The first icon means "show images one at a time in this pane." The second icon means "show all the images I have loaded in groups of up to 12 at a time" (see below for more on this). For moving target (SSO) searches, this is the default view.

Paging through single image views

If you have many images loaded in and you choose to view many images at once, it will show up to 12 images per page. It will then give you navigation aids at the top of the pane, like this:


◀ < 1 of 234 > ▶ (1 - 12 of 2,804)

In this example, the first 12 of 2804 images are shown. Use the arrows to navigate through the 234 'pages' of 12 images each.

Default views

For most results, the default view is one image at a time. For Solar System search results, the default view is tiled images.

Expanded views

As noted [above](#), if you click on this icon , it makes the images pane take up the entire browser window. When you do that, you have different image navigation options:



The first icon (the big square) denotes "show one image at a time." The second icon (the cluster of four squares) denotes "show smaller images of all the images I have loaded at once," e.g., tiled images. The third icon brings up a pop-up window with a list of the images you have loaded.

If you have more than one image loaded and you switch to viewing one image at a time, you get additional choices for navigating through the list of images:



the arrows take you forward and backward; the dots tell you where in the list you are. The "Auto play" tickbox scrolls through the list automatically.

When viewing many images at once, you get a "scroll images" switch. If you toggle this on, then each image tile becomes bigger, and you can use your mouse to scroll up and down through the collection of images. If you are on a Mac, your scrollbar may be hidden until you try to scroll.

When viewing the list of images that are loaded in, the table behaves like [any other table in this tool](#) -- that is, it is searchable, sortable, etc. However, as of this writing, the wavelength column is not correctly populated.

Tips and Troubleshooting

- ◇ When going from the 'window pane' view to the 'expanded' view, the images pane will only show you the images that you can see in the window pane view. That is, if you are looking at one image in the images window pane when you hit 'expand', it will only give you access to one image in the expanded view (even if you have more than one loaded into the tool). If you are looking at 12 images (out of many thousand) in the images window pane when you hit 'expand', it will only give you access to those 12 images image in the expanded view.
- ◇ When you are in the 'scroll images' view, and you try to scroll, if your mouse is in a currently active (selected) image (that is, highlighted in brown), then your image will zoom rather than scroll. Just move your mouse over to another image, and then your window will scroll rather than zoom. Or, find your scrollbar.

Image Toolbar (FITS and HiPS)

The image toolbox is always present as a row of tools associated with the images you have loaded, or that are loaded on your behalf. They're generally located above the images you have loaded, with most of them on the upper right. Letting your mouse hover over any of these icons will result in a "tool tip" that appears in order to remind you what the icon does. Most items apply equally to FITS and HiPS images, but some only apply to FITS images.

This is the image toolbox when you have clicked on a FITS image you have loaded:



And, this is the image toolbox when you have clicked on a HiPS image you have loaded:




The two toolbars are different, but if the same icon appears, it has the same effect on the image. Many of the icons have a downward pointing black triangle, which means that there are additional options in a drop-down menu that appear when you click on the icon.

We now discuss each icon in the order in which they appear.



Tools drop down

The choices here look like this:



Saving the image

The diskette icon will allow you to save the current image. You can save files to your local disk or to the [IRSA Workspace](#). Note that **you** control where the file is saved on your disk through your browser; your browser may be configured to store all downloads in a particular location on your disk.

If the current image is a FITS file, you can save it as a FITS or PNG or regions file to your local disk. If it is a HiPS file, your only choices are PNG or regions file. Saved FITS images will not save the color stretches or overlays; it will just save the underlying FITS image. Saved PNG files WILL include any overlays or annotations you have placed on the image, but will not include the underlying FITS image. Saved regions files will not save the underlying image, but will just save the overlays as a DS9 Regions file. See the [DS9 website](#) for more

information on the syntax of these DS9 region files.

Note that you can save the original or a cropped version of a FITS file; see the "select region" icon below to crop, then click on the save icon. Be sure to save the cropped FITS image (see annotated figure). This feature is not available for HiPS images.

Note that if you [overlay a large catalog](#) on an image, then turn around and save a regions file from the catalog overlay, the full catalog may not be saved to the regions file. If you have >5,000 sources, it's entirely likely that not every source will be overlaid on the image (because of [hierarchical catalogs display](#)), and thus will not be in the regions file. If you want to save your entire catalog as a regions file, **save the catalog from the [table pane](#)**.

The saved PNG is the same size as it is on your screen. If you want a big version, make the desired image big on your screen (view one-at-a-time; see [here](#)) before saving the PNG.

You can't save HiPS images from within this tool. To download your own copy, you will have to track down the original source of the image.

Restoring everything to the defaults

If you've played around a lot with the image, you may want to undo everything you've done. Click this button to restore everything to their original default values. Some layers may persist; remove them via the layers icon.

Viewing the image header

This icon displays a pop-up window with information about the image. If a FITS image is selected, it will show the FITS header of the image; if a HiPS image is selected, it will show the HiPS properties of the image. These are Firefly tables like all the other [tables](#) in this tool, so they are sortable and filterable, etc. If you click on the columns in the pop-up, it will sort the keywords alphabetically by that column. This is useful for finding individual keywords in particularly densely populated FITS headers. Click the header again to sort in reverse-alphabetical order, and a third time to return to the default order. Below are examples of an original and sorted FITS header. To make this window go away, click on the 'x' in the upper right of the pop-up, or click "close" on the bottom left.

ZTF Help

FITS Header : SEIP IRAC3

Pixel Size: 0.60" File Size: 2.4M Dimensions: 844 × 744

| # | Keyword | Value | Comments |
|----|----------|-------------------------|---|
| 2 | BITPIX | -32 | bits per data value |
| 3 | NAXIS | 2 | number of axes |
| 4 | NAXIS1 | 844 | size of the n'th axis |
| 5 | NAXIS2 | 744 | size of the n'th axis |
| 6 | EXTEND | T | Extensions are permitted |
| 7 | ORIGIN | Spitzer Super-Mosaic Pi | Origin of these image data |
| 8 | CREATOR | Spitzer Science Center | Creator of this FITS file |
| 9 | | | |
| 10 | | | / TIME AND EXPOSURE INFORMATION |
| 11 | | | |
| 12 | TELESCOP | Spitzer | Name of Telescope |
| 13 | INSTRUME | IRAC | Name of Instrument |
| 14 | CHNLNUM | 3 | Instrument channel number |
| 15 | WAVELEN | 5.8 | Effective wavelength of band in microns |
| 16 | MJDSTART | 53072.098615 | MJD of first observation in mosaic |
| 17 | MJDMEAN | 53117.651693 | Mean MJD of observations in mosaic |
| 18 | MJDMED | 53072.5 | Median MJD of observations in mosaic |
| 19 | MJDEND | 54465.998452 | MJD of last observation in mosaic |
| 20 | EXPTIME | 75.73 | Mean exposure time in seconds per pixel |
| 21 | MEXPTIME | 83.2 | Median exposure time in seconds per pixel |
| 22 | ETMIN | 10.4 | Minimum exposure time in seconds of input expos |
| 23 | ETMAX | 26.8 | Maximum exposure time in seconds of input expos |
| 24 | COV | 6.93 | Mean coverage in exposures per pixel |
| 25 | MEDCOV | 6.93 | Median coverage in exposures per pixel |
| 26 | ETMAX | 26.8 | Maximum exposure time in seconds of input expos |

Close

FITS Header : SEIP IRAC3

Pixel Size: 0.60" File Size: 2.4M Dimensions: 844 × 744

| # | Keyword | Value | Comments |
|----|---------|------------------------|---|
| 2 | BITPIX | -32 | bits per data value |
| 51 | BUNIT | MJy/sr | Units for image counts |
| 66 | CD1_1 | -0.00016667 | Transformation matrix |
| 67 | CD1_2 | -0. | |
| 68 | CD2_1 | -0. | |
| 69 | CD2_2 | 0.00016667 | |
| 14 | CHNLNUM | 3 | Instrument channel number |
| 24 | COV | 6.93 | Mean coverage in exposures per pixel |
| 8 | CREATOR | Spitzer Science Center | Creator of this FITS file |
| 77 | CRPIX1 | -3.610249E2 | |
| 78 | CRPIX2 | 754.8659668 | |
| 61 | CRVAL1 | 210.99613 | [deg] RA of reference point |
| 62 | CRVAL2 | 54.406342 | [deg] DEC of reference point |
| 63 | CTYPE1 | RA---TAN | RA projection type |
| 64 | CTYPE2 | DEC--TAN | DEC projection type |
| 54 | EFCONV | 0.5858 | (MJy / (MJy/sr)/(DN/s) for input exposures |
| 83 | END | | |
| 71 | EQUINOX | 2000. | [yr] Equatorial coordinates definition |
| 23 | ETMAX | 26.8 | Maximum exposure time in seconds of input expos |
| 22 | ETMIN | 10.4 | Minimum exposure time in seconds of input expos |
| 53 | EXPAIN | 3.800 | e- / e-/DN for input exposures |
| 20 | EXPTIME | 75.73 | Mean exposure time in seconds per pixel |
| 6 | EXTEND | T | Extensions are permitted |
| 47 | FCREATE | 2012-10-17T01:21:56 | File creation date/time (UTC) |
| 27 | PC1_1 | 40.560 | Maximum exposure time in seconds of input expos |

Close

For comparison, an example of the HiPS properties window is here:

HiPS Properties : AllWISE color Red (W4) , Green (W2... X

| Property | |
|--------------------|---|
| hips_service_url | https://irsatest.ipac.caltech.edu/data/hips |
| creator_did | ivo://CDS/P/allWISE/color |
| obs_collection | The Wide-field Infrared Survey Explorer - |
| obs_title | AllWISE color Red (W4) , Green (W2) , Blu |
| obs_description | NASA's Wide-field Infrared Survey Explor |
| obs_ack | This Progressive Survey distribution maki |
| obs_copyright | IPAC/NASA |
| obs_copyright_url | http://wise2.ipac.caltech.edu/docs/releas |
| client_application | AladinLite |
| client_category | Image/Infrared/WISE |
| client_sort_key | 04-003-00 |
| hips_creation_date | 2014-04-15T08:59Z |
| hips_release_date | 2019-05-20T08:30Z |
| hips_builder | Aladin/HipsGen v10.125 |
| hips_creator | Thomas Bach [CDS] |

Close



Rotating the image so that North is up

Images retrieved in the ZTF Image Service are frequently NOT North-up/East-left. Clicking this icon will orient the selected image so that North is up.



Flipping the image on the y-axis

Clicking on this icon flips the image on the y-axis. (This option is only available for FITS, not

HiPS, images.)



Add a compass rose

When you click this icon, arrows appear on the image showing which direction is North and which is East. Clicking on this icon a second time removes this compass rose. (You can also remove this layer via the layers icon, described below.)



Add a coordinate grid

Click on this icon to overlay a coordinate grid on the image. Click it again to remove it.

Customize the units of the grid (to, e.g., Galactic coordinates) via the "layers" icon (described below). (Also see information on HiPS grid in the [WCS section](#).)



Measuring a distance


When you click this icon, at first, nothing seems to happen. However, you can now click and drag to draw a line on the image, and the length of the line is displayed (in the middle of the line). The units for the measured distance (and the color of the overlay) can be changed from the "layers" icon (described below). You can calculate the difference in RA and Dec separately via the layers icon as well; find the layer associated with the distance measurement and tick the "offset calculation" box. When it displays the offset calculation, it will give you the angle in degrees in one corner, and the length of the line segment in the RA and Dec directions, in the units you have specified. When you are done with the distance tool, you can click on the

End Distance

that appears next to the image toolbar, or click on this icon a second time to remove the distance tool. (You can also remove this layer via the layers icon.)



Read in a DS9 Regions file

When you click this icon, you get a pop-up window from which you can read in a DS9 regions file from your local disk. See the [DS9 website](#)  for more information on the syntax of these DS9 region files. The supported regions are text, circle, box, polygon, line, and annulus. To make this window go away without doing anything, click on the 'x' in the upper right of the pop-up.

Tips and Troubleshooting: If you overlay a list of sources you created in ds9 regions format from your disk, it will only be overlaid on the current image, not all of the images you have loaded. If you want to have it overlaid on all the images you have loaded, create a catalog from your source list and overlay it as a [catalog](#). Then it will appear on all of the images you have loaded, provided that the positions overlap on the sky.



Put a marker on the image

When you click this icon, a drop-down menu appears with several possible options:

- Add Marker
- Add Spitzer footprint ▶
- Add SOFIA footprint ▶
- Add HST footprint ▶
- Add JWST footprint ▶
- Add Roman footprint

ZTF Help

The first overlay choice (simply called 'marker') is a red circle. Initially, it appears in the center of the images, and is meant to be moved to wherever you first click in the image. It looks like this:



The dash-dot line around it means that it is 'active', so you can move (click and drag the marker) or resize it (click and drag the dash-dot boundary). You can change the color of the marker (and change the label) via the "layers" icon (described below). You can also remove this layer via the layers icon. There are several additional options in the drop-down, enough that they have their own [section below](#).



Drill down through the image

If your FITS image has multiple planes or HDUs, especially if each plane or HDU represents a different wavelength, it can be useful to "drill" down through the image cube at a given position on the sky. (You are unlikely to find this kind of file in the ZTF archive.) This tool allows you to do just that. When activated, this tool extracts the data at the place your mouse clicks down through the cube. For more information on saving the information, see the [extraction section below](#).



Draw a line in the image

When this tool is activated, you can draw a line in your FITS image with your mouse, and it will extract for you the pixel values along that line. If you have more than one image loaded and visible, you can shift-click in another image to see the same line in another image. For more information on saving the information, see the [extraction section below](#).



Make points in the image

When this tool is activated, you can click in your FITS image with your mouse, and it will extract for you the pixel values at the location of your click, creating a catalog for you as you click. If you have more than one image loaded and visible, you can shift-click in another image to extract points from another image. For more information on saving the information, see the [extraction section below](#).



Zoom

When your mouse is in an image, these options appear in the upper left of the image.



Zooming in or out

Clicking on these magnifying glass icons zooms in or out of the image. The readout of the net effect of your zooming on the displayed field of view (FOV) appears at the top left of each image.

If you click zoom in or out rapidly, a pop-up window appears to allow you to more rapidly select the zoom level (field of view) you want. Select the desired level, or click on the 'x' in the upper right to make the window go away. Here is an example:

| Choose Field of View | | × |
|-----------------------|------|---|
| 3.8° | 1.8' | |
| 1.9° | 1.5' | |
| 57' | 1.3' | |
| 28' | 1.1' | |
| 14' | 53" | |
| 12' | 45" | |
| 10' | 37" | |
| 8.5' | 31" | |
| 7.2' | 26" | |
| 6.0' | 22" | |
| <u>5.1' : Current</u> | 18" | |
| 4.3' | 15" | |
| 3.6' | 13" | |
| 3.0' | 11" | |
| 2.5' | 9.5" | |
| 2.1' | 8.0" | |
| | 6.7" | |

You can alternatively zoom using the mouse wheel (or drag forward and backward on a touchpad or magic mouse).

Note that there is a maximum (or minimum) allowed zoom level, and they are different for FITS and HiPS images. A notification will appear when you have reached the maximum (or minimum) allowed zoom level for a given image. To enlarge images more (or less) than that, please repeat your search to obtain new images with smaller (or larger) spatial extent. HiPS images are specifically designed for large areas, so if you need a big area, use HiPS. If you want to zoom in close enough to see individual original pixels, your best choice is FITS.

See also the section below on [changing coverage images](#), specifically that on automatic transitions while zooming.



Fit image to screen or fill screen

These two icons are designed to maximize the available space in your browser window. The first one automatically picks a zoom level such that the image entirely fits within the available space (which could be your whole browser window, or just the portion of it where that image is loaded). The second one automatically picks a zoom level such that the image fills as much of the available space as possible (e.g., it is zoomed such that short axis of the window is filled with the image, whether that short axis is left-right or up-down).

ZTF Help

By default, the images that are returned are frequently but not always centered on your search target. Clicking on these icons let you see the whole image that is returned, whether or not it is centered on your target.

This is available for both FITS and HiPS images, though note that FITS images retrieved from IRSA using this tool are typically square, and HiPS images cover the sky, so fitting the image to the screen might not be what you want to do.




Zooming to a 1-to-1 size

Clicking this icon will zoom the image such that one pixel in the image is one pixel on your screen. This option is only available with FITS images; HiPS images by their nature have pixels of varying sizes, so this button would have no meaning in this case.



Color table drop down

This icon enables you to change the color table of the displayed image. (This option is available for FITS and HiPS images.) When you click the button, a drop-down menu appears.



- ◇ The top of the menu either says "Color and overlays locked" or "Color and overlays unlocked" -- by default, all of the (FITS) images that you have loaded are locked together for color and overlays. What that means is if you change the color table (via this menu), then the color table for all the (FITS) images are changed. (Or, if you add a layer to one image, then the layer is added to all the images; see below.) If you don't want this to happen, select "Color and overlays locked" to unlock it. Select the text again to lock it again.
- ◇ The arrow in the upper right creates a pop-up window out of this drop-down menu so that you can leave the choices up while settling on the best option.
- ◇ The next portion of the menu has a wide variety of color table choices. Select your new color table from the options shown.
- ◇ Alternatively, you can use the "color bar" slider to move among the color tables by number. These numbers correspond to the color bar number used in the Python implementation of the Firefly tools.
- ◇ Below the color bar slider, there are sliders controlling the bias and contrast. Click or drag the slider to change the image display.



Color stretch drop down

This icon enables you to change the color stretch of the displayed image. (This option is only available for FITS, not HiPS, images.) Because this is complicated, for much more information, please [see below](#).



Re-center the image drop down

Clicking this icon produces a drop-down menu:

By default, "Pan by table row" is turned on (checked), but, depending on how you have loaded your images, or whether you have catalogs loaded, it may not seem to do very much. However, if you have a catalog loaded and are zoomed in on your images, as you scroll through your catalog, the FITS image underneath will move as needed when you have selected an observation in a different part of the sky than was originally shown.

Other choices are to center on the target of the observation, center the image in the window, or center on a target of your choice. For the last of those, you can simply center on that target, or center and leave a marker on the image at that location.



Selecting a region drop down

When you click this icon, you can select a region of the image for further actions. Because this is complicated, for much more information, please [see below](#).




Image Layers: Viewing/Changing the Layers on the Image

Every time you add something new to the image, you add a 'layer' to the image. This is complex, so please [see below](#) for much more information.



Lock/unlock images

You may have this "lock images" icon appear in your toolbar; it will appear as the first icon if they are locked and the second icon if they are unlocked. The main purpose of this icon is to lock all the images you have loaded for zooming, scrolling, etc. You need to specify how it locks and for how long. Clicking it produces this drop-down menu:



The first set of options aligns the images only once, temporarily; the second set of options makes the alignment persist ("lock") when you move the images (that is, when you move one, they all move). You can align by the images' WCS (e.g., RA and Dec), by the target, by the pixels according to the origin of the coordinate system in the image header, or by the pixel at the image center. The most common choice is likely the WCS align and lock. This is discussed in more detail in the [WCS section](#).



Getting help


Clicking on this icon takes you to this help page.

Color Stretches




This icon enables you to change the color stretch of the displayed image. (This option is only available for FITS, not HiPS, images.) When you click the button, a drop-down menu appears with a variety of choices.

The top of the menu either says "Color and overlays locked" or "Color and overlays unlocked" -- by default, all of the (FITS) images that you have loaded are locked together for color and overlays. What that means is if you change the color stretch (via this menu), then the color stretch for all the (FITS) images are changed. (Or, if you add a layer to one image, or change the color table of one image, then the change is made to all the images; see other sections of this chapter.) If you don't want this to happen, select "Color and overlays locked" to unlock it. Select the text again to lock it again.




Below that, you can choose from a set of pre-selected options. If you pick the first one, "color stretch", you can customize the stretch. A pop-up window appears with a histogram of the values in the image, and you can change the stretch type and range.



If you pick a color stretch from the pre-defined options, the pop-up window reflects this change. If you change the color stretch in the pop-up window, the drop-down menu changes correspondingly.

Example: Display the pop-up for color stretch. From the main drop-down, pick 'Linear stretch to 99%'. Go back to the color stretch pop-up. Note that it has filled out the stretch type and ranges to reflect the current choice. Then -- either with the pop-up window still up or not -- go back and pick a different pre-defined stretch from the standard options. Note that the values in the pop-up change to reflect this current choice. From the pop-up, pick a different stretch type -- try "histogram equalization." Select "refresh" to update the images. Go back to the drop-down menu. The last 7 items have changed to be based on histogram equalization, as opposed to the "linear" default.

If you have a 3-color image, you can change the stretch in each color plane separately; select the tab at the top accordingly for red, green, or blue. By default, it stretches each band independently, and you can set the parameters in the stretch pop-up accordingly.



Modify Color Stretch [X]

Color, stretch & overlays locked

Per-band stretch | Hue preserving stretch

Red | Green | Blue

Move mouse over graph to see values

Stretch Type: Linear

☐ Use ZScale for bounds

Lower range: 1 %

Upper range: 99 %

Data Min: 95.462173 Data Max: 168.471573

Refresh [?]

As described in [Lupton et al. \(2004\)](#), a different algorithm may be useful for creating 3-band color images. Select "Hue preserving stretch" to invoke this option. This stretch should be a brightness-independent color-preserving asinh stretch, though in practical terms, it seems to work best for optical images.

Modify Color Stretch

✕

🔒 Color, stretch & overlays locked

Per-band stretch

Hue preserving stretch

Brightness-independent color-preserving asinh stretch;
images must be free of background artifacts

Scaling coefficients

^

Red: 1.00

-10.699

-0.301

0

Green: 1.00

-10.699

-0.301

0

Blue: 1.00

-10.699

-0.301

0

☐ Use ZScale for bounds

Q=0 for linear stretch;
increase Q to make brighter features visible

Q: 0.0

0

5

10

15

20

Pedestals (black point values)

^

Red pedestal:

1

%

⬆

⬇

Green pedestal:

1

%

⬆

⬇

Blue pedestal:

1

%

⬆

⬇

Refresh

?

It may be useful to scale individual channels; sliders allow you to do so. The Q parameter has another slider. For a linear stretch, $Q=0$; increase Q to change what features are emphasized. Pedestal values can also be set to

allow the level assigned to "black" to change.

Viewing/changing the layers on the image

Every time you add something new to the image, you add a 'layer' to the image. You can have an image with a lot of annotations on it.



The number that appears circled in blue over the layers icon tells you at any given time how many layers you have on the currently selected image (the image outlined in brown).




If you click this layers icon, you will get a pop-up window with a list of all the layers you have on top of the image. Here (on the right) is an example of a well-populated layers pop-up; in real life, this is scrollable to see several more layers). From this pop-up, you can:

- turn layers off and on (click on the switch on the left of the corresponding row);
- remove layers entirely (click on the 'x' on the right of the corresponding row);
- change colors of overlays (see below);
- change symbol shapes and sizes (for [overlaid catalogs](#)), including [hierarchical catalog settings](#);
- change annotations (for markers);
- or change units (for the coordinate grid or the [distance tool](#)).



To add entirely new layers, though, you need to go to other options within the toolbar.

You can "show all" or "hide all" with the buttons on the lower left of the pop-up window. To make this pop-up window go away, click on the 'x' in the upper right of the pop-up.

Note the target



description:  Image Search: 210.802267, 54.348950 Equ J2000   Offset Calculation
This reminds you of the target on which you searched -- here, it was 210.802267, 54.348950 in J2000. The two icons next in that row indicate, respectively, "copy this location to the clipboard" and "center image on this position."

Layers- WISE Band 1

☒ Image (FITS)
 ☒ Image Search: 210.802267, 54.348950 Equ J2000  

☐ WISE Latents
 ☐ WISE Optical Ghosts
 ☐ WISE Halos
 ☐ WISE Diffraction Spikes

☒ grid

☒ North Arrow - EQ. J2000

☒ Distance Tool

☐ Offset Calculation
 Unit: ☒ degrees ☐ arcminutes ☐ arcseconds ☐ pixels
 Click and drag at either end to adjust distance


Show All

Hide All


Where it's possible to change colors of a layer, click on the 'colors' link to be taken to a new pop-up from which you can select a new color.

From here, you can click on your desired color in the top colorful box. Immediately below that box, you can change the color and saturation of the top box so that you can select from a different range of colors. Below that, you can enter numerical hex codes or RGBA values (where the value for RGB is between 0 and 255, and A is in units of percent, e.g., 50 = 50%). Finally, you can also select from a pre-defined set of 15 colors by clicking on any of the small boxes. Note that the numerical codes update as you select different colors. Your choices are implemented as soon as you select them. Click 'Close' to close the window, or click 'x' in the upper right.

If you have a [catalog](#) loaded into the tool, you can also obtain this pop-up by clicking on the color swatch in the heading of the catalog tab.



For catalogs or the search target, you can also select the symbol shape and size. To adjust the size, type in the symbol size in pixels or use the up/down arrow keys to change the size by one pixel at a time. Your choices are implemented as soon as you select them. Click 'Close' to close the window, or click 'x' in the upper right.





For a HiPS image, you also have a layers icon (), from which you have new, HiPS-specific choices in the layers:

Layers- AllWISE color Red (W4) , Green (W2) , Blue (W1) from raw Atlas Images
X

☒ Image (HiPS)

☒ HiPS Search: 30 Dor NED

Symbol
Color

☒ North Arrow - EQ. J2000

Color
X

☐ HEALPix (HiPS) Grid

Color
X

☒ Auto
☐ Grid Match Image Depth
☐ Grid Level Lock

☐ MOC - AllWISE color Red (W4) , Green (W2) , Blue (W1) from r...

Color
X

Outline
Fill
MOC Tile Outline

Show All
Hide All

?

HEALPix (HiPS) Grid

To turn on these choices, toggle the switch to the left of "HEALPix (HiPS) Grid". (See [below](#) for more information on HiPS images in general.)

Auto: This option overlays a position grid, with the tile numbers marked in the center of each box. As you continue to zoom in, when smaller tiles are needed, they are drawn, with the new tile numbers marked. You may not zoom beyond HiPS Norder level 14 tiles. The numbers after the "/" is in the "NESTED" (as opposed to RING or NUNIQ) numbering system; see [the IVOA standards document](#) for more information.

Grid Match Image Depth: If you select this option, the grid will adjust to a new level when you zoom in and a new level of HiPS image both exists and is used for the display.

Grid Level Lock: Selecting this option yields an additional numerical drop-down menu. The higher number you pick, the smaller the grid boxes are that are drawn. When this option is selected, the boxes stay the same size regardless of how zoomed-in on the image you are.

HiPS MOC

To turn on these choices, toggle the switch to the left of "MOC".

A MOC tells you via a simple boolean yes/no, is there sky coverage from this data set in this region. The choices here are:

- ◇ Outline - an attempt to outline the entire region covered by the data; it still sometimes struggles near the edges of coverage, so zoom in to get a better sense of the coverage edges.
- ◇ Fill - filled regions, where you can control the opacity of the overlay by going to the [color picker](#); you control the opacity by changing the number above the "A".
- ◇ MOC Tile Outline - individual tile outlines, where the tiles are set by the MOC tiles themselves (as opposed to tiles created by the mosaic tiles that make up the data set).

Tips and Troubleshooting:

- The entire concept of a MOC is built upon the "tiles" that are inherent to the HiPS concept. As a result, those tiles are imprinted on how the MOC is rendered, especially near edges or corners of coverage. Strange behavior may result; you can always zoom in to get a better sense of the coverage. For authoritative information, download the actual data for the region you are concerned about.
- For the "fill" option for a MOC, depending on how you display a MOC, you may see two shades of color in the MOC. It is important to note, though, that the information it is displaying does not include depth of coverage, merely boolean "is there data there or not." Why is it displaying shading? Well, it's rounding. For example, a given WISE MOC might be generated at order 13. At this order, there are 805,306,368 HEALPixels on the sky, and they are about 26 arcseconds across. When zoomed out far, there is no point in trying to show each of these pixels, so the application "rounds up" the MOC to an order in which there are roughly 100-200 displayed HEALPixel polygons horizontally across the image. When it does this, it flags the rounded up polygons with the paler color. So the boundaries of a coverage region in the MOC all get a paler color. If you zoom in far enough on a MOC, the two-tone colors go away.
- You might be here in the documentation looking for more information on [hierarchical catalog settings](#); this is also related to HEALPix.

World Coordinate System (WCS) Alignment

As described above, there is a way to lock/unlock images to each other   for position matching. This section describes the image locking in more detail.

When aligning images, you can specify how the images align and for how long. Clicking the lock images icon produces this drop-down menu:

Align-only Options

- by WCS
- by Target
- by Pixel Origins
- by Pixel at Image Centers

Align and Lock Options

- Unlock
- ✓ by WCS
- by Target
- by Pixel Origin
- by Pixel at Image Centers

The first set of options aligns the images only once; the second set of options makes the alignment persist ("lock") when you move (zoom, etc.) the images.

You can align by the images' WCS (world coordinate system, e.g., RA and Dec), by the target (align by target on the screen, regardless of position in the sky), by the pixels according to the origin of the coordinate system in the image header, or by the pixel at the image center. The most common choice is likely the WCS align and lock.




Note that aligning by WCS puts North up, and aligned so that each image has the same angular scale.

Tips and Troubleshooting

- When you have both FITS and HiPS images loaded (as you should when you run the ZTF tool, because the coverage image is a HiPS image), if you select a HiPS image to be active when you select "lock by WCS", the HiPS will not lock to the FITS image unless the image is either J2000 or galactic north up. If you want the HiPS image to align to the FITS image, select the FITS image first and then select "lock by WCS"

Extraction Tools

Several tools allow you to extract information from images or image planes, but only for FITS (not HiPS) files. Within the ZTF tool, you are very unlikely to encounter data for which the drill can be used.

-  -- Extract down through image planes
-  -- Extract a line from the image
-  -- Extract points from the image

All three of these follow the same basic structure --

1. Initiate extraction mode
2. Set aperture
3. Try extraction; repeat if desired
4. Pin (retain) extraction if desired
5. Download (as table or chart) if desired
6. Repeat if desired
7. Click on "end extraction" to finish the process.


The drill pokes down through multiple planes (which you are very unlikely to encounter in the ZTF Image Service), the line moves across pixels in a plane, and the points extracts points from a plane.

Here, we cover the basic approach, with specifics of each tool integrated as we go along.


Initiate extraction mode. When you click on one of these icons, you enter into the extraction mode. Text appears next to the image toolbar to remind you that you are in this mode: **End Extraction** When you are done, to end this mode, click on this "end extraction."

When starting out, the pop-up window that you get depends on the tool you pick.


For the drill:



for the line:



and for the points:




Set aperture. In all three cases, the top center of the extract pop-up window has a drop-down from which you can select the aperture value. For the drill and points, you can choose, in pixels, 1x1, 3x3, 5x5, or 7x7. Values can be summed or averaged. For the line, it's a little different. The apertures are 1x1, 1x3, 1x5, or 1x7, and you control whether the points are summed or averaged. You can have it extract along a line that you draw with your mouse on the image (useful for examining brightness profiles, e.g., across spiral arms of a galaxy), or you can have it extract an entire line or column of the image that you specify (useful in the cases where the 'image' is a file where the first row is an extracted spectrum, the second row is the error, the third row is a mask, etc.).

Try extraction. From this point, you can click on your image, or click and drag for the line tool. The pop-up then contains a plot of your extraction.

For the drill:

for the line:

and for the points:




In each of these cases, it does the best that it can to label the axes accordingly. The cube that is used for the drill example here follows the spectral data model so that it is recognized as a spectrum, and it plots against wavelength. The line extraction is a 1x3 average and plots the offset in arcseconds from the initial mouse click, given the WCS information in the header of the image. The point extraction is a 3x3 sum, and plotted in image x coordinates, but can be changed to show image y coordinates.

Note that for the line, if you have more than one image loaded and visible, you can shift-click on a new image to see the same line on a new image. Similarly, for the points, you can shift-click to change images without extracting points.

For the line extraction, if you want to change at this point to extract along a line or column, use the drop-down menu at the bottom of the pop-up. It's shown here as "free hand selection", but the other choices are line or column selection; you click on the image to select a line or a column, which is particularly useful for quick looks at semi-extracted spectral images.

Pin extraction. Once you have an extraction that you like, you can retain the extraction for further analysis. "Pin chart/table" extracts the information as a [table](#), just like any of the other tables in this tool, with an accompanying [plot](#). You can then manipulate the table/plot just like any other table or plot in this tool. If the tool recognizes the extraction as a [spectrum](#), you may have additional capabilities.

Once you pin or save your extraction, the tool leaves a "footprint" of your extraction on the image so that you can remember what the extraction was. **NOTE THAT it is not interpolating** across fractional pixels here. It is averaging if you have asked it to average, but particularly if your pixels are large, if you draw a line that is diagonally across pixels, it will be immediately obvious that it's not interpolating. This line gets rendered as these pixels:



The point appears on the image at the lower left corner of the relevant pixel.

You can pin as many different extractions as you want.

From the line extraction pop-up, when you click on "Pin Chart/Table", you get another pop-up:

From this pop-up, you can choose to do a line extraction from just the currently selected image (most likely where you drew your line); all the images and putting all of the extracted lines into one big table (and tab); or all the images and putting all of the extracted lines into individual tables (and tabs). When you do this, the question naturally arises as to how the tool should specify which column (or tab) goes with which image. Some of the images have long, sometimes cryptic titles. You can choose to have the tool use the full image titles in the column headers or tab titles, or abbreviations.

If you choose to have the tool generate one table for each image you have loaded, you may suddenly have a lot of new tabs at the bottom of the screen. There are navigation aids within the [tables section](#) that may help.

Download extraction. You can download the extraction as a table or plot without pinning it. *Download as Table* saves the table to your local disk -- first, you have the same options as immediately above, where you can choose to do a line extraction from just the currently selected image; all the images and putting all of the extracted lines into one big table; or all the images and putting all of the extracted lines into individual tables. Then you have [all the same save options as a regular table](#). *Download Chart* saves the plot as shown, as a png file.

After pinning an extraction, you also have the extraction appearing as a table in the tables section of your window and as a plot in the plots section of your window. As with [any table](#) in this tool, you can save the table by clicking on the diskette icon in the table. You can choose from a variety of formats; [see the tables chapter for more information](#). Similarly, as with [any plot](#) in this tool, you can save the plot by clicking on the diskette icon in the plot. See the [plots chapter](#) for more information.

Repeat extraction. As long as the extraction pop-up is still open, you can continue to click points or draw lines to make additional extractions.


End extraction mode. **End Extraction** When you are done, to end the extraction, click on "end extraction" to end the extraction. Alternatively, just click on the 'x' in the upper right corner of the extraction pop-up.

Region Selection



When you click this icon, you can select a region of the image, from which then you can do a whole host of things to the image and to the catalog you may have overlaid upon it.

First, from the drop-down, you are given a choice of a rectangular selection or an elliptical selection:



After you make that choice, you can click and drag in the image, selecting a box or a circle on the image. For the circle, your click is the center of the circle and the drag is the radius of the circle; for the box, your first click is one corner of the rectangle, and the drag is the opposite corner of the rectangle. This region can be resized by grabbing and dragging the corners of the box or the pixels delineating the corners of a box around your code. If you need to move the image underneath, you can hold the shift key and click and drag.

When you have selected a region of the image, additional icons appear above the image, and exactly which icons you see is a function of whether you are working on a FITS or HiPS image, and whether or not you have a

catalog overlaid:




These icons allow you to do several things:



Crop the image

(FITS only) Crop the image to the selected region. Then you can save the cropped FITS image via the save icon described above.

Note that, if you have a rotated FITS image such that a crop would have to bisect pixels, it will show you the region that encompasses your selection. If you crop at that point, then, it will crop in image space (such that pixels are not bisected). See the figure below -- in the original image, north is up. This has been rotated 45 degrees. The selected region is in white. The yellow dash-dot line is the crop in pixel space that encompasses the selected region.



Select sources (and cancel selection)

(Only if a catalog is overlaid) Select the catalog sources overlaid on the image within the region.



Selecting highlights the sources in the list and plot with a different color row or symbol. Once there are selections made, the second icon appears to give you an option to cancel the selection.



Filter sources

ZTF Help

(Only if a catalog is overlaid) Filter the overlaid catalog down to the sources within the enclosed area. When you choose to impose a filter via this selection mechanism; the filters icon changes above the

catalog to indicate that there is a filter applied (). To clear the filters, click on the cancel filters icon (which also appears after you impose filters):  . There is much more on [filters](#) in the Tables section.



Zoom the image

Zoom the image to fit the selected area into your field of view.




Recenter the image

Recenter the image on the selected area.



Obtain statistics

(FITS only) Obtain statistics from the image on the region. The statistics option results in a pop-up that looks something like this:



Note that it calculates the location of the minimum and maximum fluxes, and the aperture and flux-weighted centroids; the flux values given are in the same units as the FITS file. If you put your mouse over the row of the table in the pop-up, that location appears as an 'x' on the image.



Search

This tool implements a new search, an "action", on the region you have selected. It results in this drop-down (right). where this example is based on a region centered on 84.036131, -69.224431, J2000 decimal degrees, over a 4-cornered polygon. (You can also use the region tool to define a

cone; this example happens to be a rectangle.) From this drop-down, you can launch:

- ◇ A TAP polygon search over this region ([more information about TAP searches](#))
- ◇ A NED cone search at this position with a radius attempting to correspond to this polygon ([more information about NED searches](#)); results loaded into this tool.
- ◇ A Simbad cone search at this position with a radius attempting to correspond to this polygon; results loaded into this tool.
- ◇ A Simbad cone search at this position with a radius attempting to correspond to this polygon, but launch another browser window or tab at Simbad with the results.
- ◇ A TAP cone search at this position with a radius attempting to correspond to this polygon ([more information about TAP searches](#)); results loaded into this tool.
- ◇ Refine the search region.

The last option brings up another pop-up window (similar to [this](#)) that allows you to refine the search region iteratively by choosing a cone or polygon, setting the center, and setting the cone size or polygon vertices.

From here, you can change the kind of search, refine the positions, launch searches from your refined position (blue button on lower left), and select from the image again (drop-down on the lower right).


When you are working with the selection tool, this: **End Select** appears next to the image toolbar to remind you that you are in that mode. If you are refining positions for a search, it will be **End Search Marker**. Either way, when you are done with the selection tool, if your other actions don't turn off the selection tool, click on that text to turn it off.


Tips and Troubleshooting

- The "region selection" tool also appears in the slightly different context of [interactive target refinement](#) in several other places in this tool, where it works in a very similar fashion.


Footprints



The marker icon () has a drop-down menu with several possible options:




Any of the options with an arrow on the right can expand to additional subsidiary choices, e.g.,:



We now describe these various footprints here.

For each of these choices, the markers appear initially in the center of the loaded images. The first mouse click you make in any of the images will move the marker to that location.

Each of these marker choices, when overlaid and/or selected as 'active', has a dot-dash square around it. If it is asymmetrical (most of them are), it has an additional "appendage" and a red plus at the center of the footprint:




These so-called "handles" allow you to resize and/or rotate the marker, depending on the nature of the marker. These handles only appear when the marker is selected as active; if you wait a few seconds, they vanish.


Tips and Troubleshooting

- Some of these footprints are *large*. If you have a small image, some of these footprints will be larger than your image. Zoom out to see it, or find a larger image to use. If you overlay, say, a Nancy Grace Roman Space Telescope (formerly WFIRST) footprint on a 2MASS Atlas FITS image, you may need to zoom out a considerable amount before you can see the Roman footprint. You will see the center indicator of the marker before you will see the Roman footprint itself.
- You can add multiple copies of the same marker using the [layers pop-up](#) (described generally above). From the layers pop-up, there is a link right under the 'angle' option that says "Add another [marker type]" -- click on that to get an additional marker of the same type. You can also add a label to the marker from the layers pop-up, or change its color.
- If you have many footprints on the same image, you may have trouble grabbing and moving footprints lower in the stack of layers on the image. For example, overlay footprint 1, then footprint 2, and you might have a hard time grabbing and rotating footprint 1 after footprint 2 has been added. The only workaround here is to use the layers pop-up (described generally above) to temporarily hide footprint 2, then move footprint 1, then restore footprint 2.
- If you have images of very different resolutions loaded (e.g., IRAS and really anything else), sometimes it struggles to render the marker on each image. You may need to place markers on one image at a time. (Unclick the "lock color & overlays" option to place markers one image at a time.)




The first overlay choice (simply called 'marker') is a red circle.

The remaining markers are all footprints from various telescopes: Spitzer, SOFIA, HST, JWST, and Roman. HST, JWST and Roman are derived from information provided via MAST (see <http://gsss.stsci.edu/webservices/footprints/help.html> ) For Roman in particular, they are pre-launch values.



Spitzer/IRAC 3.6 and 4.5 micron footprints. These two footprints are placed separately from each other. The footprint can be moved or rotated. Click and drag the center of the footprint. A circle appears with four small circles ("handles") around it. Grab and drag the small circles to rotate it, or drag the big circle to move it. Change the color, delete, or add more copies of the IRAC footprints from the layers pop-up.





SOFIA footprints. Several different SOFIA footprints are available; the graphic here shows a selection of them. The available footprints (all of which are placed separately) are:


- FIFI-LS
 - ◆ Blue (50-120 microns)
 - ◆ Red (110-200 microns)
- FLITECAM
 - ◆ Imaging
 - ◆ Grism ABBA
 - ◆ Grism AB

- FORCAST
 - ◆ Imaging
 - ◆ Grism a
 - ◆ Grism b
- FPI+
- HAWC+
 - ◆ 53 microns (Band A), Total Intensity
 - ◆ 53 microns (Band A), Polarization
 - ◆ 89 microns (Band C), Total Intensity
 - ◆ 89 microns (Band C), Polarization
 - ◆ 154 microns (Band D), Total Intensity
 - ◆ 154 microns (Band D), Polarization
 - ◆ 214 microns (Band E), Total Intensity
 - ◆ 214 microns (Band E), Polarization


Change the color, delete, or add more copies of the SOFIA footprints from the layers pop-up.




HST footprints. You can overlay the whole focal plane footprint, shown here, or individual instrument footprints (NICMOS, WFPC2, ACS/WFC, ACS/HRC, ACS/SBC, WFC3/UVIS, and WFC3/IR). Consult the [HST documentation](#)  for specifics on which apertures are which. The footprint can be moved or rotated. Click and drag the center of the footprint. A circle appears with four small circles ("handles") around it. Grab and drag the small circles to rotate it, or drag the big circle to move it. **Note that** if you overlay the footprint on a very small image, nothing will appear to have happened. You need at least a 45 arcmin image to comfortably see the footprint. Change the color, delete, or add more copies of the HST footprints from the layers pop-up.




JWST footprints. You can overlay the whole focal plane footprint, shown here, or individual instrument footprints (FGS, MIRI, NIRCAM, NIS, and NIRSPEC). **Note that** if you overlay the footprint on a very small image, nothing will appear to have happened. You need at least




a 30 arcmin image to comfortably see the entire JWST focal plane. Please consult the [JWST documentation](#)  for details about the footprints. In all cases, if the footprint is 'active', a circle near the middle of the footprint will appear with four small circles ("handles") around it. Grab and drag the small circles to rotate it, or drag the big circle to move it. Change the color, delete, or add more copies of the footprints from the layers pop-up.



Nancy Grace Roman Space Telescope


focal plane footprint. As above, the footprint can be moved or rotated. Click and drag the boresight (the cross hairs), which appears by default to the upper right of the array of squares. A circle appears, centered on the boresight, with four small circles ("handles") around it. Grab and drag the small circles to rotate it, or drag the big circle to move it. **Note that** if you overlay the footprint on a very small image, nothing will appear to have happened. You need at least a 60 arcmin image to comfortably see the footprint, and even then you will probably have to click and drag to see the entire footprint. Consult the [Roman documentation](#)  for specifics on the apertures. Change the color, delete, or add more copies of the Roman footprint from the layers pop-up.

HiPS Images: General Information & Definitions

[HiPS](#)  stands for hierarchical progressive surveys, and these kinds of images are multi-resolution [HEALPix](#)  images (where HEALPix stands for Hierarchical Equal Area isoLatitude Pixelation). (Also see [IVOA docs on HiPS](#) .) In practice, what this means is that you can interact with images of a very large chunk of sky, and as you zoom, the pixel size changes dynamically. HiPS images are fundamentally different than FITS images, and as such, what you can do with the HiPS images are different than what you can do with the FITS images.


The whole point of HiPS images is to provide on-demand resolution changes. Zoom out, and it loads large pixels. Zoom in, and it loads smaller pixels. HiPS images are designed to cover large areas of sky efficiently. If you need to visualize many degrees, this is the image type to use. This is why HiPS images are used in this tool for [coverage images](#).

HiPS images typically have the color and stretch set by the person who originally made them. The color table can be remapped within this tool. But, you cannot, in general, change the stretch of HiPS images with as much flexibility as you can with FITS images. This is why there may be multiple versions of some data sets available.


HiPS maps typically come with a **Multi-Order Coverage map (MOC)**. A [MOC](#)  is a format developed by the International Virtual Observatory Alliance to specify sky regions. In this context, a MOC tells you via a simple boolean yes/no, is there sky coverage from this data set in this region. You can overlay a MOC from one data set onto a completely different data set's HiPS image. That is likely one of the the most common way in which you might encounter MOCs -- overlaying, say, the MOC from survey X onto survey Y's HiPS image to see if there are data from X that overlap with Y.

Coverage Image

When the ZTF Image Service returns search [results](#), one of the tabs it returns on the right hand side is a "coverage image", which is basically a way for it (and you) to keep track of where you are working on the sky, and to show you an overview of the results.



You may have a coverage image like this -- this is a 2MASS HiPS image showing the search results which include 2804 science exposures, 4 reference images, 1 deep reference image, and 2804 difference images. However, they are all more or less on top of each other, so the dark red of the 2804 science exposures dominate the view here. The currently selected row in each of each of tabs on the left (not shown) are rendered as orange in this coverage image. The target of the search is the small yellow reticle in the middle.



Here is a zoom in on a different coverage image -- this has the calculated orbit for Pallas in purple, and in yellow, it has the individual exposures it found that might have observed the asteroid Pallas, given the specified orbital parameters.

You can interact with the coverage image in the same way as you would any other image loaded into this tool.


The thing that makes a coverage image a little bit different, however, is that it can automatically adapt, even beyond what a HiPS image can intrinsically do. The next subsection includes more details about how it can automatically change to accommodate your needs and zoom level.

Upper Left HiPS menus

In the upper left of the coverage image, there are two drop-down menus.



The first drop-down menu looks like this.




There are two sections here.

Under "Data Options", you can change what data are shown.

Change HiPS: Changing HiPS images

The choices made by any given creator of a HiPS image may result in any particular region being saturated or too faint to see. Color stretches are set by the creator of the HiPS map and cannot be changed; color tables can be somewhat changed by this tool, but that may be insufficient for your needs. If the HiPS map as shown does not suit your needs and you wish to change the HiPS image, click on the "HiPS/MOC" menu, and then click "Change HiPS". It brings up this pop-up:



Things to note:

ZTF Help

- To select a new image, click on the row corresponding to the new HiPS image you want, and click "Change HiPS" on the bottom left.
- To cancel without selecting a new image, click "Cancel."
- This is an interactive table, so all the [filtering](#) and [column manipulation](#) tools apply here too. You can filter down the columns to find the image you want to use.
- To learn more about each HiPS map, click on the **i** with the circle in the second column. It will spawn another window with standardized information about the HiPS map.
- By default, it shows HiPS maps corresponding to IRSA data collections. To see a more comprehensive list, unclick the box marked "IRSA Featured."

Add MOC Layer: Adding a MOC Overlay

It is often useful to see what other data are available. Click on the "HiPS/MOC" menu, and then click "Add MOC Layer." It brings up this pop-up:

Add MOC Layer

Search
Use my MOC

☒ Featured MOC

| Coverage (percent) float | Waveband char | Title char | HiPS Order (HEALPix) int | Release (date) char |
|--------------------------------|------------------|---|--------------------------------|---------------------------|
| 8.35 | IR | Herschel PACS (color composition) | 9 | 2019-07-31T11 |
| 79.79 | UV | GALEX GR6 AIS (until March 2014)- Color composition | 8 | 2019-05-05T0 |
| 68.21 | UV | GALEX GR6 AIS (until March 2014)- Far UV | 8 | 2019-05-05T0 |
| 35.62 | Optical | SDSS9 color | 10 | 2019-05-05T0 |
| 1.37 | IR | IRAC1 survey in Healpix | 9 | 2019-05-05T0 |
| 1.37 | IR | IRAC2 survey in Healpix | 9 | 2019-05-05T0 |
| 1.37 | IR | IRAC3 survey in Healpix | 9 | 2019-05-05T0 |
| 1.37 | IR | IRAC4 survey in Healpix | 9 | 2019-05-05T0 |
| 77.08 | Radio | HIPASS | 3 | 2019-05-22T11 |
| 12.7 | Optical | DES-DR1 Y | 11 | 2019-07-05T11 |
| 12.84 | Optical | DES-DR1 g | 11 | 2019-05-23T11 |
| 12.7 | Optical | DES-DR1 i | 11 | 2019-05-23T11 |
| 12.7 | Optical | DES-DR1 r | 11 | 2019-06-04T11 |
| 12.71 | Optical | DES-DR1 z | 11 | 2019-06-11T11 |
| 0.01906 | Optical | HLA-SDSSg : F475W | 13 | 2023-03-09T1 |
| 0.00126 | Optical | HST PHAT - F275W - WFC3/UVIS | 14 | 2019-05-05T0 |
| 82.42 | Radio | NVSS - The NRAO VLA Sky Survey (intensity maps) | 5 | 2019-05-05T0 |
| 78.12 | Optical | PanSTARRS DR1 color (from bands z and g) | 11 | 2019-05-20T0 |
| 97.14 | UV | ROSAT Wide Field Camera Color composition | 3 | 2019-05-20T11 |

Add MOC
Cancel

Things to note:

- Coverage (the first column) is the fraction of the sky covered by that MOC.
- To select a new MOC, click on the row corresponding to the new MOC you want, and click "Add MOC" on the bottom left.
- To cancel without selecting a new image, click "Cancel."
- This is an interactive table, so all the [filtering](#) and [column manipulation](#) tools apply here too. You can filter down the columns to find the image you want to use.
- By default, it shows MOCs likely to be most interesting for IRSA users. To see a more comprehensive list, unclick the box at the top left.

ZTF Help

- If you have your own MOC FITS file, you may upload it via the "Use my MOC" tab on the top center.
- If you try to upload a MOC FITS file via the [upload tab](#), it will behave as if you have uploaded it here.

Under "HiPS to FITS Conversion", you can control whether the viewer will automatically toggle between image types as needed.

By default, the coverage image is most likely a HiPS image. FITS images are best for small regions of the sky, and HiPS images are best for large regions of sky.

Auto Zoom-in to 2MASS K_s FITS:


If you select this, then when you zoom in very close to a target, it will automatically convert to a FITS image when you get close enough.

Switch to 2MASS K_s FITS image:


If you select this, then it will jump directly to a FITS image centered on the currently selected target.

Note that if you swap between HiPS and FITS and back again, it will include a region on the HiPS image that is the footprint of the FITS images you had just loaded. A label appears at the center of that footprint, which may be disconcerting if you are not zoomed out enough to see the region itself. Here is an example, zoomed out so it is more clear what is going on:

ZTF Help



The second drop-down menu looks like this.



There are three sections in this menu.

Orientation

Under "Orientation", you can control whether the coordinates are in Galactic or Equatorial J2000 (RA/Dec). This can be used in conjunction with the image readout and/or the coordinate layer button.

Center Galactic

If you select "Center Galactic", the HiPS image slews to put Galactic North up, the Galactic Center in the center of the field of view, and the Galactic Plane horizontally across your field of view. This is useful if you have been zooming or scrolling around to look at individual sources and need to bring it back to a familiar orientation quickly.

Projection

Under "Projection", you can control whether the display is in Spherical or Aitoff coordinates. Aitoff projection works better for all-sky displays.



ZTF Image Service: Tables


All of the tables in the ZTF Image Service (whether they are catalogs, or the results of a search, or the contents of a FITS header) are interactive tables, and they have the same basic properties, discussed in this section. The specific broad case of [catalogs](#) is in another section.

Contents of page/chapter:

- +[Table Header](#)
- +[Table Columns](#)
- +[Adding Columns](#)
- +[Table Filters](#)
- +[Table Actions: Searches](#)
- +[Row Details](#)
- +[Table Cells](#)
- +[Saving Tables](#)
- +[Table Navigation](#)

Table Header

These interactive tables -- called Firefly tables, after the software that is running here -- all have the same functionality, regardless of the contents of the table. If it looks like this sort of table, you can work with it whether it is a catalog, an image header, a list of images, etc.

If you have loaded a table into a tab and it doesn't take up the whole screen, to see more of the window, grab the divider between the window panes and slide it up/down or over as needed, or use the expand arrow icon () to enlarge the window pane to take up the whole window.

The table is shown exactly as it has been provided to the tool, with all columns as defined by the creator of the table. To understand what each column is, please see the documentation associated with that catalog or table.

The tab (and table) name itself likely indicates its origin. To remove the tab, it is likely that you can click on the "X" on the tab.

Immediately below the tab name, there may be several symbols:



which we now describe, going from left to right along the top of the tab.



The first thing to notice is that (typically) only the first 100 rows of the retrieved catalog (or table) are displayed in the table. In the example here, there are 319 sources that were retrieved as a result of the search, grouped into 4 'pages.' The left/right black arrows plus the page number allow you to navigate among these 'pages' of 100 sources each. Note that the entire set of results (not just the 100 rows you are currently viewing) can be sorted by clicking on any column's name.




Table Actions: Searches

This drop-down has choices to launch new searches, and as such, it has a [separate section below](#).

**Filter**

Filters are complex and powerful enough that they are covered in a [separate section below](#).

**Table as text**

Clicking on this changes the table display into a fixed-width text display. The icon then changes to  click this again to return to the default table view.

**Save table**

This is how you can save the table. It has a [separate section below](#).

**Add a column**

This icon adds a new column to the table. This has a [separate section below](#).

**Info link**

You may or may not see this icon. This is an "information" button and, if it exists, it may provide additional information about the table. It could have information about the job that was used to retrieve it:

Table Info

×


Job Info

Table Metadata

Phase: COMPLETED

Start Time: 2024-03-27T22:36:00.976019398Z

End Time: 2024-03-27T22:36:03.803012715Z

Service  https://irsatest.ipac.caltech.edu/cgi-bin/Gator/nph-query?outfmt=1&catalog=allwise_p3as_psd&spatial=

URL:

Summary: 319 rows found

ID: 1711578960976

?

where the direct link to the job is given there (and can be copied by clicking on the clipboard, ready to be pasted into a helpdesk query, for example), with a job id as shown. It could also just have information about the table metadata:

Table Info

Table Metadata

Table Meta

DATABASE: AllWISE Source Catalog (aliwise_p3as_psd)
DATETIME: 2024-03-27 15:36:01
EQUINOX: J2000
fixlen: T
ORIGIN: IPAC Infrared Science Archive (IRSA), Caltech/JPL
RowsRetrieved: 319
SIMULATED_TABLE: n
SKYAREA: polygon(270.99828 -24.44978, 270.84541 -24.44957, 270.84571 -24.31057, 270.99842 -24.31078)
SQL: 'WHERE (no constraints)
SQL: SELECT (45 column names follow in next row.)
StatusFile: /workspace/TMP_9GL701_10732/Gator/lrsa/10732/log.10732.html

where the information about this table includes information about the query that produced it.



Row details

You may or may not see this icon. This is how you get more information about the currently-selected row. It has a [separate section below](#).



Table options

Clicking on this icon brings up options for the table, e.g., how many rows are displayed per page, which columns are shown, metadata about each column if available, whether units and data types are shown at the top of the column, shown here:

Table Options

Show/Hide: ☒ Units ☒ Data Type ☒ Filters Page Size: 100

| Column Options | Advanced Filter | name | filter | format | null_string | type | units |
|-------------------------------------|-----------------|-------------|--------|--------|-------------|--------|------------------------|
| <input checked="" type="checkbox"/> | | name | | | | | |
| <input checked="" type="checkbox"/> | | designation | | | null | char | WISE source designati |
| <input checked="" type="checkbox"/> | | ra | | F7 | null | double | right ascension (J2000 |
| <input checked="" type="checkbox"/> | | dec | | F7 | null | double | declination (J2000) (d |
| <input checked="" type="checkbox"/> | | clon | | | null | char | |
| <input checked="" type="checkbox"/> | | clat | | | null | char | |

By default, it is often but not always the case that all columns are shown. To show or hide columns, select the tickbox in each given row. The default page size is 100 rows. Note that expanding the page size to numbers much greater than 100 may result in a substantial performance degradation (e.g., your browser will appear to freeze or not appear to be doing anything while it manages and renders the large table). See the [Filters section below](#) for more things to do from the table options pop-up.



Expand

Clicking on this expands the catalog window pane to take up the entire browser window. To return to the prior view, click on "Close" in the upper left.



Help

The last option on the top of the catalog tab may be a context-sensitive help marker, which should bring you to this online help.

Table Columns

Depending on what you did to display a table, the columns that are shown may be in easily-human-readable form, or may reflect column names used within the individual catalog. Please consult the detailed documentation associated with your specific table if the headers are not clear to you.

The table is shown exactly as it appears in the corresponding database (or as it appeared on your disk), with all columns as defined for that catalog. To understand what each column is, please see the documentation associated with that catalog. (For IRSA catalogs, this documentation is available via navigating through the IRSA website.)

Clicking on the column names sorts the table by that column; clicking once sorts in ascending order, clicking a second time sorts in descending order, and clicking a third time returns the table to the original order. Small arrows appear next to the column names to remind you if the column is sorted in ascending or descending order. When you do a single-position search on catalogs, depending on how you do it, it could be that two new columns are appended to the end of the catalog as it is returned to you. These columns are:

- dist - the distance between the source in question and the location you specified
- angle - the position angle between the target position you requested and the object it found (degrees E of N)


When you do a multi-position search on catalogs, you could have three new columns prepended to the catalog as it is returned to you. These columns are :

- cntr_01 - the target position you requested
- dist_x - the distance between the target position you requested and the object it found
- pang_x - the position angle between the target position you requested and the object it found (degrees E of N)


These additional columns can help you assess if the target it found is the target that should be matched to the position you requested.


It could be that, when you do a multi-position search on catalogs, you have an option for "one-to-one matching". If that is selected, the line (and only one line) of output is included for each line of input. It chooses the closest source within the radius you specify, or if there is no match, it adds a line indicating no match.

Tips and Troubleshooting



- You can hide or display columns; click on the gears () to get to the table options, and tick the box corresponding to the row you want to hide or show.
- If you are constructing and loading your own catalog where you don't specify the formatting, the tool tries to guess the formatting of the column based on the first row's values. Therefore, if you have a value in the first row that happens to be a string like "null" where the rest of the column isn't like that, or happens to have only one decimal place where the rest of the column has 2 or more, it will guess incorrectly and format the other rows just like the first one. Try editing your catalog file to put the most general case as the first row.

Adding Columns

This icon  allows you to add a new column to your catalog. When you click on it, it brings up this pop-up window:




This window asks for:

- *Name* of the column (required) -- it cannot have special characters like a minus sign or a percent symbol; you can only use letters, numbers, and underscores.
- *Mode* "Enter expression" or "Use preset function" -- options shown here correspond to "Enter expression" options; the preset function options are included in the last bullet here.
- *Expression* (required) -- using basic SQL operators, you can manipulate columns to create the new column. (See more on this below.)
- *Data Type* -- specify if your new column is a double precision floating point ("double"), a long integer ("long"), or a string ("char").
- *Precision* -- if you have selected "double" for data type, select how many decimal places your new column should display. For example, if you want the numbers to display as 1.23, enter "F2".
- *Units* -- specify the units of your new column. For more information, see [IVOA documentation](#) .
- *UCD*, or unified content descriptor -- for VO compliance, add this for your new column. For more information, see [IVOA documentation](#) .
- *Description* -- add a description for your new column.
- *Select a preset* -- if you select "Use preset function", you can choose (a) "set filtered rows to 'true' and the rest to 'false'", (b) "set selected rows to 'true' and the rest to 'false'", or (c) "number rows in current sort order". These options are useful for tagging items you have selected in myriad ways (from plots, images, complicated filters), or ordered in complicated ways. For example, if you have constructed a complicated filter, then you can create a column that is true for the selected rows; if you cancel the complicated filter, you can then easily recreate the complicated filter by simply filtering on your newly created column.

In order to construct the expression for your new column, your input should follow the syntax of an SQL expression. If you click on the magnifying glass next to the form input, you get a pop-up window that can help you construct an expression; click "apply" to apply the expression.

You need to use the column names exactly as they appear in your catalog. Supported operators are: +, -, *, /, =, >, <, >=, <=, !=, LIKE, IN, IS NULL, IS NOT NULL. You may use functions as well; for a list of all available

functions, [see here](#) . Some examples include:

- "w3mpro" - "w4mpro"
- $\sqrt{\text{power}(\text{"w3sigmpro"},2) + \text{power}(\text{"w4sigmpro"},2)}$
- $(\text{"ra"} - 82.0158188) * \cos(\text{radians}(\text{"dec"}))$
- $\text{"phot_g_mean_mag"} - (5 * \log_{10}(1000 / \text{"parallax"}) - 5)$

Tips and Troubleshooting




- When you create a new column that is calculated from other columns, it is created statically. That is, it is not dynamically updated like a spreadsheet, but calculated once and left alone after that.
- When you create a new column, the header of the new column is red to let you know that the column is not present in the original catalog.
- When you save the catalog, the header of the saved catalog indicates that you have added a column. When you load the catalog back into the tool, the header of the new column is still red.
- You can edit or delete columns after you have created them; click on the gears () to get to the table options, and then click on the edit icon to bring up a dialog box to edit or delete the column.
- You can hide columns; click on the gears () to get to the table options, and tick the box corresponding to the row you want to hide or show.
- If you create a new column that turns a floating point column into an integer with the "FLOOR()" function, you need to be sure to set the resulting column type to "long". For example, if you have data covering several days or years, and you have a column that is a floating-point MJD, you can convert it into an integer, e.g., via `FLOOR(mjd)` for days or `FLOOR(mjd/365.24)` for years, then you can use the drop-down filter menu for the new column to quickly compare different time ranges. But, the new column must be an integer (e.g., "long") in order for this to work properly.
- If you need to, say, take the square root of a column that occasionally has a negative number, and you want it to attempt to handle this in a physically reasonable manner, you can construct expressions like this for a column named 'col' that has some positive and some negative numbers:
`if("col">=0,sqrt("col"),-sqrt("-col"))`

Table Filters



Filters are a *very* powerful way of exploring the table full of search results. Click on this icon  in order to start the process of adding filters. A text entry box appears above each of the current catalog columns, with a small version of the filter icon corresponding to that row on the far left. You can type operators and values in these boxes -- hit return or tab after typing or click in another box to implement the filter.

Example: From a catalog, show only those sources with declination above a certain value (say, 31 degrees), type "> 31" in the box at the top of the "dec" column. Or, if you have retrieved a WISE catalog and would like to only view the objects with a W1 (3.4 micron) profile-fitted magnitude less than 6 magnitudes, in the box at the top of the 'w1mpro' column, type "< 6" in the form.

| Type | Ba |
|--|----|
| <div>clear</div> <div> <input checked="" type="checkbox"/> all-sky <input checked="" type="checkbox"/> compilation <input type="checkbox"/> extragalactic <input type="checkbox"/> galactic <input type="checkbox"/> simulated </div> <div>Apply</div> | |

For columns (fields) with a limited set of choices, on the right edge of the text entry box, an arrow appears; click on it to get a drop-down from which you can select the available choices. To implement the filter, make the choices, and click "Apply" when you are done. Click "clear" in the top of the drop-down menu to remove that filter.

After you impose a filter, then the number of rows in the table is restricted according to the rules you have specified, and the "filters" icon on the top right of the catalog pane has changed to remind you that there has

been a filter applied, in this case four filters: . To clear the filters, click on the cancel filters icon (which also appears after you impose filters): .

Filters can be used in combination. Note that the filters between columns are logically "AND"ed together, but filters within the same column can be logically "AND"ed or "OR"ed together; examples are below.

The available logical operators are :

- = which means 'equal to' (exactly!), e.g., the parameter on which you are querying (the column headers as shown) is exactly equal to this value you are specifying.
- > which means 'greater than'
- < which mean 'less than'
- != which means 'not equal to' (exactly!)
- >= which means 'greater than or equal to'
- <= which means 'less than or equal to'
- IN which means 'included within this list', e.g., the parameter on which you are querying is included within the list you are specifying (if the column filter is free-form text, type "value1,value2" and it will give you rows that have value1 or value2).
- LIKE which means 'resembles the text that is entered', e.g., the text resembles the text that you type in the box.
- IS which effectively is the same as =
- IS NOT which effectively is the same as !=

Examples:

- Retain rows for which a certain parameter is not an empty string: !="
- Retain rows for which a certain parameter is not NULL and is larger than 1.234: > 1.234 and IS NOT NULL
- Retain rows that have values between -0.5 and 1.25: > -05 and < 1.25
- Retain rows with a parameter greater than one value or exactly not equal to another value: > 12345 or != 3000
- Retain rows with a parameter equal to one of the values in a list: IN a,b,c,d

ZTF Help

You can also interactively impose filters from [plots](#) from a catalog. Moreover, all the same operators that are available for making [plots](#) can be applied in filters. In both cases, see the plots section for more information.

You may also be able to select rows one at a time via the far left column and then filter that down. Example: Retrieve a catalog of any sort. Select rows by ticking the box on the far left, say, every other row out of the first 12. Click on the filter icon on the top of the column. The filter is imposed to only include the 6 rows you selected.


If you click on the table options icon () , you get a pop-up that includes a place to filter columns. Here is an example of the table columns for a WISE catalog that has been filtered to just have SNR>10 for each of the four bands:

Table Options

Show/Hide: ☒ Units ☒ Data Type ☒ Filters Page Size: 100

| Column Options | Advanced Filter | | | | | | |
|---|----------------------|--------|-------------|--------|--------|--|---|
| <input checked="" type="checkbox"/> name | <input type="text"/> | format | null_string | type | units | | description |
| <input checked="" type="checkbox"/> designation | | | null | char | | | WISE source designation |
| <input checked="" type="checkbox"/> ra | | F7 | null | double | deg | | right ascension (J2000) (deg) |
| <input checked="" type="checkbox"/> dec | | F7 | null | double | deg | | declination (J2000) (deg) |
| <input checked="" type="checkbox"/> clon | | | null | char | | | |
| <input checked="" type="checkbox"/> clat | | | null | char | | | |
| <input checked="" type="checkbox"/> sigra | | F4 | null | double | arcsec | | uncertainty in RA (arcsec) |
| <input checked="" type="checkbox"/> sigdec | | F4 | null | double | arcsec | | uncertainty in DEC (arcsec) |
| <input checked="" type="checkbox"/> sigradec | | F4 | null | double | arcsec | | cross-term of RA and Dec uncertainties (arcsec) |
| <input checked="" type="checkbox"/> w1mpro | | F3 | null | double | mag | | instrumental profile-fit photometry magnitude, band 1 |
| <input checked="" type="checkbox"/> w1sigmpro | | F3 | null | double | mag | | instrumental profile-fit photometry flux uncertainty |
| <input checked="" type="checkbox"/> w1snr | > 10 | F1 | null | double | | | instrumental profile-fit photometry S/N ratio, band 1 |
| <input checked="" type="checkbox"/> w1rchi2 | | E3 | null | double | | | instrumental profile-fit photometry reduced chi^2, band 1 |
| <input checked="" type="checkbox"/> w2mpro | | F3 | null | double | mag | | instrumental profile-fit photometry magnitude, band 2 |
| <input checked="" type="checkbox"/> w2sigmpro | | F3 | null | double | mag | | instrumental profile-fit photometry flux uncertainty |
| <input checked="" type="checkbox"/> w2snr | > 10 | F1 | null | double | | | instrumental profile-fit photometry S/N ratio, band 2 |
| <input checked="" type="checkbox"/> w2rchi2 | | E3 | null | double | | | instrumental profile-fit photometry reduced chi^2, band 2 |
| <input checked="" type="checkbox"/> w3mpro | | F3 | null | double | mag | | instrumental profile-fit photometry magnitude, band 3 |
| <input checked="" type="checkbox"/> w3sigmpro | | F3 | null | double | mag | | instrumental profile-fit photometry flux uncertainty |
| <input checked="" type="checkbox"/> w3snr | > 10 | F1 | null | double | | | instrumental profile-fit photometry S/N ratio, band 3 |
| <input checked="" type="checkbox"/> w3rchi2 | | E3 | null | double | | | instrumental profile-fit photometry reduced chi^2, band 3 |
| <input checked="" type="checkbox"/> w4mpro | | F3 | null | double | mag | | instrumental profile-fit photometry magnitude, band 4 |
| <input checked="" type="checkbox"/> w4sigmpro | | F3 | null | double | mag | | instrumental profile-fit photometry flux uncertainty |
| <input checked="" type="checkbox"/> w4snr | > 10 | F1 | null | double | | | instrumental profile-fit photometry S/N ratio, band 4 |
| <input checked="" type="checkbox"/> w4rchi2 | | E3 | null | double | | | instrumental profile-fit photometry reduced chi^2, band 4 |
| <input checked="" type="checkbox"/> nb | | | null | int | | | number of blend components used in each fit |
| <input checked="" type="checkbox"/> na | | | null | int | | | active deblend flag (=1 if actively deblended) |
| <input checked="" type="checkbox"/> w1sat | | F3 | null | double | | | fraction of pixels affected by saturation, band 1 |
| <input checked="" type="checkbox"/> w2sat | | F3 | null | double | | | fraction of pixels affected by saturation, band 2 |

Column selection will apply to future searches of this table in this session.

You can type in constraints in the filter box in much the same way as you can from the catalog itself; note that the column description is included here, which may make this way of setting filters more useful when working with a new (to you) catalog.

The second tab is the advanced filter interface:

Table Options

Show/Hide: ☒ Units ☒ Data Type ☒ Filters Page Size: 100

Column Options **Advanced Filter**

Columns (sorted)

- cc_flags (char)
- clat (char)
- clon (char)
- dec (double)
- designation (char)
- ext_flg (int)
- foo (double)
- moon_jev (char)
- na (int)
- nb (int)
- ph_qual (char)
- pmdec (int)
- pmra (int)
- ra (double)
- sigdec (double)
- sigpmdec (int)
- sigpmra (int)
- sigra (double)
- sigradec (double)
- var_flg (char)
- w1m (int)
- w1mpro (double)
- w1nm (int)
- w1rch2 (double)
- w1sat (double)
- w1sigmpro (double)
- w1snr (double)
- w2m (int)
- w2mpro (double)
- w2nm (int)
- w2rch2 (double)
- w2sat (double)
- w2sigmpro (double)

Current Constraints: [Clear](#)

("w1snr" > 10) AND ("w2snr" > 10) AND ("w3snr" > 10) AND ("w4snr" > 10)

Additional Constraints (SQL): [Apply](#) with: ☒ AND ☐ OR

e.g., "ra" > 180 AND "ra" < 185

Usage

Input should follow the syntax of an SQL WHERE clause.
Click on a Column name to insert the name into the SQL Filter input box.
Standard SQL-like operators can be used where applicable.
Supported operators are:
+, -, *, /, %, >, <, >=, <=, !=, LIKE, IN, IS NULL, IS NOT NULL

You may use functions as well. A few of the common functions are listed below.
For a list of all available functions, click [here](#).

String functions:
CONCAT(s1,s2[,...]) INSTR(s,pattern[,offset]) LENGTH(s) SUBSTR(s,offset,length)

Numeric functions:
LOG10(x)/LG(x) LN(x)/LOG(x) DEGREES(x) ABS(x) COS(x) SIN(x) TAN(x) POWER(x,y)

Sample Filters

("ra" > 185 AND "ra" < 185.1) OR ("dec" > 15 AND "dec" < 15.1) AND "band" IN (1,2)
POWER("v",2) / POWER("err",2) > 4 AND "band" = 3

Column selection will apply to future searches of this table in this session.

[Close](#) [Reset column selection](#) [Remove all filters](#)

Here, the columns are listed alphabetically on the left, the constraints you have imposed are in the "current constraints" box, and you can apply additional SQL constraints via the free-form text box. Hints for syntax are given below the entry box. This window can be resized such that you can see the whole set of hints and imposed filters. Note that in this interface, column headers must be enclosed within double quotes.

Cancelling filters

After you impose a filter, then the "filters" icon on the top right of the catalog pane has changed to remind you

that there has been a filter applied, in this case just one filter:



To clear all the filters at once, click on the

cancel filters icon (which also appears after you impose filters):



Tips and Troubleshooting

- If you impose logically inconsistent restrictions such as "exposure_time > 160" and "exposure_time < 100" (">160;<100" in the filter box for a column called "exposure_time"), no data will result, because no data are (can be) both less than 160 seconds long and greater than 100 seconds long at the same time. However, "exposure_time > 160 or < 100" works just fine (">160 or <100" in the filter box for the column "exposure-time").
- If you impose nonsensical filters (like using a letter where a number should be, like "w1snr < f") then it will let you know that something has gone really wrong, and let you go back to fix it.
- However, a filter like "ph_qual < f" could be valid -- if the column with which you are working is a string, then a string is a valid filter. It is case-insensitive. For the ph_qual column in the 2MASS catalog, the values are always three letters, such as AAA or ABA or CUU. A filter like "ph_qual < f" will operate as if you have alphabetized the list. Any string that starts with A comes before F and so will be retained. If you do "ph_qual < BBB" then AAA will be left in, but so will "BAU", because alphabetically, BAU precedes BBB.
- If you impose filters from a plot, it can manifest as several filters on the catalog, e.g., one for each side of the square you have drawn on the plot. If you want to remove, say, just one of the four filters (rather than all of them by cancelling all filters), you can do so from the table options pop-up.

- If you want to copy all of the "current constraints", even if the entire field is not visible to you, you can click on the clipboard icon to copy the entire string, and then paste it into another field or application to see what it is.
- If you are choosing filters from a list of terms, cancelling those filters might not work the way it cavalierly seems like it should. If a down arrow appears next to the filter box, then a list of options you can select is available. Tick the boxes you want, and click "Apply" to apply the filter. Now, if you want to change the filter, click the down arrow, select different options, and click "Apply" again to re-impose the new filter. To remove the filter, you have to treat it like you would when applying a modified second filter -- unselect the choices, or hit 'clear', and **then hit Apply again**. If you deselect the choices and then click elsewhere in the window without hitting clear, your actions are interpreted as 'cancel without doing anything' as opposed to 'impose the new filter I just set' (which is 'cancel all filters'). When you are resetting the filter to be 'select nothing', it is treating that as a new filter setting, so you need to set up that filter and click 'Apply' in order for it to understand.
- If you impose filters from a plot, image, or table, you can cancel them from a plot, image, or table. That is, if you impose filters from a plot, and different additional filters from the image, when you click the 'cancel filters' icon from the table, *all* the filters are canceled at once. If you have filters imposed from multiple places, clicking on 'cancel filters' doesn't cancel just the filters imposed from that place; it cancels all of them. If you want to be able to reconstruct a complicated set of filters, though, you can add a column to your table that is one of the preset functions -- set it to true if the row is filtered. Then you can cancel all your filters at any time but you can easily recover the filtered data by filtering on that one new column.

Table Actions



This icon implements a new search, an 'action', on the currently selected row of the table. When you click on it, it reveals a drop-down:

Cone and Point Actions based on center: 67.910294, 18.232774 Equ J2000

Search NED at row with 5" radius
 Search Simbad at row with 5" radius
 Go to and Search Simbad at row with 5" radius
 Search TAP at row

For this example, the selected row is 67.910294, 18.232774 in J2000 decimal degrees. From this drop-down, you can:

- Launch a NED search at this position with a 5 arcsecond radius ([more information about NED searches](#))
- Launch a Simbad search at this position with a 5 arcsecond radius, and put the results in a table here in the tool
- Launch a Simbad search at this position with a 5 arcsecond radius, but start another browser window or tab at Simbad with the results
- Launch a TAP cone search at this position ([more information about TAP searches](#))

Any of these searches (except the search that launches another browser window with the Simbad results) places the search results into this same tool.

Row Details



This icon is not always available. When it is available, when you click on it, a new pop-up window appears with information about the row you have selected:

Row Details: irsa_catalog_search_results.tbl

(1 - 51 of 51)

| <input type="checkbox"/> | Name char | Value char | Units char | Type char |
|--------------------------|--------------|---------------------|---------------|--------------|
| <input type="checkbox"/> | cntr_01 | 1 | | long |
| <input type="checkbox"/> | dist_x | 0.602755 | arcsec | double |
| <input type="checkbox"/> | pang_x | 122.272629 | deg | double |
| <input type="checkbox"/> | objname_01 | HD787 | | char |
| <input type="checkbox"/> | ra_01 | 3.0415960000E+0 | | double |
| <input type="checkbox"/> | dec_01 | -1.7938278000E+1 | | double |
| <input type="checkbox"/> | designation | J001210.01-175618.1 | | char |
| <input type="checkbox"/> | ra | 3.0417448 | deg | double |
| <input type="checkbox"/> | dec | -17.9383674 | deg | double |
| <input type="checkbox"/> | sigra | 0.0167 | arcsec | double |
| <input type="checkbox"/> | sigdec | 0.0157 | arcsec | double |
| <input type="checkbox"/> | sigradec | -0.0050 | arcsec | double |
| <input type="checkbox"/> | w1mpro | -0.781 | mag | double |
| <input type="checkbox"/> | w1sigmpro | null | mag | double |
| <input type="checkbox"/> | w1snr | 0.3 | | double |
| <input type="checkbox"/> | w1rchi2 | 2.183E-4 | | double |
| <input type="checkbox"/> | w2mpro | -0.011 | mag | double |
| <input type="checkbox"/> | w2siampro | null | mag | double |

In some tools, this content appears as additional tab elsewhere in the tool (not in the table pane, but often viewable at the same time as the table itself), as an additional tab called "Details."

In either incarnation, this information is sometimes called a "property sheet."

This table consists of each of the columns of the retrieved catalog with additional information about each field where available. (Not every catalog may have this information available.) For additional information, please consult the full documentation that accompanies the catalog.

Note that if you leave the pop-up or tab open as you select different rows in your main table (or catalog), it is dynamically updated.

Tips and Troubleshooting

- The property sheet is a more expanded, vertical view of the information shown in a row of a catalog, along with documentation of the catalog columns. If you think of the main table (catalog) view as a single row that you have to scroll left and right to see in its entirety, this view is sort of an orthogonal

view, where you have all of the same contents of that row but shown as its own table, with the full header description, if available, and you can scroll up and down to see the entire contents (as opposed to left-right). *This is sometimes a more user-friendly way to view any given row.*

- Because you can sort/filter the data in the property sheet, you can restrict what values are shown. Those filters are respected as you page through your main table.
- When changing rows in the main table, the property sheet scrolls to preserve the visibility of whatever row in the details tab is highlighted. If you scroll down in the property sheet *without changing the highlight*, when you change rows in the main table, because the first row in any table is always highlighted by default, the property sheet will scroll back to the top.

Table Cells

Some cell values may be too long for the cell space. If that is the case, an ellipsis ("...") will appear in the cell as you mouse over it:

| access_url | access |
|--|----------------------|
| char | c |
| <input type="text"/> | <input type="text"/> |
| https://irsa.ipac.caltech.edu/dat: ... | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |

If you click on the ellipsis, you get a drop-down menu:

| access_url | access_fo |
|--|----------------------|
| char | char |
| <input type="text"/> | <input type="text"/> |
| https://irsa.ipac.caltech.edu/dat: ... | image/fits |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |
| https://irsa.ipac.caltech.edu/data/Sf | image/fi |

Copy to clipboard

View as plain text

from which you can choose to copy the cell value or view it in a pop-up window.

If you view it in a pop-up window, it will attempt to format it in a readable fashion:




which, for most cells, will be functionally indistinguishable from no special formatting. It will only matter for very complicated cells.

Saving Tables

Click on the diskette icon () , if available, to save the table.

You obtain this pop-up:




The dialog box titled "Save table" contains the following elements:

- File format:** A dropdown menu showing "IPAC Table (.tbl)".
- File name:** A text input field containing "table_WISE-allwise_p3as_psd-Polygon.tbl".
- File location:** Two radio buttons: "Local File" (selected) and "Workspace".
- Save options:** Two radio buttons: "Save table as displayed" (selected) and "Save table as originally retrieved".
- Text description:** "The table will be saved in its current state, including its sorting order and derived columns, but excluding rows not accepted by any filters applied, as well as any hidden columns."
- Buttons:** "Save" and "Cancel".
- Help icon:** A question mark icon in the bottom right corner.

You have several choices to make. In order, they are:


File format




You can save the table in a variety of formats:



The dropdown menu shows the following options:

- IPAC Table (.tbl)
- IPAC Table (.tbl)
- Comma-separated values (.csv)
- Tab-separated values (.tsv)
- VOTable - TABLEDATA (.vot)
- VOTable - BINARY2 (.vot)
- VOTable - FITS (.vot)
- Parquet file with VOTable metadata (.parquet)
- Region (.reg)


It defaults to saving it as an [IPAC table file](#) , which is basically ASCII text with headers explaining the type of data in each column, separated by vertical bars.

Other formats include comma-separated values (csv, suitable for, e.g., Excel), tab-separated values (tsv), and three different versions of [VO tables](#) . You can save the file in [parquet file format](#) , which is a highly efficient, compressed, column-oriented format for tabular data that has been adopted by many recent wide area survey projects. You can also save the file in [DS9 Regions file format](#) . The advantage of saving it here as a regions file (as opposed to from the [visualization](#)) is that this way, the entire catalog is guaranteed to be saved.

File name

The tool tries to make a guess at a sensible filename. Feel free to change it to something that makes sense to you.

File location

You may save your file to a local file (on your disk) or, if you are [logged in](#), in the [IRSA Workspace](#) .

Modifications to the table

Depending on what you have been doing to the table at this point, you may have [filtered](#) or [added columns](#). If you want to save the table as it is currently displayed, with all filters as imposed and any columns hidden, and any added columns as shown, select "Save table as displayed." If you want to save the original table, with all rows and the original columns intact, choose "Save table as originally retrieved."


Table Navigation

At any time, you can move among tables by just clicking on the tab name. But, with the ability to [extract data](#) from images comes the ability to rather quickly drown in tables. There is a way to navigate among a lot of table tabs that have accumulated.


This is probably best explained via an example. Here, I have tabs showing that I have [extracted](#) several lines, drills, and points from my images:



On the far right of the collection of tabs, at the top right of the table pane, I have a downward pointing arrow. When I click on this, I get a drop-down:



This drop-down shows that the tab marked "Points 12" is in the foreground (it is shaded yellow) and this drop-down has a filter box at the top. That filter box at the top works just like the filters discussed [above](#), so if I want to find the tabs with the extracted lines, I can type "line" in the box, and it will filter down the list, leaving only those tabs with "line" in the name:



Then, from there, I can select the tab I want to bring to the foreground. (When I select a tab to bring to the foreground, that tab is also in the foreground for plotting.)

In this fashion, I can navigate easily among many tabs that are open at the same time, even if I have so many tabs that their headers are not completely shown.

ZTF Image Service: Catalogs

Catalogs are a special case of [tables](#); the basic functionality of tables is covered in the [Tables section](#). You can choose from any of a wide variety of catalogs to load for overlaying on your [visualized data](#). Catalogs derived from the ZTF products are also available. Plotting catalogs is covered in the [Plots section](#).


Contents of page/chapter:

- +[Introduction](#)
- +[Catalog Upload](#)
- +[IRSA Catalogs](#) -- Searching for catalogs from IRSA
- +[Interacting with Catalogs](#)
- +[Hierarchical Catalog Display](#)
- +[Details Tab](#) -- More information about the columns

Introduction


There are several different ways to get catalogs into the ZTF Image Service. You can retrieve them via your [initial search](#), or via any of several blue tabs at the top of the page after your initial search.


This chapter focuses on the most local and straightforward of a few of those additional blue tabs.

When you click on the "hamburger" in the upper left , it pulls open a "drawer" from the left hand side which enables you to [add or remove tabs](#) from the row of blue tabs on the top of your window. You can add (or remove) "Catalog Upload", and also, under "IRSA search tabs," "Catalogs." The other catalog searches accessible from the "drawer" are covered in [another chapter](#).

Catalog Upload



When you activate the "Catalog Upload" tab, you get this screen:



You may upload a file from disk (you can use the system browser to identify the file, or drag-and-drop them into this window), from the web via a URL, or from the [IRSA Workspace](#) . Click "Load" in the lower left to actually load the file.

The file can be in any of a number of formats, which we now briefly describe.

IPAC table format (*.tbl)

[IPAC table format](#)  is plain text with a particular formatting. IRSA has a [table reformatting and validation service](#)  which may be helpful, or you can download just about any catalog you find

through IRSA, and mimic that format.


If you want it recognized as a catalog, your table file **MUST** have RA and Dec values, and unless it is specified, it assumes J2000. (See also "[tips and troubleshooting](#)", below.)

You can add a "SYMBOL" parameter to change the shape (X, SQUARE, CROSS, EMP_CROSS, DIAMOND, DOT) of catalog marks, e.g.:

```
\SYMBOL = X
```

You can add a "DEFAULT_COLOR" parameter to assign a CSS color name or a HEX value to catalog marks, e.g., either of these two:

```
\DEFAULT_COLOR = lightcyan
\DEFAULT_COLOR = #00FF00
```

You can find the [CSS color code or the CSS color HEX values](#)  online.


Comma-separated values (CSV) format (*.csv)

CSV format is often accepted by spreadsheet programs, and most spreadsheet programs can output CSV. It is plain text, with values for each column separated by commas.


Tab-separated values (TSV) format (*.tsv)

TSV format is sometimes accepted (or generated) by spreadsheet programs, and sometimes in tabular data downloaded from journal articles from the 90s. It is plain text, with values for each column separated by tab characters.

VOTable (*.vot)

Virtual Observatory (VO) tables are a special case of XML tables. (All VO Tables are XML but not all XML are VO Tables.) It is a format developed by the International Virtual Observatory Alliance (more information [here](#) ). XML tables initially look to the human eye like it might be HTML, but they are easier to parse with code. There are packages in astropy that handle VO Tables.

Parquet (*.parquet)

[Parquet file format](#)  is a highly efficient, compressed, column-oriented format for tabular data that has been adopted by many recent wide area survey projects. It can enable faster searching for large tables. There are packages in astropy that handle parquet files.

FITS files (*.fits)

FITS tables can be loaded into this tool. Note that this tool is flexible enough to handle multiple header data units (HDUs), so that you can upload a FITS file that has both images and tables. The ZTF Image Service will only let you load tables, however.

Nearly every file you load will result in a preview of the file you have uploaded. The [tables](#) are then shown and, if [catalogs](#), interacted with in the same way as the other catalogs described here.

Tips and Troubleshooting

- If you would like to have your catalog overlaid on an image, it needs to have RA and Dec columns. If the tool doesn't seem to recognize your RA and Dec columns, check your formatting, or try headers of "ra" instead of "RA" and "dec" instead of "DEC" or "Dec". If you have columns like "_RA2000" and "_DE2000", it's going to be confused.
- Unless specified, the tool assumes any coordinates you give it are J2000.
- If there are no discernible positions in the uploaded file, it will still let you plot columns from the file after you've loaded it; it just can't overlay things on images in that case.

- This interface looks a lot like the file upload window that is available in other tools such as [IRSA Viewer](#), but if you try to upload things that aren't catalogs here, it will give you an error.

IRSA Catalogs -- Searching for catalogs at IRSA

Select Project: WISE

Select Catalog: AllWISE Database

AllWISE Source Catalog
Rows: 747634026 Cols: 334 [info](#) [Column Def](#)

AllWISE Multiepoch Photometry Table
Rows: 42759337365 Cols: 48 [info](#) [Column Def](#)

AllWISE Reject Table
Rows: 428787253 Cols: 334 [info](#) [Column Def](#)

AllWISE Atlas Metadata Table
Rows: 18240 Cols: 349 [info](#) [Column Def](#)

AllWISE Frame Cross-Reference Table
Rows: 21208389 Cols: 6 [info](#) [Column Def](#)

AllWISE Atlas Inventory Table

Search Method: Cone

Coordinates or Object Name [Try NED then Simbad](#)

Examples: m81 ngc 18 12.34 34.89 46.53 -0.251 gal
19h17m32s 11d58m02s equ J2000 12.3 8.5 b1950 J140258.51+542318.3

Radius: 10 arcseconds

Valid range between: 1" and 3600"

Table Selection: Long form [Reset](#)

| | name | constraints | description | units | indx | db |
|-------------------------------------|-------------|-------------|--|--------|------|-------|
| <input checked="" type="checkbox"/> | designation | | WISE source designation | | n | varcl |
| <input checked="" type="checkbox"/> | ra | | right ascension (J2000) | deg | n | numl |
| <input checked="" type="checkbox"/> | dec | | declination (J2000) | deg | y | numl |
| <input checked="" type="checkbox"/> | sigra | | uncertainty in RA | arcsec | n | numl |
| <input checked="" type="checkbox"/> | sigdec | | uncertainty in DEC | arcsec | n | numl |
| <input checked="" type="checkbox"/> | sigradec | | cross-term of RA and Dec uncertainties | arcsec | n | numl |

Add additional constraints here (SQL)

Enter SQL additional constraints here `ra>102.3 and ra<112.3 and dec<-5.5 and dec> -15.5(source_id_mf = '1861p075_ac51-002577')`

[Search](#)

The upper left quadrant of this window is where you specify which catalog you want to search. To change catalogs, first select the "project" under which they are housed at IRSA, such as 2MASS, IRAS, WISE, MSX, etc. The available choices underneath that change according to the project you have selected. A short description is provided for each of the catalogs, with links for more information (including definitions of the sometimes cryptic column names); an example is here:

AllWISE Source Catalog
Rows: 747634026 Cols: 334 [info](#) [Column Def](#)

AllWISE Multiepoch Photometry Table
Rows: 42759337365 Cols: 48 [info](#) [Column Def](#)

AllWISE Reject Table
Rows: 428787253 Cols: 334 [info](#) [Column Def](#)

AllWISE Atlas Metadata Table
Rows: 18240 Cols: 349 [info](#) [Column Def](#)

AllWISE Frame Cross-Reference Table
Rows: 21208389 Cols: 6 [info](#) [Column Def](#)

AllWISE Atlas Inventory Table

ZTF Help

The upper right quadrant of this window is where you specify the target (the position is sometimes pre-filled with its best guess as to what you want) and the search method (cone, elliptical, box, polygon, multi-object, all-sky), and the parameters that go with that search method (e.g., the radius of the cone). The parameters for each of these searches change dynamically as you select search options, which we describe next.

Tips and Troubleshooting: Pick your units from the drop-down first, and then enter a number; if you enter a number and then select from the drop-down, it will convert your number from the old units to the new units. There are both upper and lower limits to your search radius; it will tell you if you request something too big or too small. Note that these limits are catalog-dependent.

Cone search:

The screenshot shows the 'Cone' search method selected. The search area is labeled 'Coordinates or Object Name' with a dropdown menu set to 'Try NED then Simbad'. Below this, a list of examples is provided: 'm81', 'ngc 18', '12.34 34.89', '46.53 -0.251 gal', '19h17m32s 11d58m02s equ j2000', '12.3 8.5 b1950', and 'J140258.51+542318.3'. The 'Radius' section has a text input field containing '10' and a unit dropdown menu set to 'arcseconds'. A note below the radius field states 'Valid range between: 1" and 360000"'. The interface is clean with a light blue background and clear labels.

You can put in a position, but sometimes it attempts to guess a position, based on prior searches. You specify the cone radius; the default is 10 arcsec.

Elliptical search:

The screenshot shows the 'Elliptical' search method selected. The search area is labeled 'Coordinates or Object Name' with a dropdown menu set to 'Try NED then Simbad'. Below this, a list of examples is provided: 'm81', 'ngc 18', '12.34 34.89', '46.53 -0.251 gal', '19h17m32s 11d58m02s equ j2000', '12.3 8.5 b1950', and 'J140258.51+542318.3'. The 'Semi-major Axis' section has a text input field containing '10' and a unit dropdown menu set to 'arcseconds'. A note below the semi-major axis field states 'Valid range between: 1" and 360000"'. The 'Position Angle' section has a text input field containing '0'. The 'Axial Ratio' section has a text input field containing '.26'. The interface is clean with a light blue background and clear labels.

You can put in a position, but sometimes it attempts to guess a position, based on prior searches. You specify the search ellipse's semi-major axis, position ratio, and axial ratio. Defaults are as shown.

Box search:

Search Method: Box ↕

Coordinates or Object Name Try NED then Simbad ↕

Examples: 'm81' 'ngc 18' '12.34 34.89' '46.53 -0.251 gal'
 '19h17m32s 11d58m02s equ j2000' '12.3 8.5 b1950' 'J140258.51+542318.3'

Side:

10 arcseconds ↕

Valid range between: 1" and 360000"


You can put in a position, but sometimes it attempts to guess a position, based on prior searches. You specify the box's length on a side; default is as shown.

Tips and Troubleshooting: If you enter coordinates in non-equatorial units (e.g., Galactic or ecliptic), the search is still carried out in equatorial coordinates (RA and Dec).

Polygon search:

Search Method: Polygon ↕

Coordinates:




- Each vertex is defined by a J2000 RA and Dec position pair
- A max of 15 and min of 3 vertices is allowed
- Vertices must be separated by a comma (,)
- Example: 20.7 21.5, 20.5 20.5, 21.5 20.5, 21.5 21.5

Search Method: Polygon ↕

Search area ☒ Image ☐ Visible ☐ Custom

Coordinates:



- Each vertex is defined by a J2000 RA and Dec position pair
- A max of 15 and min of 3 vertices is allowed
- Vertices must be separated by a comma (,)
- Example: 20.7 21.5, 20.5 20.5, 21.5 20.5, 21.5 21.5


For this, note that it no longer has a single target location. It will sometimes try to pre-fill the vertices of the position it thinks you want, based on prior searches. If you have images loaded, it will give you choices based on the current image -- you can select whether you want the catalog request to match the entire area of the image you have selected ("image"), or just the portion of the image you can see in the

ZTF Help

current view ("visible"), or your own ("custom") area. (However, note that if you have selected a HiPS image before searching, you are limited to a maximum of 5 degrees.) The list of vertices in the coordinates box are in decimal RA and Dec in degrees. You must enter at least 3 and at most 15 vertices, separated by a comma. Note that, for overlaying catalogs on HiPS images, you cannot select "image", because HiPS images are generally very, very large, so this would result in too many points being returned. There is a maximum of 5 degrees imposed on catalog searches to match HiPS images.

If you [select a rectangular region](#) of your image and then select a polygon catalog search, you will have a fourth radio button above, "selection", which matches the corners of your selected image region.

If you select the "bullseye" icon on the right (), you get a pop-up with a way to interactively select your target; this works just like [this interactive target refinement](#) (go there for more details) :



Multi-Object search:

Search Method: Multi-Object




☒ Local File ☐ Workspace

Choose File Choose a file

Radius

arcseconds

Valid range between: 1" and 360000"

For a multi-object search, it can't guess what position you want. You need to upload a file (from your disk or the [IRSA Workspace](#) ) in [IPAC table format](#) , which is a varietal of plain text. (IRSA has a [table validator](#) ) which may be helpful.) Note that you also have to specify the radius over which to search for each of the targets in your list.


When you do a multi-position search on catalogs, three new columns are added to the catalog as it is returned to you. These columns are :

- ◇ cntr_01 - the target position you requested
- ◇ dist_x - the distance between the target position you requested and the object it found
- ◇ pang_x - the position angle between the target position you requested and the object it found

ZTF Help

These additional columns can help you assess if the target(s) it found is the target that should be matched to the position you requested.

All-sky search:



Because this is an all-sky search, it does not have a single target entry box. In order to constrain this search, you need to impose constraints on the bottom of the screen (see below).

The bottom of this window allows you to set restrictions on specific columns. It gives you a list of all the available column names in the corresponding catalog. (Most catalogs have identical "standard" and "long form" selections, but some have more columns available in "long form".) From here, you can choose what to display (tickboxes on the left), and filter what is returned ("constraints" column). For example, only return objects with values in column y that are greater than x. If you add more than one restriction, they are combined logically using an "AND" operators; be careful, because you can thus restrict data such that none of the catalog meets your criteria.

Click on "Search" to initiate the search. It will load the catalog into a tab of its own. The objects will also be overlaid on any images you have loaded, and a default x-y plot will be shown. (For more on the x-y plots, see [Plots section](#).) All of these representations are interlinked -- clicking on a row in the table shows it on the image and in the plot, and clicking on an object in the image shows it in the table and in the plot, and clicking on an object in the plot shows it in the table and on the image.

To close the catalog search window without searching for a catalog, click on "Cancel".

Tips and Troubleshooting

- If the catalog search is successful quickly, it will promptly return the results in a tab of its own.
- The search may take a long time to return, especially if you have asked for a large catalog, and you may think that nothing has happened, but be patient and eventually it will return a tab.
- Use large search radii with caution! Be sure you understand how many sources you are likely to retrieve. Searches that retrieve more rows will take longer. Searches that retrieve tens of thousands of rows will take quite a while.
- If you want to impose additional constraints on the catalog during your initial search, you can do so in the lower half of the screen (e.g., $\text{SNR} > n$ in some band, or an SQL command), you can place constraints at this point. However, be advised that it is easy to combine constraints such that no sources are retrieved!
- If you overlay a large catalog, the tool will show cells with a number enclosed indicating the number of sources in that region. As you zoom in closer and closer, the tool will adjust those bins to smaller and smaller cells until it shows you individual sources. [Go here](#) for more information!
- If you overlay a large catalog, then turn around and [save a regions file from the catalog overlay](#), then the entire catalog may not be saved. To get a large catalog saved as a regions file, [save it from the table](#).
- By default, it may show you fewer columns than are available in the full catalog. By selecting "long form" (above the list of columns), you can access the full range of available columns. In some cases, there are literally hundreds of columns that you can access!

The search results are then shown in a [Firefly table](#) and you can [interact with it](#).

Interacting with Catalogs

When you load a catalog, the tool may create a table, a plot, and/or, if your catalog has position information (e.g., RA and Dec), it overlays the catalog on an image. All three of these ways of displaying the catalog are interlinked and interactive.

Catalogs are a special case of [tables](#); the basic functionality of tables is covered in the [Tables section](#). You can sort and filter the table.

[Plots](#) are also covered in a different section. You can make scatter plots, heat maps, and histograms. You can plot columns from your catalog, including simple mathematical manipulations of catalog columns.

If the catalog has positions included, the catalog will also be overlaid on the loaded image(s). The [Visualization section](#) includes information about that. Each catalog that you load is overlaid on the image using different, customizable symbols and colors.

When you have catalogs loaded into the tool, the header of the catalogs has the name of the catalog and a color swatch:



This color swatch corresponds to the symbol color that is used in the image overlays. You can change the color by clicking on the color swatch in the header, or by navigating to the layers in the image pane. See the [color picker section](#) of the visualization chapter for more information.

Tips and Troubleshooting

- Large catalogs will be displayed hierarchically! See next section.
- If you save the overlays from an image as a regions file, you may not get your complete catalog, especially if it is a large catalog (see next section!). However, you can save the full contents of a single catalog as a regions file using the "save" (diskette) icon in the table toolbar, instead of the image toolbar.
- The "color swatches" may not appear immediately. To make loading faster, sometimes the colors don't load until they are actually needed. If you are in a situation where no images are visible, then no color swatches may appear until you ask the tool to show you an image (like the [coverage image](#)), and then the color swatches will appear.

Hierarchical Catalog Display


If you have a large catalog loaded into the tool overlaid on top of lots of images, the possibility exists that the computer or the network could be overwhelmed trying to render all the points on all the images. Historically we dealt with this by "thinning out" the catalog and not showing all the points. However, there is a better solution, which is now employed here!

For catalogs below about 1000 points, the tool will show the individual points on the image.

For catalogs above that threshold, the tool will bin up the catalogs based on HEALPix pixels (see [HiPS section here](#) for more links). In summary, the sky is broken up into sections, and the tool will show symbols with a number indicating the number of sources in that region. Then, when you zoom in, it will dynamically adapt to show you smaller and smaller cells until it shows you all the individual sources.



From the layers icon (see [visualization chapter](#)), you can bring up many display options. Below are examples of what is displayed, the options seen in the layers, and additional options. The same catalog and zoom level and minimum group size are used for each view. The "Min Group" option here is 50, so if there are cells with fewer than 50 sources, then the individual sources are shown, and if there are more than 50 sources, then the cell is shown with a number inside corresponding to the number of sources from the catalog. (See below for additional information.)




☒ Coverage: Spitzer-sphotdr4 (Cone:6
 Grouping **Healpix Grid** ↕ Min

In this view, the 'cells' used are the cells explicitly shown in the image. The size of the cells is very clear. In the top row 1 across the top have fewer than 50 sources (so the individual sources are shown), then the next row 57 sources respectively.

☒ Coverage: Spitzer-sphotdr4 (Cone:6
 Grouping **Box** ↕ Min

In this view, the 'cells' are shown by circles enclosing the sources. The sizes are the same as in the prior screenshot, but it is obvious to new users.





☒ Coverage: Spitzer-sphotdr4 (Cone:6

Grouping


Ellipse ↕

Mir

In this view, the 'cells' are shown by ellipses showing cell sizes are the same as in the prior screenshot, less obvious to new users. It may be more obvious groups of points.




Finally, in this view, the 'cells' are again shown as a heatmap. The color of the cells corresponds to the number of sources in each cell. You can change the color range by changing the color using the color bar, which you can also change the transparency. This view shows how many sources are in each cell, but makes it difficult to see the image, though you can change the transparency of this overlay. This view still can make seeing the image challenging in some cases.



Tips and Troubleshooting

- For all of these renditions, when you zoom in close enough, it will dynamically adapt and show you individual sources when you zoom in. (That is, it no longer decimates the overlaid catalog, which is what it used to do.)
- For all of these renditions, if you click on a cell, it will display all of the sources in the cell. You can click on many cells in a row and it will continue to display all the sources it can until it reaches the point at which it thinks performance will suffer, at which point it will turn some of the points back into cells.
- If you want to have more of your catalog shown as individual sources, pick a smaller "min group" number.
- If you have more than one catalog loaded, the numbers within the cells (and in some cases the cell



- indicators themselves) will be offset slightly so that you can see them.
- If you have a catalog that includes sources from all over the sky, it very well may just give you box groupings, and may not allow you to change that view until you zoom in.
 - If you have cells where only 1/4 of a cell is populated, it automatically renders a smaller cell, so if you have a sparsely populated but still large catalog, the size of the display will always be "small" size cells.

- If you are looking at many footprints from, say, a complex, and long ObsCore search, if you have more than 30,000 footprints, it may not be able to render all of the outlines of all of those images. It may render the centers of all of those images as if it were a catalog, in which case you will encounter these kinds of hierarchical catalog display options.

Details Tab

When you have a table loaded on the left, you will have an additional tab on the right hand side, under the plot, called "Details." This additional tab is sometimes called a "property sheet." This tab is, itself, another [Firefly table](#), and consists of each of the columns of the retrieved catalog with additional information about each field where available. (Not every catalog may have this information available.) This information can be used to learn more about each of the columns in retrieved. For additional information when it is showing details about a catalog, please consult the full documentation that accompanies the catalog.

Tips and Troubleshooting

- The property sheet is a more expanded, vertical view of the information shown in a row of a table or catalog, along with documentation of the catalog columns. Because you can sort/filter the data in the property sheet, you can restrict what values are shown. Those filters are respected as you page through a catalog. So, for example (see screenshot below), you can pull up the property sheet, filter it down to only show the profile-fitted magnitudes and errors by filtering on "mpro", and then step through the values in the catalog and inspecting the brightnesses as shown in the property sheet for each source.
- When changing rows in the main table, the property sheet/details tab scrolls to preserve the visibility of whatever row in the details tab is highlighted. If you scroll down in the property sheet *without changing the highlight*, when you change rows in the main table, because the first row in any table is always highlighted by default, the property sheet will scroll back to the top.

The screenshot shows the ZTF software interface. On the left, there is a table with columns: designation, ra (deg), dec (deg), clon, clat, sigra (arcsec), sigdec (arcsec), and double. The table contains several rows of data, with the first row highlighted. On the right, there is a 'Details' tab showing a more detailed view of the selected row. The 'Details' tab has columns: Name, Value, Units, and Description. The 'Name' column is filtered to show 'w1mpro', 'w2mpro', 'w3mpro', 'w4mpro', and 'w1sigmpro'. The 'Value' column shows magnitudes and fluxes. The 'Units' column shows 'mag' and 'mag units'. The 'Description' column shows 'instrumental profile-fit photometry magnitude, band 1 (mag)' and 'instrumental profile-fit photometry flux uncertainty in mag units, band 1 (mag)'.

| designation | ra (deg) | dec (deg) | clon | clat | sigra (arcsec) | sigdec (arcsec) | double |
|---------------------|-------------|------------|--------------|--------------|----------------|-----------------|--------|
| J140248.89+542341.7 | 210.7037281 | 54.3948374 | 14h02m48.89s | 54d23m41.77s | 0.3772 | 0.4002 | |
| J140301.33+541818.3 | 210.7555682 | 54.3051103 | 14h03m01.34s | 54d18m18.40s | 0.4235 | 0.4362 | |
| J140259.72+541732.5 | 210.7488372 | 54.2923813 | 14h02m59.72s | 54d17m32.57s | 0.1747 | 0.1825 | |
| J140320.67+542028.6 | 210.8361547 | 54.3412989 | 14h03m20.68s | 54d20m28.68s | 0.0780 | 0.0817 | |
| J140344.05+541755.1 | 210.9335444 | 54.2986494 | 14h03m44.05s | 54d17m55.14s | 0.2986 | 0.3417 | |
| J140258.43+542423.3 | 210.7434839 | 54.4064953 | 14h02m58.44s | 54d24m23.38s | 0.1104 | 0.1117 | |
| J140339.70+542736.7 | 210.9154410 | 54.3602042 | 14h03m39.71s | 54d21m36.74s | 0.3073 | 0.3177 | |
| J140322.32+542436.6 | 210.8430400 | 54.4101900 | 14h03m22.33s | 54d24m36.68s | 0.0924 | 0.0960 | |
| J140335.95+542202.5 | 210.8998188 | 54.3673640 | 14h03m35.96s | 54d22m02.51s | 0.0766 | 0.0805 | |
| J140326.65+542213.9 | 210.8610481 | 54.3705330 | 14h03m26.65s | 54d22m13.92s | 0.1272 | 0.1352 | |
| J140331.43+542151.4 | 210.8809600 | 54.3643000 | 14h03m31.43s | 54d21m51.48s | 0.0862 | 0.0899 | |

| Name | Value | Units | Description |
|-----------|--------|-------|---|
| w1mpro | 16.999 | mag | instrumental profile-fit photometry magnitude, band 1 (mag) |
| w1sigmpro | 0.122 | mag | instrumental profile-fit photometry flux uncertainty in mag units, band 1 (mag) |
| w2mpro | 17.449 | mag | instrumental profile-fit photometry magnitude, band 2 (mag) |
| w2sigmpro | null | mag | instrumental profile-fit photometry flux uncertainty in mag units, band 2 (mag) |
| w3mpro | 12.546 | mag | instrumental profile-fit photometry magnitude, band 3 (mag) |
| w3sigmpro | null | mag | instrumental profile-fit photometry flux uncertainty in mag units, band 3 (mag) |
| w4mpro | 8.988 | mag | instrumental profile-fit photometry magnitude, band 4 (mag) |
| w4sigmpro | null | mag | instrumental profile-fit photometry flux uncertainty in mag units, band 4 (mag) |

ZTF Image Service: Other Searches





There are several other searches you can add to the ZTF Image Service using the [side menu to add to the tabs at the top](#). This chapter covers the more complex of these choices. The VO searches retrieve some sort of [tables](#), many of which are [catalogs](#). For the results of any of these searches, if the tool recognizes positions in a catalog, it will overlay the catalog on [images](#) and [make plots](#).

Contents of page/chapter:

- +[Introduction & Terminology](#)
- +[Interactive Target Refinement](#)
- +[VO TAP: More about constraints](#)
- +[VO ObsCore: More about constraints](#)
- +[IRSA VO TAP Search](#)
- +[Multi-archive VO TAP Search](#)
- +[NED Objects](#) -- Searching for NED objects
- +[ObsCore Search](#)

Introduction & Terminology

There is a lot of terminology in this chapter to understand.

- VO = [Virtual Observatory](#) 
- TAP = [table access protocol](#) . TAP services enable complex queries of tables using ADQL.
- ADQL = [astronomical data. query language](#) 
- ObsCore = [core components of Observation Data Model](#) 
- Data model = A standard logical structure for a type of dataset; more flexible and general than a data format.
- ObsTAP = TAP service that serves ObsCore tables


There are myriad places on the web to learn more about TAP queries and ADQL, as well as all the rest of the VO standards and protocols. We just provide a brief overview here in the context of this tool.

The ZTF Image Service can help you interactively create ADQL which then you can copy and use in your own code elsewhere.


By using TAP and ObsTAP queries, you can use IRSA services to talk to other archives that also comply with these standards, world-wide.

The first several parts of this section talk more generally about interactive target refinement and constraints that are common to more than one of the searches discussed here. Specifics of particular searches follow after that.


Interactive Target Refinement

Whenever you see this icon  in IRSA tools, you can click on it to bring up a window to **interactively refine your target selection via clicking on a HiPS map**. Here, we are using a TAP search to demonstrate this process, but you can find this kind of target refinement in several places in IRSA tools.

When you click on the icon  you bring up a window:



If you have entered a target already, the window arrives already centered on the target. If not, it is centered on the galactic center, zoomed out. If you have entered a cone search radius already, then the circle drawn on the image is that cone size. You can manipulate this image with the same basic tools as in the [visualization tools](#).





To change the search region interactively, choose the selection tools and draw a shape on the image.

Note that if you have selected a cone search on the left, no matter what you select on the right, it will give you a cone search. If you change the cone position or radius in the yellow boxes after you change the selection, it will update the region in the image.

If you want to quit out of the selection without changing, click on "end selection" (the brown text near the top of the image).

ZTF Help



If you select polygon on the left, and you use the selection tool for "cone selection" on the right, you will get a spherical polygon (a polygon where the line segments are on a sphere).

When you are done with this pop-up window, click on the 'x' in the upper right of the window. Then you can continue with whatever you were doing before you started to refine your target parameters.

VO TAP Searches: More information about constraints

You can have several different ways of constraining your search depending on the options you have selected before the "Enter Constraints" section, and the options depend on what kind of service is available at the TAP service you have selected. If the options do not appear initially, click on the downward arrow to "unfold" the options.

Enter Constraints: Spatial

This part of the interface allows you to specify the details of a spatial search. You need to specify both what kind of search you want to do and which columns of the catalog are to be used for coordinates.

Enter Constraints ?☒ Spatial ?Spatial Type: ☒ Single Object ☐ Multi-objectShape Type: ☒ Cone Shape ☐ Polygon Shape

m101

Try NED then Simbad ↕ **m101** resolved by NED

210.80227, 54.34895 Equ J2000 or 14h03m12.54s, +54d20m56.2s Equ J2000

Radius

10

arcseconds ↕


Valid range between: 1" and 360000"

Position Columns: ra, dec (from the selected table on the right) ^

These are the recommended columns to use for a spatial search on this table; changing them could cause the query to fail

Lon
Columnra Lat
Columndec ☒ Spatial ?Spatial Type: ☒ Single Object ☐ Multi-objectShape Type: ☐ Cone Shape ☒ Polygon ShapeSearch area: ☒ Visible (limit 5 deg) ☐ Selection ☐ Custom

Coordinates:

269.19395 -26.40912, 263.61623 -26.40912, 263.47850 -31.40291, 269.33168 -31.40291 

- Each vertex is defined by a J2000 RA and Dec position pair
- A max of 15 and min of 3 vertices is allowed
- Vertices must be separated by a comma (,)
- Example: 20.7 21.5, 20.5 20.5, 21.5 20.5, 21.5 21.5

Position Columns: ra, dec (from the selected table on the right) ^

These are the recommended columns to use for a spatial search on this table; changing them could cause the query to fail


Lon
Columnra Lat
Columndec 

This is what it looks like when you do a **single target cone search**; note that you have the same name resolution options as in any other search here.



And, this is what it looks like when you do a **single target polygon search**. The search areas here (visible, selection, and custom) are the same as when you do a polygon search on [catalog](#) -- that is, you can select whether you want the catalog request to match the entire area of the image you have selected ("image"), or just the portion of the image you can see in the current view ("visible"), or your own ("custom") area. The list of vertices in the coordinates box are in decimal RA and Dec in degrees. You must enter at least 3 and at most 15

vertices, separated by a comma.

You can also click

on this icon  to [interactively refine your search position](#).

If you want to perform a **multi-target search**, click on "multi-object", which automatically brings up this pop-up, from which you can load a table from disk ("Upload tables" tab) or select one of the tables you have already loaded into the tool (click on the "Loaded tables" tab). Your uploaded catalog has to follow all the same rules as normal [catalogs from disk](#).



After you find your file with your listed positions and upload it, the tool attempts to guess which two columns are the position columns. In this example, it has (correctly) guessed that the position columns are "ra" and "dec". If it guesses wrong, or can't figure it out, you can help it along by clicking

on the down-arrow to 'expand' that part of the panel and selecting the two coordinate columns to use.

Regardless of what configuration you use, the last thing to check is which columns the tool has assumed are the position columns in the catalog to be matched to your position, region, or list of positions. Again, it attempts to make an educated guess as to the right columns, but if it guesses wrong, you can help it along by clicking on the down-arrow to 'expand' that part of the panel and selecting the two coordinate columns to use.

Position Columns: ra, dec (from the selected table on the right) ^

These are the recommended columns to use for a spatial search on this table; changing them could cause the query to fail

| Lon Column | Lat Column |
|------------|------------|
| ra | dec |

Enter Constraints: Temporal

This part of the interface allows you to specify which column of the catalog is to be used for timing, and allows you to constrain the date in two different systems.

This is what the panel looks like initially, where you specify the column in the catalog you are searching with the time and then the dates. If you don't remember what the column is in the catalog, click on the magnifying glass to get a pop-up with a list of all of the columns.

☐ Temporal ? ^

Temporal Column

☒ UTC date/times (ISO format) ☐ MJD values

Start Time End Time


YYYY-MM-DD HH:mm:ss YYYY-MM-DD HH:mm:ss

e.g.: 2019-02-07T08:00:20 e.g.: 2019-02-07T08:00:20

2019-02-07 2019-02-07

ZTF Help

For the dates and times, if you click on the calendar icon at the far right of the entry box, you get a pop-up from which you can specify the date and time, shown here.



If you would like to work in MJD instead of ISO dates, select the "MJD" radio button.

Note that it echoes below the box what it thinks you've entered in two different systems (UTC and MJD) to verify what you have entered.

Enter Constraints: Object ID

This part of the interface allows you to match object IDs.

This is what the panel looks like initially:

This is what the panel looks like after you have selected your uploaded list of IDs (in this case, a file called "gaiaids.tbl", which consists of an IPAC table file that is just the list of Gaia IDs, in a column called "gaiaid"), and it is being matched against the Gaia DR3 main catalog, where the relevant field is "source_id".

Tips and Troubleshooting

- ◇ The names have to match exactly, so in the case of this example, since the Gaia column source_id is a long, the IPAC table file must also cast the Gaia ID as a long.
- ◇ If the catalog to which you are matching is not indexed by the name column you are using, the search may take a long time.

- ◇ If you are doing, say, an object ID search, you need to turn off the position search, otherwise it doesn't understand what you want it to do.

VO ObsCore Searches: More information about constraints

These are several additional ways of constraining your search depending on the options you have selected before the "Enter Constraints" section. These options appear if you have configured an ObsCore search from a Multi-archive VO TAP search. If all of these options do not appear initially, click on the downward disclosure arrow to "unfold" the options.

Enter Constraints: Observation Type and Source

☒ Observation Type and Source ?

Calibration Level
☐ 0 ☐ 1 ☐ 2 ☐ 3 ☐ 4

Data Product Type
 Image

Instrument Name

Collection

This panel provides a way to constrain the:

- ◇ *Calibration level* - 0 is the least processed and 4 is the most processed, and not all instruments provide all levels
- ◇ *Data product type* - image, cube, spectrum, SED, time series, visibility, event, measurement, or none specified. You can select more than one of these at a time by using a right mouse click.
- ◇ *Instrument name* - must match exactly, wild cards not accepted
- ◇ *Collection* - must match exactly, wild cards not accepted

Enter Constraints: Location

☒ Location ?

Spatial Type: ☒ Single Object ☐ Multi-object

Query Type: Observation boundary contains point

m16 Try NED then Simbad

m16 resolved by NED
 274.70073, -13.80723 Equ J2000 or 18h18m48.17s, -13d48m26.0s Equ J2000

This panel provides a way to constrain the location of your search. Here, it is a single object search, which works just like it does above, including the [interactive target refinement](#) via the bullsye icon. You can also upload a list of targets by selecting "multi-object" -- it brings up the same pop-up as above, from which you can load a table from disk ("Upload tables" tab) or

select one of the tables you have already loaded into the tool (click on the "Loaded tables" tab). Your uploaded catalog has to follow all the same rules as normal [catalogs from disk](#).

You can specify via the drop-down the type of your query: "observation boundary contains point", "observation boundary contains shape", "observation boundary is contained by shape", "observation boundary intersects shape", and "central point (s_ra, s_dec) is contained by shape." The latter refers to the columns "s_ra" and "s_dec" in the ObsTAP table.

Enter Constraints: Timing

☐ Timing ?

Time of Observation Completed in the Last... ⌵

Hours ⌵

Exposure Duration

to seconds

This panel provides a way to constrain the observation time of your search. This is the default option, where you want data completed in the last x hours (or other unit of time).

☐ Timing ?

Time of Observation Overlapping specified range ⌵

☒ UTC date/times (ISO format) ☐ MJD values

Start Time End Time

e.g.: 2019-02-07T08:00:20 2019-02-07T08:00:20

2019-02-07 08:00:20 2019-02-07 08:00:20

2019-02-07 2019-02-07

Exposure Duration

to seconds

This is the alternate option, where you want data overlapping a specified date range, where you can specify UTC or MJD times.

Enter Constraints: Spectral Coverage

☐ **Spectral Coverage** ?

Select observations whose wavelength coverage

contains

enter wavelength nanometers

☐ **Spectral Coverage** ?

Select observations whose wavelength coverage

overlaps

-Inf to +Inf nanometers

This panel provides a way to constrain the spectral coverage of your search. This is the default option, where you want data containing a given wavelength.

This is the alternate option, where you want data overlapping a specified wavelength range.

IRSA VO TAP Search

To see this tab as a choice on the top, you may need to select it from the [side menu](#). (You may also find yourself having landed here from [a Multi-archive VO TAP search](#), in which case you need to go there for more information.)

This is what the IRSA VO TAP search screen looks like:

ZTF Help

Project: wise_allwise (tables: 8)
AllWISE: data products with enhanced sensitivity and accuracy from the combined cryogenic and post-cryogenic WISE...

Tables: allwise_p3as_psd (rows: 747634026)
AllWISE Source Catalog

Project count: 52 Table count: 8

View: **UI assisted** Edit ADQL

Enter Constraints ?

☒ **Spatial** ?

Spatial Type: ☒ Single Object ☐ Multi-object

Shape Type: ☒ Cone Shape ☐ Polygon Shape

m101 Try NED then Simbad

m101 resolved by NED
210.80227, 54.34895 Equ J2000 or 14h03m12.54s, +54d20m56.2s Equ J2000

Radius: 10 arcseconds

Valid range between: 1" and 360000"

Position Columns: ra, dec (from the selected table on the right)

☐ **Temporal** ?

☐ **Object ID Search** ?

Output Column Selection and Constraints

| Name char | constraints char | unit char | ucd char | description char |
|---|------------------|-----------|-----------------------|---------------------------------|
| <input checked="" type="checkbox"/> designation | | | | WISE source designation |
| <input checked="" type="checkbox"/> ra | | deg | pos.eq.ra;meta.main | right ascension (J2000) |
| <input checked="" type="checkbox"/> dec | | deg | pos.eq.dec;meta.main | declination (J2000) |
| <input checked="" type="checkbox"/> sigma | | arcsec | | uncertainty in RA |
| <input checked="" type="checkbox"/> sigdec | | arcsec | | uncertainty in DEC |
| <input checked="" type="checkbox"/> sigradec | | arcsec | | cross-term of RA and Dec unc |
| <input type="checkbox"/> glon | | deg | | galactic longitude |
| <input type="checkbox"/> glat | | deg | | galactic latitude |
| <input type="checkbox"/> elon | | deg | | ecliptic longitude |
| <input type="checkbox"/> elat | | deg | | ecliptic latitude |
| <input type="checkbox"/> wx | | pix | | x-pixel coordinate, all bands |
| <input type="checkbox"/> wy | | pix | | y-pixel coordinate, all bands |
| <input type="checkbox"/> cntr | | | meta.record;meta.main | unique entry counter (key) num |
| <input type="checkbox"/> source_id | | | | unique source ID (coadd ID and |
| <input type="checkbox"/> coadd_id | | | | coadd ID |
| <input type="checkbox"/> src | | | | source number in coadd |
| <input checked="" type="checkbox"/> w1mpro | | mag | | instrumental profile-fit photom |
| <input checked="" type="checkbox"/> w1sigmpro | | mag | | instrumental profile-fit photom |
| <input checked="" type="checkbox"/> w1snr | | | | instrumental profile-fit photom |
| <input checked="" type="checkbox"/> w1rchl2 | | | | instrumental profile-fit photom |
| <input checked="" type="checkbox"/> w2mpro | | mag | | instrumental profile-fit photom |
| <input checked="" type="checkbox"/> w2sigmpro | | mag | | instrumental profile-fit photom |
| <input checked="" type="checkbox"/> w2enr | | | | instrumental profile-fit photom |

Search Row Limit: 50000 Title: allwise_p3as_psd - irsa **Populate and edit ADQL**

Just do it: a quick start

Select Table: It comes up ready to search on *IRSA Tables*. You first need to select the "project" (sometimes called "Table Collection" or "Schema" in other contexts). Then, having selected that, the drop-down menu on the right changes to reflect the tables available under that schema.

Then **Enter Constraints:** On the **left**, you can impose a variety of constraints. In addition to selecting the tickbox indicating that you wish to impose a particular kind of constraints, you need to specify which columns should be used for those constraints. [More information on these constraints is above.](#) On the **right** is a list of the columns in the selected table, with tickboxes to indicate which columns will be returned. You can also set constraints on the columns from here, following the [same filter rules as for any tables here.](#) Above this section of the screen, there is an indication of which columns are selected (e.g., 45 of 298 columns). You can reset the column selection via the button here as well.

Then to **actually do it**, click "Search."

Getting more out of it: Taking advantage of additional options

Selecting a Query Type

On the far right of the top row, there is a slider or button:

View: **UI assisted** Edit ADQL

By default, it is set to "UI-assisted", as opposed to "Edit ADQL". Especially when starting out, UI-assisted is easier. By using the "UI assisted" option, you can select pre-defined options and have the interface construct the query in ADQL. Alternatively, if you are already fluent in ADQL, you can select the second option, "Edit ADQL", to construct even more complex queries.

ZTF Help

After populating the search parameters using the UI, you can click the button on the bottom, "Populate and edit ADQL" -- this takes the parameters you have entered, creates the ADQL, and launches the "Edit ADQL (advanced)" interface.

Advanced ADQL

IRSA

Advanced ADQL ? ADQL edits below will not be reflected in Single Table view View: UI assisted Edit ADQL

Schema Browser

Enter Filter

Schema -> Table -> Column

- wise_allwise
- neowiser
- wise
- wise_allsky
- wise_prelim
- fp_2mass
- twomass
- sixx2
- wax
- scal
- ntmass
- tmassr
- selp
- spitzer
- c2d
- astrometry
- pubdb
- swire
- planck
- herschel
- gala
- cosmos
- ptf
- ztf
- iras
- msx
- akari
- bolocam
- irismn

ADQL Query Reset Clear

```
SELECT designation, ra, dec, sigra, sigdec, sigradec, w1mpro, w1sigmpro, w1snr, w1rchi2, w2mpro, w2sigmpro, w2snr, w2rchi2, w3mpro, w3sigmpro, w3snr, w3rchi2, w4mpro, w4sigmpro, w4snr, w4rchi2, nb, na, w1sat, w2sat, w3sat, w4sat, pmra, sigpmra, pmdec, sigpmdec, cc_flags, ext_flg, var_flg, ph_qual, moon Lev, w1m, w1m, w2m, w2m, w3m, w3m, w4m, w4m
FROM allwise_p3as_psd
WHERE CONTAINS(POINT('ICRS', ra, dec), CIRCLE('ICRS', 210.8022671, 54.34895, 0.0027777777777777777))=1
```

☒ Insert fully-qualified column names (recommended for table joins)
When selecting a column from the Schema browser use the full qualified name

Add Upload Table...

Popular Functions

```
TOP n -- Limit the results to n number of records
ORDER BY [ASC/DESC] -- Used for sorting
POINT('<coordinate system>', RIGHT_ASCENSION, DECLINATION)
CIRCLE('<coordinate system>', RIGHT_ASCENSION, CENTER, DECLINATION, CENTER, RADIUS)
BOX('<coordinate system>', RIGHT_ASCENSION, CENTER, DECLINATION, CENTER, WIDTH, HEIGHT)
POLYGON('<coordinate system>', POINT1, POINT2, POINT3...)
DISTANCE(POINT1, POINT2)
CONTAINS(REGION1, REGION2)
INTERSECTS(REGION1, REGION2)
```

Sample Queries

From the IRSA TAP service, a 1 degree cone search of the 2MASS point source catalog around M101 would be:

```
SELECT * FROM fp_psc
WHERE CONTAINS(POINT('J2000', ra, dec), CIRCLE('J2000', 210.80225, 54.34894, 1.0)) = 1
```

From the IRSA TAP service, a .25 degree cone search of the 2MASS point source catalog around M31 would be:

Search Row Limit: 50000 Title: allwise_p3as_psd - irsa Single Table (UI assisted) ?

You can get to this screen by selecting "Edit ADQL (advanced)" in step two, or by clicking on "Populate and edit ADQL" after filling out the UI.

You can select the schema from the left side of the screen. Each of the schemas can expand into viable tables and then columns within each table via clicking on the "+" to the left of the folder icon. Click on a column name to have it appear at the location of your cursor in the ADQL query box on the right. If you have the tickbox checked on the right that says "Insert fully-qualified column names", clicking on the column name inserts fully-qualified column names at your cursor location in the box.

You can type the ADQL directly into the box. If you configured a search on the "UI assisted" page, this box is already pre-filled with the ADQL version of your search, and you can proceed to edit it further.

Examples of useful functions and queries are given on the lower right of this window; you may need to scroll down.

Tips and Troubleshooting

- All the drop-downs near the top are roughly searchable. This is very useful if you are trying to find a particular table or service that you can't quite recall. Click in the drop-down area, type the first letter of what you are looking for, and it will jump to the first instance of a string starting with that letter. Hit that letter again, and it goes to the second instance of a string starting with that letter.
- Not every table available via this interface even has RA/Dec or, if it does, it may not be searchable via positions. If you have selected a table that doesn't have positions, it will not yield results if you try to search by position.
- If none of the columns are selected, then the tool behaves as if you have selected all of the columns.

ZTF Help

- There is a maximum number of returned rows at the bottom. If you are anticipating more than this number of rows, increase this number!
- If you arrive at the advanced ADQL page from the "Populate and edit ADQL" button, this is a one-way trip -- any changes you make to the ADQL here are NOT transmitted automatically back to the "UI Assisted" query page.

If you choose to use the GUI, you can work within it to set the constraints you desire at the bottom of the screen; see [VO TAP: More About Constraints](#) for all of the information about setting constraints.

The result of an IRSA TAP search is a catalog that can be interacted with like any other [catalog in this tool](#).

Multi-archive VO TAP Search

To see this tab as a choice on the top, you may need to select it from the [side menu](#). Or, you may land in this tab from a [table action](#).

When you first go to this tab, you will see this near the top of your screen:

At the top, you now have a choice of which TAP service you want to use, and it defaults to IRSA's. You can select your favorite from the list, or use the toggle on the left to enter your own custom URL. If you want to hide this top row after setting it (to, say, regain screen real estate), look for this on the far right:

the "TAP Services:" button (show/hide) will reveal or conceal this top row.

The rest of this search screen is basically identical to that which you get from the [IRSA VO TAP Search](#) screen, even if you pick a TAP service other than IRSA's (with a few exceptions, including if it's ObsCore; see below).

For VizieR's services in particular, because there are so many tables, the tool will give you a slightly different interface under the "Tables" section of the window. Here is the default Vizier choices as of this writing:

Note that it tells you how many tables and rows are available. Switching to tables associated with journal articles, far more tables are available:

Now, if you click on the second tier menu (J/AJ/100/1091/table9), you get a pop-up, which is another Firefly

[table](#) like any other in this tool, so it's searchable and sortable:

Choose Table

| Table Name char | Description char | Rows char |
|-----------------------|--|--------------|
| like '%Massey%' | | |
| J/AJ/101/1408/mt91 | Observations in Cyg OB2 (tables 2,5,6) (Massey P., Thompson A.B.) | 801 |
| J/AJ/103/1205/stars | All stars with UVB photometry with their bolometric magnitudes and effective temperatures which were not listed in the o | 795 |
| J/AJ/103/1205/ubv | UBV data from Tables 3-6 in the paper (Parker J.W.M., Garmany C.D., Massey P., Walborn N.R.) | 1229 |
| J/AJ/105/980/catalog | Photometry and cross-identifications (tables 1 and 2) (Massey P., Johnson J.) | 768 |
| J/AJ/105/980/table4 | The brightest and bluest stars (Massey P., Johnson J.) | 95 |
| J/AJ/105/980/table5 | New Spectral types (Massey P., Johnson J.) | 19 |
| J/AJ/105/980/table6 | Distance & Reddening derived from spectroscopy (Massey P., Johnson J.) | 48 |
| J/AJ/106/1906/posmk | MK classification, with accurate position (Hillenbrand L.A., Massey P., Strom S.E., Merrill K.M.) | 77 |
| J/AJ/106/1906/table1 | NGC 6611 Optical and Near-IR Photometry Data (Hillenbrand L.A., Massey P., Strom S.E., Merrill K.M.) | 1022 |
| J/AJ/108/1256/posmk | *Position and MK types of selected stars (Garmany C.D., Massey P., Parker J.W.) | 29 |
| J/AJ/108/1256/table3 | UBV photometry of stars in LH 58 (Garmany C.D., Massey P., Parker J.W.) | 839 |
| J/AJ/110/2715/m33 | Photometry of M33 stars (Massey P., Armandroff T.E., Pyke R., Patel K., Wilson C.D.) | 490 |
| J/AJ/110/2715/ngc6822 | Photometry of NGC 6822 stars (Massey P., Armandroff T.E., Pyke R., Patel K., Wilson C.D.) | 167 |
| J/AJ/119/2214/table2 | Catalog of Photometry and spectroscopy of 19 Magellanic Cloud OB associations (Massey P., Waterhouse E., DeGioia-Ea | 548 |
| J/AJ/119/2214/table5 | Derived parameters for the highest mass unevolved stars (Massey P., Waterhouse E., DeGioia-Eastwood K.) | 184 |
| J/AJ/121/2020/table1 | CTIO Photometry (Bianchi L., Scuderi S., Massey P., Romaniello M.) | 3232 |
| J/AJ/121/2020/table3 | WFPC2 Photometry (Bianchi L., Scuderi S., Massey P., Romaniello M.) | 1025 |

Choose

which makes it trivially easy to find tables in which you are interested, such as those associated with papers by Massey, as shown. Select the table that you want to search, and then continue to specify the rest of your search, just as described above in the [IRSA VO TAP Search](#) screen discussion.

The result of any VO TAP search is a catalog that can be interacted with like any other [catalog in this tool](#).

NED Objects -- Searching for NED objects

(NED= [NASA Extragalactic Database](#) )

To see this tab as a choice on the top, you may need to select it from the [side menu](#).

m101 Try NED then Simbad

m101 resolved by NED

210.80227, 54.34895 Equ J2000 or 14h03m12.54s, +54d20m56.2s Equ J2000

Radius:

10 arcseconds

Valid range between: 1" and 18000"

As for the other catalog searches, the tool may pre-fill the target position with its best guess of the coordinates of the target with which you have been working. You can use an object name in place of coordinates. Note that although NED is used for name resolution, the actual search is then performed using coordinates, as opposed to name. In this case, you are limited to a cone search, so the next option is the cone search radius. Pick your units from the drop-down first, and then enter a number; if you enter a number and then select from the drop-down, it will convert your number from the old units to the new units. There are both upper and lower limits to your search radius; it will tell you if you request something too big or too small.

From the NED results, you have one-click access to the fully detailed information from NED on any object returned from such a search. The search results will generally include a column "Details", though you may have to scroll to the right to see it. Clicking on a link in this column takes you directly to the full NED information display for the selected object in a new window.

The result of any NED search is a table that behaves like any other [table in this tool](#).

ObsCore Search

An ObsCore search is technically a subcategory of a TAP search, but it is a special subcategory in that it can return images, spectra, catalogs, and more, or even links to services. As such, it is covered here in a wholly different section than the [General TAP](#) section above.

To launch an ObsCore search, you need to find a server that supports an ObsTAP search, and flip the corresponding toggle on the left, for example:

The "UI Assisted"/"Edit ADQL" switch at the top right works [just like it does above](#) -- use the UI to construct a query or dive right into the ADQL yourself.

Then in the remaining part of the screen, impose the constraints you want -- see [the constraints section above](#).

At the bottom of the screen, you can "Populate and edit ADQL" if you want to work with the ADQL directly, or just search straight away after setting your search parameters.

Here are results of a basically unconstrained search using the CADC ObsTAP server on M16:

| obs_publisher_id | obs_collection | facility_name | instrument_name | char |
|---------------------------------------|----------------|---------------|-----------------|------|
| ivo://cadc.nrc.ca/OMM?C160619_0119/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/DAO?dao_c182_2003_0 | DAO | DAO 1.8-m | Newtonian Image | |
| ivo://cadc.nrc.ca/OMM?C160619_0189/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/DAO?dao_c182_2003_0 | DAO | DAO 1.8-m | Newtonian Image | |
| ivo://cadc.nrc.ca/DAO?dao_c182_2005_0 | DAO | DAO 1.8-m | Newtonian Image | |
| ivo://cadc.nrc.ca/OMM?C160525_0159/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0267/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0247/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160525_0083/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0302/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160430_0257/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0441/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160525_0044/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160430_0363/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160525_0013/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0398/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160430_0255/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160525_0057/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160619_0146/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C060627_0366/C | OMM | CTIO-1.5m | CPAPIR | |
| ivo://cadc.nrc.ca/DAO?dao_c182_2001_0 | DAO | DAO 1.8-m | Newtonian Image | |
| ivo://cadc.nrc.ca/OMM?C160430_0290/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0278/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_0317/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C160430_0284/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/JCMT?19970823_dem_1 | JCMT | JCMT | SCUBA | |
| ivo://cadc.nrc.ca/DAO?dao_c182_2001_0 | DAO | DAO 1.8-m | Newtonian Image | |
| ivo://cadc.nrc.ca/OMM?C160430_0374/C | OMM | OMM-1.6m | CPAPIR | |
| ivo://cadc.nrc.ca/OMM?C130514_M16_H | OMM | OMM-1.6m | CPAPIR | |

This kind of search is somewhat hobbled in this tool; you may find it more satisfying to do this kind of search in the [IRSA Viewer](#) tool, specifically because it yields much more than just a row in a catalog; it can give you

ZTF Help

images, spectra, and more. Nonetheless, here in this tool, the table on the left as a list of the observations that it found consistent with the search parameters. This table is like [any other table in this tool](#), so it can be sorted, filtered, etc. The coverage image on one of the tabs on the right shows the polygons of coverage of the observations it found, and the plot also in one of the tabs on the right is the (relatively uninformative) plot of the positions associated with the observations.

ZTF Image Service: Plots


Plots (sometimes called charts) are made from [Tables](#), and, more commonly (or usefully) from [Catalogs](#). Plotting is covered in this section. The [Tables](#) section discusses tables more generally, and the specific case of loading [catalogs](#) is in another section. If your table has RA and Dec in it, the [Visualization](#) section covers how the catalog can be overlaid on images.

Contents of page/chapter:


- +[Default Plot](#)
- +[Plot Format: A First Look](#)
- +[Plot Navigation](#)
- +[Plot Linking](#)
- +[Changing What is Plotted](#)
- +[Plotting Manipulated Columns](#)
- +[Restricting What is Plotted](#)
- +[Overplotting](#)
- +[Adding Plots](#)

Default Plot

When doing a position search for a fixed target, the default plot is often somewhat less than useful -- it grabs the 'crval1' and 'crval2' from the list of images, which is just the coordinates of the reference pixel (the center pixel) of the retrieved images (see first screenshot below). If you have constrained your search results to only return the most centered image, this is an even more phenomenally uninteresting plot, because it has a single point. If you do a search on a moving target, the default plot is the RA and Dec of the object that it finds with data, so moderately more interesting (see second screenshot below).



(positions of a list of images returned by an inertial target search.)




(positions of a list of images returned by a moving target search.)

You can change what is plotted (see below) but plots of image metadata may not be what is most desirable.


Try loading in a [catalog](#) and keep reading! The default plot for a catalog will also be RA and Dec.

Note that all of these RA/Dec plots follow astronomical convention -- RA increases to the left.

To obtain a full-screen view of your plot, click on the expand icon in the upper right of the window pane: . To return to the prior view, click the "Close" arrow in the upper left.

Plot format: A First Look

If you have loaded a catalog with many (> 5,000) points, you may have an RA/Dec plot that looks something like the one on the left here. If you have loaded a catalog with few (< 5,000) points, you will have an RA/Dec plot that looks more like the one on the right here.



The difference between them is that, for larger catalogs (left), the plot is binned -- more points are encompassed in a black tile and fewer points are encompassed in a white tile. In the context of this tool, this is called a **heatmap**. The shades of grey correspond to how many points are encompassed in each 'cell', with the density scale given on the right hand side of the plot. For smaller catalogs (right), each individual point is shown as a

blue dot. In the context of this tool, this is called a **scatter plot**. Note that even when individual points are shown, where the points overlap, the color is darker.

In either case, letting your mouse hover over a point tells you the values of the point under your cursor, and (if binned) how many points are represented:

ra = 325.2655066 deg
dec = 57.0346142 deg
represents 14 points

for binned plots, and

ra = 323.271454 deg
dec = 57.1493865 deg

for just one point.

ra = 324.7363179 deg
dec = 57.4941601 deg

Clicking (in an unbinned plot) highlights that point, and it stays highlighted, though you must keep your mouse on the point in order to see the information about it.

The reason the tool makes a heatmap for large catalogs is to more fairly represent the point density -- and to make the plotting faster. In these cases, though, it will not give you the option to overplot errors (see below). If you have a heatmap and want a scatter plot *by default*, you need to filter or otherwise restrict the catalog to have fewer points (see below). You can change the bin size and shading via the plot options pop-up (more on this below).

Plot Navigation

The top of the plot window has a row of icons something like this:



which we now describe.



Add new plot

You may or may not have this icon. Clicking on this icon adds a new plot. This has a [separate section](#) below.



Plot mode

This trio of icons controls the plot interaction 'mode'. By default, you are in 'selection' mode, as seen here -- the last icon is darker, like a pushed-in button. To activate the other modes, click on the other icons, and they become darker or "pushed in."




Zoom mode

When this mode is active, when you click and drag in the plot, the plot is zoomed to the region you have selected. Even when this mode isn't active, you can also zoom using your scroll





Pan mode

When this mode is active, when you click and drag in the plot, it moves around in response to where you drag. To return to the original view, click on .



Select mode

When this mode is active, when you click and drag in the plot, you are given additional options at the top of the plot :   The checkmark means "select" and the funnel means "filter."

ZTF Help

The difference is that filtering (temporarily) limits what is shown in the plot, catalog, and image (see [general information on filters](#)), and selecting just highlights the points enclosed within your

selection. To cancel either one, click on cancel filters



or cancel selection



Re-scale plot

Return to the view that optimizes the range of x and y to show the currently displayed points.

Tips and Troubleshooting: Did you accidentally zoom in the plot with your magic mouse or touchpad? Click on this icon to reset the plot.



Save plot

Save the plot. It will save as a png file, wherever your browser is configured to save files. The saved png is the same size as it is on your screen. If you want a big version, make the desired plot big on your screen (expand the view to take up as much space as possible) before saving the png.



Undo

Restore everything to the defaults. If you've played a lot with the plot, you may want to undo everything you've done. Click this icon to restore everything back to the defaults.



Filter from plot

Pull up interactive filters. This button brings up filters for the displayed catalog in an interface [like all the other tables here](#), except you don't see the values in the catalog themselves; you can enter filters here in the same way you can everywhere else in this tool (see [general information on filters](#)).



Configure plot

Click on this icon to [change what is plotted](#) (much more on this below).



Expand plot

Click on this icon to make the plot take up the whole browser window. To return to the prior view, click the "Close" arrow in the upper left.



Help

This icon may not appear, but if it does, it is a context-sensitive help marker, which should bring you to this online help.

Plot Linking: Plots are linked to catalog and image(s)

If you move your mouse over any of the points in the plot, you will get a pop-up telling you the values corresponding to the point under your cursor. For scatter plots, if you click on any of the points, the object(s) corresponding to that point will be highlighted in the overlays in the images shown, and highlighted in the catalog table. This works the other way too -- click on a row in the catalog, or an object in the images, and the object will be highlighted in the plot or the catalog or the image.

Changing What is Plotted

To change what is plotted, click on the gear icon in the upper right of the plot window pane:



Configuration options then appear; the options are a little different depending on whether the points are binned or not. This section describes how to change what is plotted, i.e., the "Modify Trace" option at the top of both of these pop-ups. The [overplotting](#) option (and, for that matter, [adding plots](#)) are covered in more detail below.

Plot Parameters ✕

☐ Overplot New Trace ☒ Modify Trace

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X: 🔍

Y: 🔍

Color Scale: ⬆️⬆️ ☐ reverse

Number of X-Bins:

Number of Y-Bins:

Chart Options ⬆️

Chart title:

X Label:

Options: ☐ grid ☒ reverse ☐ top ☐ log

Y Label:

Options: ☐ grid ☐ reverse ☐ right ☐ log

Set plot boundaries if different from data range.

X Min: X Max:

Y Min: Y Max:

Enter display aspect ratio below.
Leave it blank to use all available space.

?

This is the configuration window for a binned (a.k.a. heatmap and/or greyscale) plot. By default, the "chart options" may be hidden; to reveal them, click on the name "Chart Options" or the disclosure arrow on the right. To hide them again, click on the disclosure arrow on the right.

Plot Parameters ✕

☐ Overplot New Trace ☒ Modify Trace

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X: 🔍

Error: ☒

Y: 🔍

Error: ☒

Trace Style: ⬆️⬆️

Trace Options ⬇️

Chart Options ⬇️

?

The configuration window for a plot that shows individual points, once fully extended, is much longer (and scrollable), and so is shown here in two parts. Both the "Trace Options" and "Chart Options" may be hidden by

Plot Parameters ✕

☐ Overplot New Trace ☒ Modify Trace

Trace Options ^

Symbol:

Color: 🔍

Color Map: 🔍

Color Scale:

Size Map: 🔍

Chart Options ^

Chart title:

X Label:

Options: ☐ grid ☒ reverse ☐ top ☐ log

Y Label:

Options: ☐ grid ☐ reverse ☐ right ☐ log

Set plot boundaries if different from data range.

X Min: X Max:

Y Min: Y Max:

Enter display aspect ratio below.
Leave it blank to use all available space.

X/Y ratio:

?

default; to reveal them, click on the name or the disclosure arrow on the right. To hide them again, click on the disclosure arrow on the right.

Options found in both kinds of plots

In either case, you can **specify what should be plotted on each axis**. The magnifying glass is a link that brings up a table that lists all of the available columns in the catalog. Alternatively, you can just start typing, and viable options appear below the box. Whatever you put in the box must match the column name as shown in the catalog *exactly*.

Click on the black triangle to reveal additional options.

In both of the examples above, RA is plotted on the x-axis. It has pulled the column name for the label; in this table, the column is "ra" rather than "RA", and it is case-sensitive. It has copied over the units ("deg") from the catalog, and plotted the x-axis increasing to the left as per astronomical convention. You can change what column is plotted, and whether or not errors are shown. Under "**Chart Options**", you can specify:

- ◊ title of the plot;
- ◊ labels on the x and y-axis;
- ◊ whether or not there is a grid shown;
- ◊ whether or not the axis is reversed (as for ra in the examples above);
- ◊ whether the x-axis is on the top or bottom and the y-axis is on the left or right;
- ◊ whether or not the axis is logarithmic;

ZTF Help

- ◇ the maximum and minimum values of the plot range;
- ◇ the aspect ratio of the plot (e.g., square or rectangular).

By default, the boundaries of the plot are set to encompass the full data range. Here you can change the boundaries to specific numbers. (This can also be set via filtering from the plot; see below.)

You can enter **simple mathematical relations** in these boxes too, such as (for a WISE catalog) "w1mpro-w4mpro" to put [W1]-[W4] on one axis. Supported operators:

- ◇ +, -, *, /
- ◇ abs(x), acos(x), asin(x), atan(x), atan2(x), ceil(x), cos(x), exp(x), floor(x), lg(x), ln(x), log10(x), log(x), power(x,y), round(x), sin(x), sqrt(x), tan(x)
- ◇ degree(x) and radians(x) are also supported -- these are the same functions as in ADQL and convert radians to degrees or degrees to radians. For small astrometric offsets, you could make a scatterplot of dec2-dec1 vs. (ra2-ra1)*cos(radians(dec1)) instead of typing cos(dec1*pi()/180). (NB: pi() is also a supported function you can use, instead of typing 3.14159.)
- ◇ Non-alphanumeric column names (e.g., those with - or + or similar characters) should be quoted in expressions.

Click "Apply" to apply, and "Close" to return to the plot without making changes. (For the latter, you can also click the 'x' in the upper right.)

Options found only in binned plots

(Plots are binned by default if there are > 5,000 points in the catalog.) From the pop-up, you can control the color table that is used (greyscale is the default; there are many other choices in the drop-down menu), as well as the number of bins in the x and y directions. The default value for the number of bins is 100 in both directions.


Options found only in plots showing individual points

You can add errors. Toggle the error switch, and then additional choices appear. From there, you can select symmetric or asymmetric errors, and then you can specify an error as either an existing column in the catalog, or calculated from a column in the catalog.

Under "**Trace Style**," you can control whether the points are shown as individual points, connected points, or just lines connecting the points.

Under **Trace Options**, you have many choices.

- ◇ Choose the **symbol type**: circle (default), open circle, square, open square, diamond, open diamond, cross, x, upward-pointing triangle, hexagon, or star.
- ◇ Choose the **color**. By default, the point color is a mid-range blue that is darker where more points. This is specified by the rgba vector shown in the example here (31, 119, 180, 50) where the last number is in units of fraction of 1, so 0.5=50% in this example. Click on the magnifying glass to bring up a color picker window:



From here, you can click on your desired color in the top colorful box. Immediately below that box, you can change the color and saturation of the top box so that you can select from a different range of colors. Below that, you can enter numerical hex codes or RGBA values (where the value for RGB is between 0 and 255, and A is in units of percent, e.g., 50 = 50%). Finally, you can also select from a pre-defined set of 15 colors by clicking on any of the small boxes. Note that the numerical codes update as you select different colors. Click "OK" to implement your color choice, or click 'x' in the upper right to close the window without changing the color.


Tips and Troubleshooting: Don't like the transparency feature of the points that makes them darker when there are more points? Set the last value of the vector (A) to 1. Don't like the blue? Pick a different color entirely. Want the faintest point to be brighter than it is by default? Set the last element of the color vector ("A") to be 0.7 or 0.8.

- ◇ Choose the **color map**. By default, all of the points are the same color, but darker where there are more points. You can change this such that the color scale of the points is tied to a column value, such as `w1snr` (WISE-1 signal-to-noise ratio) in a WISE catalog. If you select this option, you can also change the color scale to any of many different options (see the drop-down). Simple mathematical relations (as above) are also permitted in this box.
- ◇ Choose the **size map**. By default, all of the points are the same size. You can change this such that the color scale of the points is tied to a column value, such as `w1snr` (WISE-1 signal-to-noise ratio) in a WISE catalog. Simple mathematical relations (as above) are also permitted in this box.

Example: Load a large WISE catalog. Plot `w1snr` (WISE-1 signal-to-noise ratio) vs. `w1mpro` (WISE-1 profile fitted magnitude). It defaults to a heatmap. Change the labels, making the y-axis label "WISE-1 SNR" rather than the more cryptic column header "w1snr". Change the x-axis label to "[W1]". Change the greyscale to

ZTF Help

yellow-green-blue ("YlGnBu") to make it easier to see the lowest-populated bins. Depending on your catalog, you may need to adjust the ranges. Obtain this plot:




Example: Load either a smaller WISE catalog, or the same large WISE catalog, but [filter](#) it down such that w1snr, w2snr, and w3snr are all greater than 10, which limits the number of points to be <5,000. Plot w1snr vs. w1mpro. It shows the points individually. Change the labels. Change the point color map to scale with w2mpro (WISE-2 profile fitted magnitude). Change the point size map to scale with w4snr (WISE-4 signal-to-noise). Obtain this plot:



Plotting Manipulated Columns

You can choose a single column to plot against another column, as above. However, you can also do simple mathematical manipulations.

For example, if you have loaded a WISE catalog, you can plot $[W1]-[W2]$ vs. $[W3]-[W4]$. In terms of the names of the columns in the database, this is $w1mpro-w2mpro$ vs. $w3mpro-w4mpro$.



Plot Parameters

☐ Overplot New Trace
 ☒ Modify Trace

For X and Y, enter a column or an expression
 ex. log(col); 100*col1/col2; col1-col2

X:

Y:

Color Scale: ☐ reverse

Number of X-Bins:

Number of Y-Bins:

Chart Options

Chart title:

X Label:

Options: ☐ grid ☐ reverse ☐ top ☐ log

Y Label:

Options: ☐ grid ☐ reverse ☐ right ☐ log


Set plot boundaries if different from data range.

X Min: X Max:

Y Min: Y Max:

Enter display aspect ratio below.
 Leave it blank to use all available space.

If you have few enough points that the plot is not binned, you can add errors that you calculate. Here, the expression for the x-axis errors is $\sqrt{\text{power}(w1sigmpro,2)+\text{power}(w2sigmpro,2)}$ and for the y-axis errors, it is $\sqrt{\text{power}(w3sigmpro,2)+\text{power}(w4sigmpro,2)}$ -- that is, the errors for the individual photometric points added in quadrature.






Restricting What is Plotted (from the plot)

You can also restrict what data are plotted in any of several different ways.

You can [filter the catalog](#) from the table itself (discussed in another section).

You can set axis limits on the plot itself from the plot options pop-up (discussed above).

However, and perhaps more powerfully, you can set limits from the plot itself using a rubber band zoom. Click on the select icon in the plot  Then, click and drag in a sub-region of the plot. New icons appear:

  If you click on the funnel icon, only those data points that pass the filter are shown in the plot, in the table, and/or overlaid on the image(s). (This is the behavior of 'filter', as opposed to 'select'; the former restricts what is shown, the latter just highlights the points.) For more on filters, see [the filtering discussion in the tables section](#).

Example: Obtain a WISE catalog of a star-forming region, say IC1396. Filter down the catalog to only have detections at all four WISE bands. (Limits have undefined errors, so ask the catalog to filter down such that $w1sigmpro > 0$, $w2sigmpro > 0$, $w3sigmpro > 0$, and $w4sigmpro > 0$). Plot $w1mpro - w4mpro$ on the x-axis, and

ZTF Help

w1mpro on the y-axis. Reverse the y-axis to put bright objects at the top. Click and drag in the plot to select the bright and red objects, and filter them down to get a subset of bright and red sources. For clarity, the screenshot here has the sources selected, not filtered.



Overplotting

At the top of the pop-up that you get when you click on the gears, you have two radio buttons:

☐ Overplot New Trace ☒ Modify Trace

They are "Overplot New Trace" and "Modify Trace." Modifying traces (plots) has been covered above; in this section, we will cover overplotting. This is sometimes called "multi-trace," meaning that more than one thing is plotted.

When you select "Overplot New Trace," you get a new interface that is very similar to the original interface where you selected what to plot:

Plot Parameters

☒ Overplot New Trace
☐ Modify Trace

Plot Type:
Scatter

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X:

Error:
☐

Y:

Error:
☐

Trace Style:
points

Trace Options

Chart Options

OK
Close

?

As before, you need to :

- select a plot type (scatter, heatmap, histogram);
- tell it what column(s) (and and manipulations thereof) you want for x, y, and associated errors;
- select the trace style (points, connected points, lines);
- set any additional trace options;
- set any additional chart options.

The best way to explain how to use this feature is probably with an example. We have a plot of [W1] vs. [W1-W4] from above. We want to add on top of it a plot of [W2] vs. [W1-W4]. Click on the "Add Trace" button to bring up the pop-up. Select "Overplot New Trace." Enter "w1mpro-w4mpro" for x and "w2mpro" for y. Expand "Options." Note that it has preserved the overall chart title, but has erased the X and Y labels (and lost the red line for the y axis) because the overplot could literally be anything. The x and y need not be the same columns or even the same units as the original plot. You need not be the same columns or even the same units as the original plot. Type them in again. Here is the configuration:

Plot Parameters ✕

☒ Overplot New Trace ☐ Modify Trace

Plot Type: Scatter ▾

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X: w1mpro-w4mpro 🔍

Error: ☐

Y: w2mpro 🔍

Error: ☐

Trace Style: points ▾

Trace Options ▾

Chart Options ^

Chart title: Example

X Label: [W1]-[W4]

Options: ☐ grid ☐ reverse ☐ top ☐ log

Y Label: [W1] or [W2]

Options: ☐ grid ☒ reverse ☐ right ☐ log

Set plot boundaries if different from data range.


X Min: X Max:

Y Min: Y Max:

OK Close ?

window right before clicking "ok", and the resultant plot

Example



After you add the overplot, if you click on the gears again that the choices at the top of the window have changed. You can add another overplotted trace, modify a trace, or remove a trace. Each trace that you add is a new 'layer' on the plot. A drop-down menu near the top of the window controls which trace is 'active' for setting the x, y, errors, trace style, name, symbol, color, etc. there is now a drop-down menu at the top of the window. There is a legend on the plot specifying which color corresponds to which trace. In this example, the plot above has appeared with a blue and green color scheme, which may be too hard to

Plot Parameters

☐ Overplot New Trace
 ☒ Modify Trace
 ☐ Remove Active Trace

Choose Trace: trace 1

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X: w1mpro-w4mpro

Error: ☐

Y: w2mpro

Error: ☐

Trace Style: points

Trace Options

Name: [W2]

Symbol: circle

Color: rgba(144,19,254,0.5)

Color Map:


Color Scale: Greys

Size Map:


Chart Options

differentiate. To change the new points' color, click on the gear icon to open the "Modify Trace" pop-up window. Ensure "Modify Trace" is selected, select "trace 1" (as opposed to "trace 0", the first one you loaded), go down and expand "Trace Options" and pick a different color. You can also change the legend name from "Trace 1" to, in this case, "[W2]". Click "apply" to apply the changes to the plot. Note that once you change the trace name, the relevant drop-down menus in the pop-up window and the legends on the plot update accordingly.

Example



Note that the pop-up spawned by clicking the gears now has an additional option at the top: "Add New Chart", "Overplot New Trace", "Modify Trace", and "Remove Active Trace." From here, you can modify a trace you have already plotted (as described above), overplot another trace (also as described above), or remove the selected trace:




Plot Parameters [X]

☐ Overplot New Trace
 ☐ Modify Trace
 ☒ Remove Active Trace

Choose Trace: [W1] [v]

Remove [W1] (active trace) of the chart?


Tips and Troubleshooting

- Right now, the overplotting only works from the same catalog -- that is, you cannot plot [W1] vs. [W1]-[W4] from one catalog and overplot [W1] vs. [W1]-[W4] from another catalog. (We enthusiastically await this capability too.)
- You can easily get yourself into a physically nonsensical situation, say, by overplotting a histogram onto a scatter plot. If you find yourself in a hopeless mess, click on the "undo" icon to reset everything  and try again.
- When you have more than one thing (trace) plotted, double click on the legend to bring that trace to the foreground and temporarily hide the other traces.
- You can overplot a scatter plot on top of a heatmap if you really want to!

Adding Plots



Clicking on this icon brings up a dialog from which you can choose to make another scatter plot (left below), a heatmap (center below), or a histogram (right below):



Add New Chart [X]

Plot Type: Scatter [v]

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X: [] [v]

Error: ☐

Y: [] [v]

Error: ☐

Trace Style: points [v]

Trace Options [v]

Chart Options [v]

Add New Chart [X]

Plot Type: Heatmap [v]

For X and Y, enter a column or an expression
ex. log(col); 100*col1/col2; col1-col2

X: [] [v]

Y: [] [v]

Color Scale: Default [v] ☐ reverse

Number of X-Bins: []

Number of Y-Bins: []

Chart Options [v]

Add New Chart [X]

Plot Type: Histogram [v]

Column or expression: [] [v]

Algorithm: ☒ Uniform binning

☒ Number of bins: [50]

☐ Bin width: []

Min: []

Max: []

Trace Options [v]

Chart Options [v]

The options for these plots here are very similar to what is described above. You can specify which columns to plot or manipulate and plot, specify labels, etc.

Scatter plots allow you to choose points, connected points, or lines; you can add errors to each point.


Heatmap plots are binned scatter plots; you can choose what color scale and how many bins to use.

Histogram plots allow you to choose how many bins or the bin width. Note that, if you provide a minimum number, the binning starts at the minimum value you provide, and may exceed the maximum you entered in order to fit in a whole bin.

You can change what is plotted after plotting by clicking on the gears, as described above.

You can have many plots up at the same time.

You can view multiple plots all at once or one at a time by clicking on the corresponding icons above the plots

(just as when you have multiple images loaded).  The single box means "one at a time", the set of four boxes means "all the plots at once". If you are viewing one at a time and have more than one plot loaded, you will see the ">" and "<" signs (as in the image here), and you can scroll among the plots by clicking on these arrows (just as when you have multiple images loaded).

Tips and Troubleshooting


- Note that many plots of a large catalog may make your browser run slowly.
- You can force the tool to make a scatter plot even if you have a catalog of >5,000 points; it just might make your browser slow down. You can even overplot a scatter plot on top of a heatmap if you really want to!
- To remove a plot, click on the 'x' in the upper right corner of the plot.

ZTF Image Service: Downloading Data

Contents of page/chapter:

- +[Overview](#)
- +[Options for Downloading Data](#)
- +[Job Monitor](#)
- +[Sending Email](#)
- +[Scripts](#)
- +[Job Information](#)
- +[Contents of your download - Quick Start](#)
- +[Acknowledging ZTF and IRSA](#)

Overview

To save individual things like single tables, images, or plots, look for a diskette icon () in the corresponding pane. [Tables](#), [images](#), and [plots](#) can all be saved individually.

To download data, in the simplest case, on the search [results](#) page, just click the checkboxes on the far left of each row to pick specific observations to download, and then click the "Prepare Download" button


Prepare Download

to begin the packaging (and downloading) process. A pop-up window will appear in order to define exactly what kinds of data you would like to have packaged up. Clicking "prepare download" in the pop-up initializes this process.

To select *all* of the data you have displayed, click on the checkbox at the top of the column of checkboxes, and all of the rows are automatically clicked (even those on subsequent pages if you have more than one page). Then click "Prepare Download" to initiate the packaging process.

The packaging process spins off into the [Job Monitor](#), which keeps track of its progress and notifies you when the downloads are complete. You can choose to have an [email](#) sent to you to let you know when things are ready, even after the packaging process has started.

Tips and Troubleshooting

- **You** control where the file is saved on your disk through your browser; your browser may be configured to store all downloads in a particular location on your disk. Try looking in a "Downloads" directory, or for "recently modified files."
- You need to be [logged in](#) to use the [IRSA Workspace](#) .

Options for Downloading Data

From the pop-up, you can choose what to download:

Download Options

Title:

Download Sci Products: ☒ Yes ☐ No

Download Ancillary Files:

☒ Mask ☒ Raw images ☐ SExtractor catalog ☐ DAOPhot catalog ☐ DAOPhot PSF table

☒ Science PSF ☒ Difference image ☐ Difference image PSF ☐ Calibration log ☐ Difference image log ☐ Summary log

Flattened File Structure ☐

File Location: ☒ Local File ☐ Workspace


Prepare Download **Cancel**

(The options may be slightly different, depending on the tab from which you initiate the download.)

The title is the name by which this packaging job will be known to the [Job Monitor](#) as well as what the root filename is for the saved file - change it to whatever you want (time or a description of your search is usually the most helpful).

The second row shown here may be slightly different, depending on where you were when you initiated the packaging process, and is asking what kinds of additional data you want - science or reference data products.

The next row controls whether the observations are bundled one per subdirectory or are all in one directory (flattened).

The last row controls whether the file is saved to your local disk or the [IRSA Workspace](#) .


Click "Prepare Download" in the pop-up window, and it will go do it!

If you request relatively little data, the download will happen quickly. If you request a lot of data, you are given a choice to place the job in the [Job Monitor](#).

Tips and Troubleshooting


- Note that **you** control where the data are saved on your disk through your browser; your browser may be configured to store all downloads in a particular location on your disk. Look for a "Downloads" folder or search for recently modified files.
- You will download zip files. Depending on how, exactly, you unzip your files, your computer may put the contents of each *zipfile* into one directory, rather than, say, the contents of each *observation* into one directory. If you are using a GUI-based method (e.g., click to uncompress), there should be a preferences option to allow you to uncompress subsequent zipfiles into the same root directory. You can also set flags on the command line to put all files from the same observation in the same directory.

ZTF Help

- Double-clicking on the saved downloads should uncompress them, and then you should be off and running. However, some Windows users have reported having difficulty unzipping files downloaded from the SOFIA archive using the default application. We recommend using [7-zip](#) .


Job Monitor




















To explore the Job Monitor, click on the Job Monitor tab at the top of the screen:



Here is a well-populated job monitor list:

Job Summary Total: 6 Active: 1 Failed: 0

Notification Email By default, email notification is turned off. To toggle email notification for any given job in progress, click on the blue bell icon: 








| Title | Service ID char | Type char | Start Time | End Time | Phase char | Control |
|---------------------------------|--------------------|--------------|---------------------|---------------------|---------------|---|
| ZTF_deep_Files | IRSA | PACKAGE | 2025-06-06 00:04:41 | | EXECUTING |     |
| ZTF_deep_Files | IRSA | PACKAGE | 2025-06-06 00:04:22 | 2025-06-06 00:04:35 | COMPLETED |    |
| ZTF_ref_Files | IRSA | PACKAGE | 2025-06-06 00:04:11 | 2025-06-06 00:04:12 | COMPLETED |    |
| Spitzer-sphotdr4 (Polygon) | IRSA | SEARCH | 2025-06-06 00:03:57 | 2025-06-06 00:04:03 | COMPLETED |    |
| WISE-allwise_p3as_psd (Polygon) | IRSA | SEARCH | 2025-06-06 00:03:45 | 2025-06-06 00:03:49 | COMPLETED |    |
| ZTF_sci_Files | IRSA | PACKAGE | 2025-06-06 00:03:29 | 2025-06-06 00:03:37 | COMPLETED |    |


Note: The listed jobs are limited to your current session, where "session" may refer to your browser or archive, or account with which you're currently logged in. Jobs older than 14 days will not appear.

At the top, it summarizes (in this case) that there are 6 jobs, one of which is currently active, and none of which have failed. The email has been filled out, so that [email notification](#) can easily be toggled on (or off) with a single click.

Below that, there is a table, like [any other table in this tool](#) (with all the associated sorting and filtering capabilities), that lists all of the jobs that have been sent to the Job Monitor in this session, along with basic information like what time (in Universal Time) they were launched. Four of them in this screenshot are data packaging (type = package), one of which is still executing. Two other jobs were catalog searches (type = search).

On the far right is a collection of icons. The different icons do different things:

-  Usually this icon is animated -- the job is executing.
-  Display the results of this job in the tool -- usually this appears in reference to a catalog search, and the icon matches that in the "Results" tab, which is where the results will appear after you click on this icon.
-  Notification toggled on -- if an email is provided in the top of the Job Monitor, then email will be sent upon completion (see [below](#)).
-  Notification toggled off -- this is the default state.
-  Download the results of this job to your disk -- this could be a zip file, a data file (e.g., a FITS file), or a download script, depending on what data you are accessing.
-  Get more information about this job (see [below](#)).
-  Stop this job.

 Discard this job from this list.

Jobs accumulate in the Job Monitor over a given session, which could include more than one browser window accessing the same archive, because it relies on cookies being set. Jobs that are older than 2 weeks will not appear.

Tips and Troubleshooting

- **You** control where the file is saved on your disk through your browser; your browser may be configured to store all downloads in a particular location on your disk. Try looking in a "Downloads" directory, or for "recently modified files."
-

Sending Email

For large data packaging jobs, you may wish to have the system email you when it is done and ready for downloading.

In order to make this happen, you have to do two things.

1. Enter a valid email at the top of the Job Monitor page. (It should go without saying that if you don't enter a correct email, it can't do anything to fix that.)
2. Tell it that you want it to send you an email for the specific job in question. Click on the blue bell at any time before the job completes to toggle an email being sent to you upon completion.



This means don't send email



This means do send email

The reason it defaults to "don't send email" is so that you avoid spamming yourself - if you make a lot of requests, you most likely don't want it to send you a lot of emails in rapid succession.

If you ask it to email you for a download packaging request, you will be emailed links to obtain a curl or wget script, or a list of URLs that you can feed to your own code to get your data. See the [scripts section](#) for more details.

Tips and Troubleshooting


- By default, it will NOT send you email when it is complete, even if you have an email filled out. (This is to avoid accidentally spamming yourself!) Click on the blue bell at any time before the job completes to toggle an email being sent to you upon completion.
-


Scripts

If you [get an email from the Job Monitor](#), you will get a curl or wget script that you can execute on your computer to download the files you have requested, or you may choose to obtain just a list of URLs that you can feed to your own code to download the data. The scripts are designed to echo to the screen updates on what they are doing, so that you can track the download's progress.


To use these, save the script to a plain text file, and invoke the script. You may need to do something at the command line like "chmod +x script.sh" and then "./script.sh" to invoke it. You could also copy and paste the script lines individually into your terminal window.


ZTF Help

Generally speaking, the wget script is best for Linux and Unix users. The curl script is best for Mac users, because curl is part of the standard OS distribution; Mac users can also go retrieve and install [wget](#)  and then use the wget scripts.

Double-clicking on the downloaded zip files should uncompress them, and then you should be off and running. However, some Windows users have reported having difficulty unzipping files downloaded from the SOFIA archive using the default application. We recommend using [7-zip](#) .

Job Information

The information you get when you click on the i-in-a-circle  in the Job Monitor looks something like this:




The screenshot shows a 'Job Information' window with a close button (X) in the top right corner. The window displays the following details:

| | |
|---------------------------------------|------------------------------|
| Phase: COMPLETED | Job ID: c7-v5ccv_14688281924 |
| Created: 2025-06-06T00:04:41.925Z | Owner: |
| Start Time: 2025-06-06T00:04:41.947Z | Run time limit: 86400s |
| End Time: 2025-06-06T00:04:53.995Z | Actual run time: 12s |
| Planned end: | |
| Destruction: 2025-06-13T00:04:41.925Z | |

Below this is a 'Parameters' section with a collapse arrow (^). It contains the following text:


```
request: {"startIdx":0,"META_INFO":{"title":"Deep Reference Image, m16","Image selectionInfo: true--4  
cmd: packageRequest  
downloadRequest: {"startIdx":0,"FilePrefix":"Ztf_Files","SearchType":"deep","Ba
```

Next is a 'Results' section with a collapse arrow (^). It contains one result:

```
0:  https://irsatest.ipac.caltech.edu/applications/ztf/servlet/Download?log...
```


Finally, there is an 'Extra Information' section with a collapse arrow (^). It contains the following text:

```
userEmail: Guest  
userId: Guest  
title: ZTF_deep_Files
```

At the bottom right of the window is a help icon (question mark in a circle) .


It specifies things about the query, like when it was submitted and how long it took, but also the job ID (useful for helpdesk tickets), and the parameters you used (which you can copy using the ellipsis, just like for [table cells](#)), and also what information you provided -- username if you [logged in](#), [email](#) if you provided it, title if you provided it, and the URL that links directly to the job (also useful for helpdesk tickets; to copy it, click on the tiny clipboard icon).


Contents of your download - Quick Start

We strongly recommend reading the documentation at the [ZTF site](#)  to understand the contents of your download. However, very briefly, depending on what level you are downloading, and what files you select for packaging when you download your data, you can get:

- Science exposures:
 - ◆ log.txt
 - ◆ mskimg.fits
 - ◆ sciimg.fits
 - ◆ sciimlog.txt
 - ◆ sexcat.fits
 - Calibration frames:
 - ◆ *bias.fits
 - ◆ *hifreqflat.fits
 - Raw : *.fits
-

Acknowledging ZTF and IRSA

The main [ZTF page at IRSA](#)  has all the wording you need, plus the canonical papers to cite.

Different data sets may have different DOIs. This service you are using now, the Zwicky Transient Facility Image Service, has DOI [10.26131/IRSA539](#) .

Note that you can use the \facilities call in AASTeX to acknowledge IRSA as a facility you used in your journal article.

ZTF Image Service: API


Contents of page/chapter:

- +[Introduction](#)
- +[API Input Parameters](#)
- +[API Input Examples](#)

Introduction

You can construct calls to the ZTF Image Service in two ways.

- Open a browser with a search panel with coordinates and search parameters pre-filled
- Open a browser with search results

If you want to search for ZTF images or catalogs independent of this interface, please use the [general IRSA API tools](#) .

The **base URL** for this service is <https://irsa.ipac.caltech.edu/applications/wise/>

The **input parameters** are specified by *parameter=value* pairs, separated by ampersands (&).

Note that it is https, not http.

API Input Parameters

The input parameters are entered as standard HTTP "parameter=value" pairs in HTTP/GET syntax. In this syntax, the parameter name is followed by an equals sign which is then followed by a value. These pairs are separated from each other by ampersand (&) characters. No extra spaces are allowed, and if the value needs to contain any spaces or special characters that might cause ambiguities, these spaces have to be encoded as shown in any URL reference. In the rest of this section, we list the parameters. For examples, see later sections below.

| Parameter | Values | Default | Description |
|---------------------------------------|---|------------|---------------------|
| api (<i>required</i>) | searchPos, searchFieldid | (none) | ZTF search menu |
| worldPt or ra/dec (<i>required</i>) | worldPt format - lon;lat;Csys - eg: 1.0;2.3;EQ_J2000 or 5;4;GAL ra, dec format - ra=1&dec=2 - always j2000 | (none) | position for search |
| sr (<i>optional</i>) | sr format options: d or none - degrees, m - arcminutes, s - arcseconds sr=1.1d or sr=1.1 - 1.1 degrees sr=150s - 150 arcseconds sr=22m - 22 arcminutes | 30 arcsec | radius of search |
| imageSize (<i>optional</i>) | imageSize format options: d or none - degrees, m - arcminutes, s - arcseconds imageSize=1.1d or imageSize=1.1 - 1.1 degrees imageSize=150s - 150 arcseconds | 600 arcsec | returned image size |

| Parameter | Values | Default | Description |
|--------------------------------|------------------------------------|---------|---|
| | imageSize=22m - 22 arcminutes | | |
| dataproductlevel (optional) | "sci", "ref", "deep", "diff" | sci | ZTF data product level, separated by commas |
| intersect (optional) | CENTER, COVERS, ENCLOSED, OVERLAPS | CENTER | search region intersection type |
| fieldid (optional) | e.g., 792 | (none) | ZTF field ID |
| ccdid (optional) | e.g., 7;8;9 | (none) | ZTF CCD ID, separated by semicolons |
| execute (optional) | true or false | false | if true, execute the search and show the results. |

API Input Examples

The following examples can be run by clicking their links. All of them should have this prepended:

<https://irsa.ipac.caltech.edu/applications/ztf/>

1. [api=searchPos&WorldPt=83.773986;-5.418506;EQ_J2000&execute=false](https://irsa.ipac.caltech.edu/applications/ztf/?api=searchPos&WorldPt=83.773986;-5.418506;EQ_J2000&execute=false)
Open ZTF search panel with object coordinates pre-filled
2. [api=searchPos&ra=210.80227&dec=54.34895&sr=50s&intersect=OVERLAPS](https://irsa.ipac.caltech.edu/applications/ztf/?api=searchPos&ra=210.80227&dec=54.34895&sr=50s&intersect=OVERLAPS)
Open ZTF search panel with a particular object coordinates pre-filled, and set image search type: OVERLAPS, search size: 50 arcsec
3. [api=searchPos&WorldPt=10.68479292;41.269065;EQ_J2000;m31&imagesize=500s&dataproductlevel=sci,ref](https://irsa.ipac.caltech.edu/applications/ztf/?api=searchPos&WorldPt=10.68479292;41.269065;EQ_J2000;m31&imagesize=500s&dataproductlevel=sci,ref)
Return ZTF results from a fixed target search with specified cutout image size: 500 arcsec
4. [api=searchPos&ra=210.80227&dec=54.34895&sr=50s&intersect=OVERLAPS&fieldid=792&ccdid=7;8;9&execute=true](https://irsa.ipac.caltech.edu/applications/ztf/?api=searchPos&ra=210.80227&dec=54.34895&sr=50s&intersect=OVERLAPS&fieldid=792&ccdid=7;8;9&execute=true)
Open ZTF search panel with position coordinates, specific Field ID and ccd id, and set image search type: OVERLAPS, search size: 50 arcsec
5. [api=fieldidSearch&fieldid=792&ccdid=7;8;9&execute=false](https://irsa.ipac.caltech.edu/applications/ztf/?api=fieldidSearch&fieldid=792&ccdid=7;8;9&execute=false)
Open ZTF search panel with specific Field ID and ccd id

ZTF Image Service: User Registration for the IRSA Archives

There is one user registration for all IRSA applications, but data access, preferences, search history, data tagging, etc., are all unique to each archive.

While you certainly **do not have to register** to search the archive, download data, analyze data, and write a paper, you may wish to register.

On the other hand, *if you have access to the ZTF proprietary data, you will need to log in* so that the system grants you access to your data. If you got email from the ZTF project about account information, you may already have an account; otherwise you can set up an account (see below). Once you have set up an account, please contact the ZTF project so that we can tie your new account to your proprietary data.

Login

The "Login" link is in the far top right of the page.

Select this option to log in if you know your password, or to create a new account.

Create Account

Find this option by selecting "Login" in the far top right of the browser window, and then "Create an account" appears as an option in the lower left of the pop-up window.

Select this option to create a new account.

Forgot your Username or Password

If you do not remember your username or password, select this option to retrieve this lost information.

Find this option by selecting "Login" in the far top right of the browser page, and then "forgot your password?" appears as an option below the Login button.

Edit Profile

Find this option by logging in, and then clicking on your account name in the top right of the browser window. Then, select "Edit Profile" to change your password on an existing account.

Change Password

Find this option by logging in, and then clicking on your account name in the top right of the browser window. Then, select "Change Password" to change your password on an existing account.

Update Email

Find this option by logging in, and then clicking on your account name in the top right of the browser window. Then, select "Update Email" to change your email on an existing account.

ZTF Image Service: Frequently Asked Questions (FAQs)

I asked for difference images as part of my search and I'm not getting them in the download! Why?

If you asked for difference images to be returned as part of your search, then tried to download a difference image without changing the default download options, you will not get a difference image! If you want to download the difference image, you will need to explicitly select the difference image in the download options.

I've retrieved a catalog from the catalog tab (e.g., not a ZTF catalog). What are all these columns?

The columns that are returned are exactly those that are stored in the corresponding archive for that catalog. Each catalog is different. Please check the project's documentation for each catalog separately -- catalogs retrieved from IRSA have documentation that is available at IRSA, but you can also retrieve catalogs via the VO, so the documentation for those catalogs would be at the catalog's place of origin. Some of the more commonly used IRSA ones are:

◇ [2MASS](#) 


◇ [WISE](#) 

◇ [IRAS](#) 

I've created a nice image within the FITS viewer, and I have the stretch and overlays exactly the way that I want them. How do I save this?


The diskette icon in the toolbox enables you to save the image as a FITS file (no overlays), a ds9 region file (just the overlays), or a PNG file (a copy of what you are viewing, image with that stretch plus overlays).

What do I do with the zip files I get when I download data?



To uncompress the files you have downloaded, type "unzip foo.zip". To uncompress multiple files at once, type "unzip '*.zip'" (the single quotes are important), or "unzip *.zip" -- you just have to escape out the wildcard. If you have a Windows machine, try [7zip](#) .

How do I get more help?

The "Help" blue tab leads you into this online help, as does "ZTF Help" from under the "Help" in the IRSA menu on the top of the ZTF page. You can also download a PDF version of this manual; look at the top of the help window.

You can submit questions to the [IRSA Help Desk](#) .

How do I report a bug?

The known bugs and issues in this version of the ZTF Image Service are listed [here](#) . If you think you have found a bug, before reporting it, please check this list, and read this online ZTF Image Service help. It may be a "feature" we already know about. If you have found a new, real bug then please do contact us via the [IRSA Help Desk](#) . Please include your operating system version and your browser software and version. If you can, please also include any specific error message you may have gotten. (NB: In our testing, copying shortcuts worked on Windows and Linux; the command-C did not work on Macs, but selecting and clicking the right mouse button did.)

ZTF Image Service: Notice to Users -- Privacy Notice

The data contained in this archive are managed by the NASA/IPAC Infrared Science Archive (IRSA), which includes an archive of images, catalogs, and spectra from multiple telescopes and missions, managed by the Jet Propulsion Laboratory. This website is maintained by the Infrared Processing and Analysis Center (IPAC), located on the campus of the California Institute of Technology (Caltech).

The information you provide on a Caltech website will be used only for its intended purpose. We will protect your information consistent with the principles of the Privacy Act, the e-Government act of 2002, the Federal Records Act and, as applicable, the Freedom of Information Act. This notice is posted pursuant to the California Online Privacy Protection Act of 2003 (Cal Bus & Prof Code Sections 22575-22579).

Submitting information is strictly voluntary. By doing so, you are giving Caltech your permission to use the information for the intended purpose. In addition, Caltech may also furnish this information to NASA at NASA's request. If you do not want to give Caltech permission to use your information, simply do not provide it. However, not providing certain information may result in Caltech's inability to provide you with the information or services you desire.

Caltech never collects information for commercial marketing. We will only share your information with a government agency if it relates to that agency, or as otherwise required by law. Caltech/JPL never creates individual profiles or gives your information to any private organization.

We collect no personal information about you when you visit this Web site, unless otherwise stated or unless you choose to provide this information to us. However, we collect and store certain information automatically for use in site management and security purposes. What we collect and store automatically in terms of site statistics is:

- The Internet Protocol (IP) address for the domain from which you access the Internet (e.g., 123.456.789.012) whether the domain is yours individually or is provided as a proxy by your Internet Service Provider (ISP)
- The date and time you access our site
- The pages you access (recorded by the text and graphics files that compose that page)
- The Internet address of the website from which you linked directly to our site.

We use the summary statistics to help us make our site more useful to visitors, such as assessing what information is of most and least interest to visitors, and for other purposes such as determining the site's technical design specifications and identifying system performance or problem areas.

The website also collects and stores information about your search options, such as

- Name resolver choice (NED/Simbad)
- Page size (number of rows)
- Which search results (tabs) should be displayed
- Email address, if provided, for email notifications
- Search parameters so that you can resubmit your search via your search history
- Data tags, if you create one
- Plus, additional preferences that may be developed in the future, such as those tied to the visualization options.

ZTF Help

If you register as a user, these options will be kept in our database (along with your login ID and password via MD5 hash) and used for your session the next time you log in. If you do not register as a user, these options are set via cookies kept on your computer; if you clear your cookies and start a new session, these preferences are lost.

At no time is your private information, whether stored in persistent cookies or elsewhere, shared with third parties who have no right to that information. If you do not wish to have session or persistent cookies stored on your machine, you can turn them off in your browser. However, this may affect the functioning of the website on your computer.

IPAC will protect all such information consistent with applicable law.

Comments Sent by E-mail

You may choose to provide us with personal information, as in an e-mail containing your comments or questions. We use this information to improve our service to you or to respond to your request. There may be times when your message is forwarded, as e-mail, to other IPAC employees who may be better able to help you. We normally do not share our e-mail with any other outside organizations, unless determined necessary for security purposes or when required by law. Remember that email isn't necessarily secure. You should never send sensitive or personal information like your Social Security number in an email. Use postal mail or secure websites instead.

Security Notice IPAC is part of the Division of Physics, Mathematics and Astronomy at the California Institute of Technology ("Caltech"), and operates this website as part of a federally funded computer system used to accomplish Federal functions. Unauthorized attempts to defeat or circumvent security features, to use the system for other than its intended purposes, to deny service to authorized users, to access, obtain, alter, damage, or destroy information, or otherwise to interfere with the system or its operation is prohibited. Evidence of such acts may be disclosed to law enforcement authorities and may result in criminal prosecution under the Computer Fraud and Abuse Act of 1986 and the National Information Infrastructure Protection Act of 1996, codified at section 1030 of Title 18 of the United States Code, or other applicable criminal laws.

IPAC uses software programs to monitor this website for security purposes to ensure it remains available to all users and to protect information in the system. Any and all uses of this system and all files on this system may be intercepted, monitored, recorded, copied, audited, inspected, and disclosed to authorized Caltech, JPL, NASA, law enforcement personnel, as well as authorized officials of other agencies. By accessing this website, you are expressly consenting to such interception, monitoring, recording, copying, auditing, inspection and disclosure at the discretion of Caltech or NASA. Users have no explicit or implicit expectation of privacy.

Disclaimers

Disclaimer of Liability


With respect to documents available from this server, neither Caltech, nor the United States Government, nor any of their employees, makes any warranty, express or implied, including the warranties of merchantability and fitness for a particular purpose, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Disclaimer of Endorsement

ZTF Help

Reference herein to any specific commercial products, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by Caltech or the United States Government. The views and opinions of authors expressed herein do not necessarily state or reflect those of Caltech or the United States Government, and shall not be used for advertising or product endorsement purposes.

Copyright Status

For information on possible copyright infringement, please visit Caltech's "[Copyright Infringement](#) " page.